



Henry Gee Barnard 1839.)









CHEMICAL ESSAYS.

BY

R. WATSON, D.D. F.R.S.

AND REGIUS PROFESSOR OF DIVINITY IN THE UNIVERSITY OF CAMBRIDGE.

VOL. II.

CAMBRIDGE,

Printed by J. Archdeacon Printer to the UNIVERSITY;

For T. & J. Merrill, and J. Deighton, in Cambridge; P. Elmsley, and T. Cadell, in the Strand, J. Almon, in Piccadilly, J. Dodsley, Pall Mall, J. Robson, Bond-street, T. Payne & Son, Mews Gate, C. Dilly, in the Poultry, and T. Evans, in Paternoster Row, London,

MDCCLXXXI.



CONTENTS.

ESSAY	
I. Of the Composition and Analys	is of
Gunpowder. Pag	ge I
II. Of common Salt.	33
III. Of common Salt and Nitre as	Ma-
nures.	67
IV. Of the Saltness and Temperate	ire of
the Sea.	93
V. Of fresh Water procurable from	n Sea
Water, by Congelation, an	d by
Distillation.	141
VI. Of calcareous Earth, crude	and
calcined.	175
VII. Of Clay, Marle, and Gy	seous
Alabaster or Plaster-stone.	255
VIII. Of Pit-coal.	317

ESSAY

A TO THE DESTRUCTION OF THE PARTY OF THE PAR



ESSAY.I.

Of the composition and analysis of Gunpowder.

CUNPOWDER is an artificial composition, consisting of saltpetre, sulphur, and charcoal. The principal things to be respected in the making of gunpowder are, — the goodness of the ingredients; — the manner of mixing them; — the proportion in which they are to be combined; — and the drying of the powder after it is made.

VOL. II.

A

Salt-

Saltpetre in its crude state, whether it be brought from the East Indies, or made in Europe, is generally, if not universally, mixed with a greater or less portion of common falt: now a small portion of common falt, injures the goodness of a large quantity of gunpowder, hence it becomes necessary, in making gunpowder, to use the very finest saltpetre. -The purest sulphur, is that which is fold in the shops under the name of flowers of sulphur; but the roll sulphur, being much cheaper than the flowers of fulphur, and being also of a great degree of purity, it is the only fort which is used in the manufacturing of gunpowder. - With relation to the charcoal, it has been generally believed that the coal from foft and light woods, was better adapted to the

the making of gunpowder, than that from the hard and heavy ones; thus Evelyn fays of the hazel that "it made one of the best coals used for gunpowder, being very fine and light, till they found alder to be more fit *. And in another place he thinks that lime tree coal is still better than that from alder +. An eminent French chemist has shewn, from actual experiment, that this opinion in favour of coal from light woods is ill founded; he affirms that powder made from lime tree coal, or even from the coal of the pith of elder tree, is in no respect preferable to that made from the coal of the hardest woods, such as guaiacum and oak.

^{*} Evelyn's Silva by Dr. Hunter. p. 223. † Id. p. 946.

oak ‡. This remark, if it be confirmed by future experience, may be of use to the makers of gunpowder; as it is not always an easy matter for them, to procure a sufficient quantity of the coal of soft wood.

The mixture of the materials of which gunpowder is made, should be as intimate and as uniform as possible; for, in whatever manner the explosion may be accounted for, it is certain that the three ingredients are necessary to produce it. Saltpetre and fulphur mixed together give no explosion; fulphur and charcoal give no explosion; and though faltpetre and charcoal when intimately mixed, do give an explosion, vet it is, probably, of far less force than what is produced from a mixture

T Chym. par M. Baume Vol. I. p. 455.

ture of the three ingredients. I have faid, probably; because this point does not feem to be quite fettled at present, as may appear from the following opinions, of two eminent chemists, each of whom appeals to experience. - "Un mêlange de fix onces de nitre et d'une once de charbon produit une poudre qui a moitiè moins de force que toutes celles dans lesquelles on fait entrer du soufre: cette substance est donc absolument essentielle à la composition de la poudre. Dans le temps que je travaillois fur cette matiere, quelques particuliers proposerent de faire de la poudre sans soufre: ils promettoient qu' elle seroit plus forte, - La poudre dans laquelle on fait entrer une petite quantité de soufre, A 3 augaugmente de force du double" *. --"The principal ingredients of gunpowder, and those to which it owes its force, are nitre and charcoal; for these two ingredients, well mixed together, constitute gunpowder at least equal, if not superior in strength to common gunpowder (as I found by experience,) and may be feen in the Memoire of Count Saluce inferted in the Melanges de Philosophie et de Mathematiques, de l' Academie Royale de Turin. The fulphur seems to serve only for the purpose of setting fire to the mass with a less degree of heat"+. - If I may trust some crude experiments which I have made with a com-

* Chy. par M. Baume Vol. I. p. 461.

[†] Philos. Trans. 1779. p. 397, where the reader will find several ingenious experiments relative to the nature of gunpowder by Dr. Ingenhousz.

a common powder Trier, I must accede to the opinion of M. Baumè; as I repeatedly found that equal bulks of common powder, and of the fame fort of powder, freed from its fulphur by a gentle evaporation, differed very much both in the loudness and force of the explosion; the powder which had loft its fulphur being inferior to the other in both particulars. It is not without reason that equal bulks are here specified, for any definite measure of common powder, weighs more than the same measure of powder which has lost its fulphur; hence the refult of experiments made with equal weights of these powders, will be different from that which is derived from the explosion of equal bulks: may not this observation tend to reconcile the

A 4

opinions

opinions before mentioned? But whether fulphur be an absolutely necessary ingredient in the compofition of good gunpowder or not, it is certain, that an accurate mixture of the ingredients is essentially requifite. In order to accomplish this accurate mixture, the ingredients are previously reduced into coarse powders, and afterwards ground and pounded together, till the powder becomes exceeding fine; and when that is done the gunpowder is made. But as gunpowder, in the state of an impalpable dust, would be inconvenient in its use, it has been customary to reduce it into grains, by forcing it, when moistened with water, through fieves of various fizes.

The necessity of a complete mixture of the materials, in order to have

have good gunpowder, is fenfibly felt, in the use of such as has been dried, after having been accidentally wetted. There may be the same weight of the powder after it has been dried, that there was before it was wetted; but its strength is greatly diminished, on account of the mixture of the ingredients being less perfect. This diminution of strength proceeds from the water having diffolved a portion of the faltpetre, (the other two ingredients not being foluble in water) for upon drying the powder, the diffolved faltpetre will be crystallized in particles much larger than those were, which entered into the composition of the gunpowder, and thus the mixture will be less intimate and uniform, than it was before the wetting. This wetting

ting of gunpowder, is often occafioned by the mere moisture of the atmosphere. Great complaints were made concerning the badness of the gunpowder, used by the English in their engagement with the French fleet off Grenada, in July, 1779; the French having done much damage to the masts and rigging of the English, when the English shot would not reach them. When this matter was inquired into by the House of Commons, it appeared, that the powder had been injured by the moisture of the atmosphere; it had concreted into large lumps, in the middle of which the faltpetre was visible to the naked eye. If the wetting has been confiderable, the powder is rendered wholly unfit for use; but if no foreign fubstance has been mixed with

it except fresh water, it may be made into good gunpowder again, by being properly pounded and granulated. If the wetting has been occafioned by falt water, and that to any considerable degree, the sea salt, upon drying the powder, will remain mixed with it, and may fo far vitiate its quality, that it can never be used again in the form of gunpowder. However, as, by folution in water and fubsequent crystallization, the most valuable part of the gunpowder, namely, the faltpetre, may be extracted, and in its original purity, even from powder that has been wetted by sea water, or otherwise fpoiled, the faving of damaged powder, is a matter of national œconomy, and deservedly attended to in the Elaboratory at Woolwich.

The

The proportion in which the ingredients of gunpowder are combined together, are not the same in different nations, nor in different works of the fame nation, even for powder destined to the same use. It is difficult to obtain from the makers of gunpowder, any information upon this subject; their backwardness in this particular, arises not so much from any of them fancying themfelves possessed of the best possible proportion, as from an affectation of mystery, common to most manufacturers, and an apprehension of discovering to the world, that they do not use so much saltpetre as they ought to do, or as their competitors in trade really do use. Saltpetre is not only a much dearer commodity than either sulphur or charcoal, but

portion into the composition of gunpowder, than both these materials taken together: hence, there is a great temptation to lessen the quantity of the saltpetre, and to augment that of the other ingredients; and the fraud is not easily detected, since gunpowder, which will explode readily and loudly, may be made with very different quantities of saltpetre.

Baptista Porta died in the year 1515, he gives three different proportions for the making of gunpowder, according as it was required to be of different strength*. I have reduced his proportions, so that the reader may see the quantities of the several ingredients, contained in 100 pounds

Mag. Nat. L. XII. c. 3.

pounds weight of each fort of powder.

Saltpetre Sulphur Charcoal	Weak. 66 ² ₃ lb. 16 ² ₃ 16 ² ₃	Strong. 75 12½ 12½	Strongek. 80 10
	100	100	100

It is fomewhat remarkable, that, in all these proportions, the sulphur and charcoal are used in equal quantities. Cardan died about fixty years after Baptista Porta, and in that interval, the proportions of the ingredients of gunpowder, seem to have undergone a great change. Cardan's proportions for great, middle-sized, and small guns, are expressed in the following table *.

Salt-

^{*} Card. Oper. Vol. III. p. 379.

Sáltpetre Sulphur Charcoal	Gt. Guns. 50 lb. 16 ² / ₃ 33 ¹ / ₃	Mid.fized. 662/3 131/3 20	Small. 83 ¹ / ₃ 8 ¹ / ₃ 8 ¹ / ₃
	100	100	100

For great and middle-fized guns, we see a much greater proportion of charcoal than of sulphur, was used in Cardan's time; at present, I believe, it is in most places the reverse, or at least, the charcoal no where exceeds the sulphur. I have put down the proportions used at present in England, France, Sweden, Poland, and Italy, for the best kind of gunpowder.

Saltpetre Sulphur Charcoal	75	Fran. 75 9½ 15½	Swed. 75 16 9	Pol. 80	Italy. 76½ 12½ 12½
	100*	100	100‡	1001	1011+

Several experiments have been lately made in France, in order to determine the exact proportions of the feveral ingredients, which would produce the strongest possible powder; these proportions when reduced, as all the rest have been, to the quantity

* These are said to be the proportions of government powder.—Pemb. Chem. p. 207.

|| Chem. Dict. & Baume's Chem. Vol. I. p. 466.

† Mem. de Chem. Vol. II. p. 425. where it is faid, that two specimens of powder from Holland, gave only 71 lb. of faltpetre from 100. of powder.

† Comm. Scien. Bonon. Vol. IV. p. 113.

(17)

tity composing one hundred pounds of gunpowder, are

Saltpetre 80 lb.
Charcoal 15
Sulphur 5

From hence it would appear, that in a certain weight of faltpetre, the powder would produce the greatest effect, when the weight of the charcoal was to that of the sulphur, as 3 to 1. On the other hand, experiments are produced from which it is to be concluded, that in a certain weight of faltpetre the best powder is made, when the fulphur is to the charcoal, in the proportion of 2 to 1; From these different accounts, it feems as if the problem of deter-VOL. II. B mining mining the very best possible proportion was not yet solved.

In drying gunpowder after it is reduced into grains, there are two things to be avoided, too much and too little heat. If the heat is too great, a portion of the fulphur will be driven off, and thus the proportion of the ingredients being changed, the goodness of the powder, so far as it depends on that proportion, will be injured. In order to see what quantity of fulphur might be feparated from gunpowder, by a degree of heat not fufficient to explode it, I took 24 grains of the powder marked FF in the shops, and placing it on a piece of polished copper, I heated the copper by holding it over the flame of a candle; the gunpowder foon fent forth a strong sulphureous vapour;

vapour; and, when it had been dried fo long that no more fume or smell could be distinguished, the remainder weighed 19 grains, the loss amounting to 5 grains. The remainder did not explode by a spark like gunpowder, but like a mixture of faltpetre and charcoal, and it really was nothing elfe, all the fulphur having been distipated. Gunpowder was formerly dried by being exposed to the heat of the fun, and this method is still in use in France, and in some other countries; afterwards a way was invented of exposing it to a heat equal to that of boiling water; at present it is most generally in England, dried in stoves heated by great iron pots; with any tolerable caution no danger of explosion need be apprehended from this method. All B 2

the watery parts of the gunpowder may be evaporated by a degree of heat greatly less than that in which gunpowder explodes, that degree having been ascertained, by some late experiments, to be about the 600th degree on Fahrenheit's scale, in which the heat of boiling water is fixed at 212. There is more danger of evaporating a portion of the sulphur, in this way of drying gunpowder, than when it is dried by exposure to the sun.

The necessity of freeing gunpowder from all its moisture, is obvious from the following experiment, which was made some years ago before the Royal Society. A quantity of gunpowder was taken out of a barrel, and dried with a heat equal to that in which water boils; a piece of ordnance was charged

charged with a certain weight of this dried powder, and the distance to which it threw a ball was marked. The fame piece was charged with an equal weight of the same kind of powder, taken out of the same barrel, but not dried, and it threw an equal ball only to one half the distance. This effect of moisture is fo sensible, that some officers have affirmed, that they have seen barrels of gunpowder which was good in the morning, but which became (by attracting, probably, the humidity of the air) good for nothing in the evening *. In order to keep the powder dry, by preventing the access of the air.

^{* —} qu'il avoit vu, dans les guerres d' Italie, quelques barrils de poudre qui étoit bonne le matin, et qui ne valoit rien le soir. Hist. Nat. de l'Espagne, p. 82.

air, it has been proposed to line the barrels with tin foil, or with thin sheets of lead, after the manner in which tea boxes are lined †.—Would it not be possible to preserve powder free from moisture, and from the loss of a part of its sulphur in hot climates, by keeping it in glazed earthen bottles, or in bottles made of copper or tin, well corked?

This disposition to attract the humidity of the air, is different in different forts of powder, it is the least in that which is made from the purest saltpetre; pure saltpetre, which has been dried as gunpowder is dried, does not become heavier by exposure to the atmosphere; at least, its increase of weight is very small, not amounting, as far as my experiments

have

have informed me, to above one 72d part of its weight; I rather think that it does not acquire any increase of weight. But faltpetre mixed with fea falt, attracts the humidity very fenfibly, and hence, though there fhould be the same weight of saline matter in a certain weight of gunpowder, yet the goodness of the powder may be very variable, not only from the foreign saline matter, be it fea falt, or any other falt, injuring the quality of the powder as being an improper ingredient, but from its rendering the powder more liable to become humida

Saltpetre being the ingredient, in which there is the greatest room for fraud, in the composition of gunpowder, and on the quantity of which its strength chiefly depends, the rea-

der

der will excuse the minuteness of the following process, to ascertain the quantity of saltpetre contained in any specimen of gunpowder.

Take any quantity of gunpowder, pound it in a glass mortar till all the grains are broken, lay it before a gentle fire till it be quite dry, in that state weigh accurately any quantity of it, suppose 4 ounces; boil these four ounces in about a quart of water, the boiling need neither be violent nor long continued, for the water will readily dissolve all the faltpetre, or other faline matter, and not a particle of either the fulphur or the charcoal of the powder. In order to feparate the water containing the faltpetre, from the fulphur and charcoal, pour the whole into a filter made of brown paper; the water

con-

containing the faltpetre will run through the paper, and must be carefully preserved; the charcoal and fulphur will remain upon the paper. But as some particles of saltpetre will stick both to the filtering paper and to the mass of sulphur and charcoal, these are to be repeatedly washed, by pouring hot water upon them, till the water in running through the filter is quite infipid; then we may be certain, that we have all the faltpetre, originally contained in the powder, now disfolved in the water, and all the fulphur and charcoal remaining a mixed mass upon the filter. These respective quantities may be afcertained without much difficulty. The water containing the dissolved faltpetre, must be evaporated by a gentle heat; the faltpetre cannot be

evaporated by the same degree of heat which evaporates the water, all the faltpetre then contained in the gunpowder, will remain after the water is dispersed, and being carefully collected and weighed, it will shew the quantity of faline matter contained in the powder. Dry the mass of sulphur and charcoal, by laying the filtering paper containing it before the fire; it should be made as dry as the powder was before it was dissolved in the water: in that state weigh the faltpetre and charcoal; and; when the experiment has been accurately made, the weight of the faltpetre added to that of the mixture of fulphur and charcoal, will just amount to four ounces, the weight of the powder. The quantity of faline matter contained in any specimen of gungunpowder, being thus ascertained, its quality may be known by dissolving it in water, and crystallizing it; if any part of it crystallizes in little cubes, it is a sign that it contains sea salt; or if any part of it, after being duly evaporated, will not crystallize, it is a sign that it contains another fort of impurity, called by saltpetre makers, the mother of nitre, which powerfully attracts the humidity of the air.

The gunpowder marked FF, was analysed in the following manner. Twenty-four grains, by evaporating the sulphur, were reduced to nineteen; these nineteen grains gave, by solution in water and subsequent siltration and crystallization, sixteen grains of saltpetre, the charcoal, when properly dried, weighed three grains.

Ac-

According to these proportions, 100 pounds of this kind of gunpowder consisted of

Saltpetre $66\frac{2}{3}$ Sulphur $20\frac{5}{8}$ Charcoal $12\frac{1}{2}$ 100 lb.

I tried this gunpowder in two or three other ways, by taking larger quantities of it, but the quantity of faltpetre was always 66 lb. together with some fractional part of a pound, from 100 lb. of gunpowder. The powders marked with a fingle and a double F, differ in the fize of the grain, but they do not seem to differ, as far as I have tried them, in the quantity of the faltpetre they contain. From some forts of powder, I have got after the rate of 76 lb. of faltpetre, from 100lb. of the gunpowder. The

The method of analysing gunpowder, by evaporating the fulphur, is not wholly to be relied upon; I have often observed, that when mixtures of fulphur and charcoal have been exposed to evaporation, on a plate of heated copper, the remainder has weighed less than the charcoal which entered the composition, part of it having been carried off by the violent evaporation of the fulphur; and hence the proportion of fulphur in the above analysis is probably too great. I am aware that this observation is wholly opposite to the conclufion of M. Baumè, who contends, that one twenty fourth part of the weight of the fulphur employed in any mixture of fulphur and charcoal, adheres fo strongly to the charcoal, that it cannot be separated from it without burning the charcoal. -I can only fay, that he separated the fulphur by burning it, and I separated mine by fubliming it without fuffering it to take fire, and this difference in the manner of making the experiment, may, perhaps, be fufficient to account for the different refults. — But it is unnecessary to pursue this subject further, there are feveral things to be attended to in forming a complete analysis of gunpowder, which any person, tolerably well versed in chemistry, would certainly take notice of, if the analysis of any particular powder was required to be made, and which cannot in this general view be minutely described: and, indeed, it is the less necessary to enter into a detail on this subject, as the strength of the powder

powder is not much affected by small variations in the quantities of the fulphur and charcoal, which enter into its composition; and the method of ascertaining the quantity and quality of the saltpetre, in any particular gunpowder, has been sufficiently explained.

In order to judge with more certainty concerning the effect of sea salt, when mixed with saltpetre, in attracting the humidity of the air, I made the following experiment. Five parts of pure saltpetre in powder, were exposed for a month to a moist atmosphere, but I did not observe that the saltpetre had gained the least increase of weight; for the same length of time, and in the same place, I exposed four parts of saltpetre mixed

mixed with one of common falt, and this mixture had attracted fo much moisture, that it was in a state of fluidity.

ESSAY



ESSAY II.

Of common Salt.

OMMON falt is a neutral falt, it has neither an acid nor an alkaline taste, nor does it change the blue colour of vegetables into a red as acids do, nor into a green as alkalies do. It consists of two things, of an acid peculiar to itself, and of the alkali which is separable from the ashes of marsh samphire and other maritime plants, and which vol. II. C has

has been denominated the mineral or fossile fixed alkali. The fossile alkali, as was observed of the vegetable alkali, when the manner of decomposing saltpetre was explained, is more powerfully attracted by the acid of vitriol than by the acid of common falt; hence common falt is effectually decomposed when it is distilled in conjunction with the acid of vitriol, for this acid expels the acid of common falt from its union with the mineral alkali, and unites irself with it in its stead: the acid of common falt being thus difengaged from its basis, is easily, by the heat, raifed in vapour, and forced into the receiver. The acid of common falt, thus obtained, is very volatile, constantly emitting white fumes; and it is usually called the marine acid, the

the muriatic acid, Glauber's fuming acid or spirit of salt. If the reader pours a few drops of very strong acid of vitriol on a small portion of dry common falt, he will fee a white vapour arising from the falt, this vapour is the most volatile part of the acid of the falt, and a judgment may be formed of its pungency and volatility, from its presently infecting the air with its smell to a great extent. This acid vapour is a kind of air, for it retains its elasticity for fome time, not being readily condensable by cold. It has engaged the attention of Dr. Priestly; and with his accustomed ingenuity he has made several experiments, from which we learn, that this vapour when condensed, constitutes an acid which is twice as heavy as rain water, and that

C 2

the strongest acid of falt may be confidered as confifting of one third of this elastic vapour, and of two thirds of water*. After the extraction of the acid, which is one of the constituent parts of common falt, there remains, in the veffel used for the distillation, a compound mass, confisting of the acid of vitriol united with the mineral fixed alkali, the other constituent part of common salt: this is proved by diffolving the mass, and crystallizing it, for the crystals are precifely the same as would refult from a direct combination of the acid of vitriol with the mineral fixed alkali. The falt refulting from a decomposition of common salt by means of the acid of vitriol, or from a direct combination of that acid with

^{*} Philos. Trans. 1772. p. 239.

with the mineral alkali, is the genuine Glauber's salt. The artificial composition of common falt, confirms the account we have given of its constituent parts from its analysis, for if we combine the acid procured from distilling common salt and acid of vitriol together, with the mineral fixed alkali, there will refult from their union a falt, in all respects the fame as common falt, except that it will be fomewhat more pure than common falt; the falt thus produced is called regenerated falt.

Common falt is generally diffinguished by mineralogical writers into three different forts — fossile falt — spring falt — sea falt. In chemistry though we admit this division, as ferviceable in pointing out the three general sources from which common

falt

falt is most copiously derived, yet we reckon all these salts, when pure, to be of the same sort; they are all composed of the marine acid, and of the mineral fixed alkali.

Fossile or rock salt, is found in large beds in the bowels of the earth, in every quarter of the globe; it is sometimes crystallized, and as transparent as a diamond, and it has thence been called sal gemmæ; but it is more frequently found in irregular masses of a red, yellow, or blue colour. There are several mines of rock salt near Northwich in Cheshire; the first of which was discovered, as they were boring for coal, in the year 1670*.

The fprings which are met with, both above and below the level of the Northwich bed of rock falt, are ftrongly

^{*} Philof. Tranf. No. 66.

ftrongly impregnated with falt. This is easily accounted for; the rain water in finking through the ground which lies over the rock falt, at last arrives at the falt; its further descent is in a great measure obstructed by the folid body of falt, it rests upon it, and in resting upon the falt it disfolves it, and thus constitutes a brine fpring above the level of the bed of rock falt. The brine springs, which are found below that level, probably arise from the water, which has disfolved a portion of rock falt, in finking to that depth in the earth.

I have had the curiofity to go to the bottom of fome of the most famous mines in England; such as the copper mine at Ecton; the coal mines at Whitehaven, and Newcastle; the cannel coal mines in Lancashire; and

C 4

a variety of lead mines in Derbyshire, and other places; but I never thought my labour, in these subterraneous expeditions, fo well rewarded, as in the fight of the rock falt mines at Northwich. The falt mines at Wilizka near Cracow in Poland, have long been a subject of admiration, and every traveller has exerted his descriptive talents, in magnifying the stupendous wonders, which are there to be met with. These mines have been wrought above five hundred years, and from that circumstance we may readily imagine, the great number of vast caverns which have been formed, in confequence of the blocks of falt which have been annually extracted: yet it deserves to be remarked, that the Northwich rock falt mines are superior to those of Cracow, with respect to the quantity of salt, which is annually raised. The single pit, into which I descended at Northwich, yielded at a medium 4000 tons of salt in a year; this quantity is about two thirds of that which is raised every year in the Polish mines here spoken of *.

A great quantity of rock falt is used at Northwich, in order to strengthen their brine springs, and a much greater quantity is sent coastwise to Liverpool, and other places, where it is used either for strengthening brine springs or sea water; much of this rock salt was formerly exported to Holland, and it is still fent to Ireland for the same purpose. Rock salt, and the white salt which

is

^{*} See Memoire sur les Mines de Sel de Wieliczka en Pologne, in Hist. de l' Acad. des Scien. a Par. 1762.

is at Northwich, chiefly made from rock falt, is exported free from the falt duty; and I was informed, that the quantity, which is annually exported from Northwich, is fo great, that, if it paid the duty, it would bring in to government, a fum not much short of four hundred thousand pounds a year. "According to the best accounts I have been able to procure, the gross duty on falt made in South Britain, amounts annually to feven hundred thousand pounds *." The duty on falt made at Northwich is about seventy thousand pounds a year, or a tenth part of the whole duty 1.

The

^{*} Camp. Sur. of Brit. Vol. II. p. 26.

[‡] Since I received this information, an additional duty of 10 d. a bushel has been laid, in 1780, on falt. The whole duty now amounts

The Northwich rock falt is never used at our tables in its crude state; and its application to the pickling or curing of flesh or fish, or preserving any provisions, without its being previously refined into white falt, that is, without its being diffolved in water, and boiled down into what is called white falt, is prohibited under a penalty of 40s. for every pound of rock falt fo applied. The pure transparent masses, however, of rock falt, might, probably, be used by us with our food, without any fort of danger or incovenience; at least, we know that rock falt is fo used, without being refined, both in Poland and in Spain. In the last of these countries.

at

to 4s. 2 d. a bushel, the bushel weighing 56lb. The makers of salt can afford, in most places, to sell their salt, exclusive of duty, from 8 d. to 10 d. a bushel.

at Cardona in the province of Catalonia, there is a folid mountain of rock falt, between four and five hundred feet in height, and a league in circuit; its depth below the furface of the earth is not known *. prodigious mountain of falt, which has no mixture of other matter with it, is esteemed so singular an appearance, that it is thought to militate very much against the opinion of those, who would derive the origin of all the beds of rock falt, which are found under the furface of the earth, from the evaporation of falt water, left in fubterraneous caverns, either at the deluge, or upon some more local commotions of the globe.

The

^{*} Hist. Nat. de l'Espag. p. 406. See an account of similar mountains of rock salt in Shaw's Travels, p. 229. and in Pliny's Hist. Nat. 1. xxxi. c. 7.

The quantity of rock falt which may be dissolved in a definite quantity, suppose a pint or 16 avoirdupois ounces of water, is differently estimated by different authors. Boerhaave is of opinion, that 16 ounces of water will not dissolve quite 5 ounces of rock falt*; Spielmann thinks that they will dissolve $6\frac{2}{3}$ ounces +; Newmann agrees with Spielmann 1; Eller fays, that 7 ounces of fossile falt may be dissolved in 16 ounces of water §; lastly, Hoffmann assures us, that 16 ounces of water will not diffolve above 6 ounces of common falt ||. I have tried this matter with distilled and with common water, and

^{*} Chem. Vol. I. p. 476.

[†] Inst. Chem. p. 48.

¹ Newmann's Chem. by Lewis. p. 256.

Obf. Phy.-Chem. L. ii. Ob. xvi.

^{||} Ber. Mem. 1750.

and in various degrees of heat, and cannot but be of opinion, that Hoffmann's experiment approaches nearest to the truth; I never could disfolve quite 6 ounces of rock salt in 16 ounces of water. It is not wholly improbable, that different forts of rock salt, may differ somewhat with respect to their solubility in water.

If it be admitted, that 16 ounces of water can dissolve 6 ounces of salt and no more, then we may be certain, that no brine spring, in any part of the world, can yield 6 ounces of salt from a pint of the brine. For brine springs are, ordinarily, nothing but water in which fossile salt has been dissolved; but a pint of the strongest brine cannot contain so much salt, as is contained in a pint of water, which has been saturated

with

with 6 ounces of falt; for a pint of water, in which 6 ounces of falt have been dissolved, is increased a little in bulk, it will do more than fill a pint measure, and the salt left in the surplus will shew, how much the falt, contained in a pint of the strongest brine, falls short of 6 ounces. Or we may confider the matter in the following manner, which will, perhaps, be more intelligible; 16 ounces of water, impregnated with 6 ounces of falt, constitute a faturated brine, weighing 22 ounces; if therefore we would know how much falt is contained in 16 ounces of fuch brine, by the rule of proportion we may argue, that if 22 ounces of brine, contain 6 ounces of falt, 16 ounces of brine will contain 4 to ounces of falt. Hence we may infer, that the strongest

strongest brine springs will not yield much above one quarter of their weight of falt *.

Dr. Leigh, who first shewed the manner of refining rock falt, informs us, that some of the strongest springs at Northwich, gave seven or eight ounces of falt from a quart of brine; but a quart of brine weighs considerably more than 32 ounces, the weight of a quart of water; fo that the Northwich springs, from this ac-

count,

^{*} __ "Several pits at Northwich, and at Barton in Lancashire, contain no less than fix ounces of falt upon fixteen of brine; which is as large a proportion of falt as water will dissolve." Newm. Chem. p. 212. Lewis' note. The author here is fallen, probably, into a little mistake, by confounding a pound of water with a pound of brine; for if a pound or 16 ounces of water will only dissolve 6 ounces of falt, a pound of the brine, thus formed, will only hold 4-4 ounces of falt.

count, do not yield a quarter of their weight. At Middlewich there is faid to be one falt spring, which is stronger than the rest, this spring yields a full fourth part of falt *, and hence it is, probably, fully saturated. We have an account in Kircher's works, of some samous brine springs in Burgundy, from which we learn, that one hundred pounds weight of the strongest brine, gave 25 pounds, or just one fourth of its weight of white salt †.

There are a great many brine springs in Cheshire, Worcestershire, Staffordshire, Hampshire, and in other parts of Great Britain, some of which are sufficiently rich in salt to be wrought with profit, others not.

From

^{*} Philos. Trans. No. 53.

[†] Kirch. Mun. Sub. Tom. II. Cap. XI.

From what has been before advanced, the reader will readily comprehend, that 16 tons of the strongest brine confift of 12 tons of water, and of 4 tons of falt; and that, in order to obtain these 4 tons of falt, the 12 tons of water must be, by some means or other, evaporated, fo as to leave the falt in a concrete form. Suppose there should be a brine, which in 16 tons, should contain 15 tons of water, and only I ton of falt; yet it may chance, that fuch a weak brine may be wrought with more profit than the strongest; for the profit arising from the boiling of brine into falt, depends as much upon the price of the fuel used in boiling it, as upon the quantity of falt which it yields. Thus the fea water, which furrounds the coasts of Great Britain, is said to hold

hold feldom more than one thirtieth, or less than one fiftieth part of common salt; but fuel is so cheap at Newcastle, that they can evaporate thirty or forty tons of water, in order to obtain one ton of salt, and yet gain as much clear profit as those do, who, in counties less favourably situated for suel, boil down the strongest brine.

The advantage refulting from firengthening weak brine or fea water, by means of rock falt, is very obvious. Suppose that the fea water at Liverpool, where large quantities of rock falt are refined, would yield I ton of falt from 48 tons of water, then must a quantity of fuel sufficient to evaporate 47 tons of water be used, in order to obtain I ton of falt. But if as much rock falt be

D 2

Dut

put into the 48 tons of sea water, as can be dissolved in it, then will the sea water resemble a brine fully saturated, each 16 tons of which will give 4 tons of salt, and the whole quantity yielded by the evaporation of 47 tons of water, will be 12 tons of salt.

In warm climates, fuch as Italy, Spain, and the fouthern provinces of France, where the heat of their fummer is fufficient to exhale confiderable depths of water in a little time; they prepare large quantities of what is called bay falt at a very small expence. Their general method is to felect a marshy spot of ground, communicating by fluices with the fea, and fufficiently removed from fresh fprings, and the mouths of large rivers. In this ground they form ufually a

ufually three pits of small but different depths, and by clay and timber they secure them from leaking. The fea water is let into the first and deepest pit, from which it flows slowly, so as to give the mud and sand time to fettle, through the fecond, into the third, where it is foon inspissated by the heat of the sun into a strong brine. This brine being still further evaporated by the continued action of the sun, concretes into crystals of falt, which gradually fink to the bottom of the pit. When a proper quantity of it is formed, it is drawn out for use, and is of different colours, according to the colour of the clay employed in making the pits. In a favourable feafon, the French are faid to be able to make enough of bay falt in a fortnight, to

D 3

fup-

fupply their home confumption for a year, and the wants of the other nations, who purchase from them much more than is consumed in France*.

In this method of making bay falt, art has but copied nature; for we read in Pliny, Alonfo Barba, Shaw, and others, of large briny lakes, which are evaporated, in many parts of the world, to a perfect dryness in fummer time: when the inhabitants cut and carry away as much falt as they have occasion for. A remarkable lake of this kind was met with by Mr. Masson, in his botanical excursions from the Cape of Good Hope. " Zwart Kop's falt-pan, is a lake feveral

* See Dr. Brownrigg's Treatife on the Art of making common Salt, where the reader's curiofity on this subject will be abuncantly gratified.

veral miles diftant from the fea, and upon an eminence. In the rainy feafon it is filled with fresh water, which by the saltness of the ground, soon becomes strongly impregnated with saline particles; and when the summer's heat exhales the fresh water, the bottom of the lake is covered with a crust of pure salt, two or three feet thick. The lake is about three miles round, and surrounded by a rising ground *."

Though it appears, from what Dr? Brownrigg has faid upon this subject, that we might, with much advantage to our trade, imitate the French in their manner of procuring bay salt; yet most of our salt is prepared by boiling either the brine of salt springs, or sea water, into white

^{*} Philos. Trans. 1776. p. 297.

falt. In Hampshire, and some other counties, they have a method of heightening the sea water into a strong brine, by exposing it to the sun in large pits, much after the manner in which bay falt is made; and fo much of the sea water, is, by this means, naturally evaporated, that though they boil the remainder with Newcastle coal, yet they can afford their falt at a less price, than the Newcastle salt boilers can afford their's; though the fea water is, probably, equally impregnated with falt at both places.

The greatest difficulty which attends the making of bay salt in Great Britain, arises from the heat of our summer not being sufficiently strong, to evaporate a great quantity of sea water in a small portion of time. I

will

will mention an experiment or two, which suggested a hint, that may not, perhaps, be unserviceable to those who shall, in future, be disposed to attempt the making of bay falt.

I took a piece of coarfe linen cloth, its area was a fquare yard, and having thoroughly wetted it with water, but not fo much as to cause it to drip, I weighed it, and in that wet state exposed it to a warm sun in June, when there happened to be but little wind; it was not laid upon the ground, but held opposite to the fun, so that the air and fun had a free access to every part of it; it became nearly dry in an hour, and in that space of time it had lost eight ounces of its weight. - Upon another occasion, when there was a bright fun and a brifk wind.

wind, on an April day, a fimilar experiment was made; and the cloth lost after the rate of 6 ounces in one quarter of an hour; hence, if it had been kept constantly wetted, it would have lost in 16 hours 24 pounds; a pound of water is equal to a pint in measure, and therefore we may infer, that in a fummer day of 16 hours in length, 24 pints or 3 gallons of water may be dispersed into the air, by a warm fun and a brisk wind, from the furface of a linen cloth, equal to one square yard.

Now it is very possible, in any place where bay falt is made, to devise means of wetting and drying alternately any number of square yards of coarse cloth; one labourer, assisted by proper mechanical contrivances, might be equal to the daily manage-

ment

ment of a thousand yards, or more. By this plan, in favourable weather, there would be daily evaporated twenty-four thousand pounds of water, which, supposing sea water to contain one thirty-fecond part of its weight of falt, would give 750 pounds of falt. Those who have seen the artifice of strengthening brine, which is practised in Franche-Comtè, and other places, by making it drip through fagots, in order that the evaporation may be increased, by increafing the furface of the water which is exposed to the air, will not be furprifed at the method of evaporating water here hinted at.

Though the constituent parts of common salt, when free from all heterogeneous mixtures, are probably the same in every part of the world,

yet in the ordinary state in which it is met with, it is found to have very different qualities, and may properly enough be divided into different forts. Bay falt differs in some of its properties from the white falt, prepared by boiling brine or fea water; and both the bay falt and the boiled falt have, respectively, different qualities, according as they are prepared at different places. There are two general reasons of this diversity; one respects the manner of preparing the falt, the other respects the quality of the water from which the falt is prepared. When fea water or brine. is boiled into falt, a portion of the acid, which is one of the constituent parts of the falt, is difperfed; and a greater or less portion is dispersed, according as the falt has been formed with

with a greater or less degree of heat. We have an instance of this, both in bay falt when compared with boiled falt, and in the different forts of boiled falt, when compared with each other. Bay falt is prepared from sea water, by the mild heat of the fun, and it is generally esteemed much stronger than the white salt, which is prepared likewise from sea water by boiling the fea water. At Northwich, and in other places, they prepare from brine, not only the ordinary white falt, but a falt whose crystals are much larger than the ordinary falt, and which is usually called shivery falt. This shivery falt is esteemed stronger than the other, and it is formed by a milder heat; for in forming the ordinary falt, the brine is kept gently boiling; but in forming

forming the large grained shivery falt, they let the brine cool till they can bear to put their hands into it, and keeping it in that state, as near as may be, from Saturday night to Monday morning, the shivery falt is gradually formed. Sea water, brine fprings, and rock falt, generally contain, besides common salt, various other earthy and faline ingredients, fuch as the calcareous earth from which fish shells are probably formed; — the earth called magnefia; — Epsom salts, or the falt resulting from the combination of the acid of vitriol with magnefia; - Selenites, or the falt refulting from the combination of the acid of vitriol with the earth of the nature of fish shells; -Glauber's salt; — fixed alkali uncombined with any acid, &c. Sometimes


all these heterogeneous substances, and fometimes only a few of them are found in the waters from which common falt is prepared; they are all of them foreign to the nature of the falt, and injure its quality; and hence we may, without difficulty, comprehend that common falt may have very different properties, according to the quality of the water from which it is made, or the skill of the falt-maker exerted in separating these mixtures from it. The Dutch have long been famous for preparing a falt for the pickling of herrings, by which they have acquired a superiority in that article of commerce over all other European nations. Their principal fecret in this business consists in evaporating the brine made from the folution

of bay falt with the gentlest fire, and in mixing with the brine a proper quantity of very four whey; the acid whey unites itself with the uncombined fixed alkali before mentioned, and thus prevents it from adhering to the common falt as it crystallizes. Any other mild acid might probably answer the same purpose. This acid whey is called azy: les Hollandois se servent de l'azy dans le travail en grand pour raffiner nos sels de mer, et pour en rendre la cristallisation parfaite; c'est par cet artifice qu'ils font depuis long-temps, en possession de fournir les meilleures salaisons de l'Europe *.

^{*} Hist. de l'Acad. des Scien. 1762. Dr. Brownrigg had mentioned this secret of the Dutch above 30 years ago, in his excellent treatise before referred to. The reader will meet

meet with an accurate examination of the various ingredients with which common falt, and the waters from which it is made are impregnated in Baumè's Chem. vol. iii. p. 512.

VOL. II. E ESSAY





ESSAY III.

Of common Salt and Nitre as Manures.

ages of the world, was so far from being held in any estimation as a manure, that it was looked upon as a symbol of extreme sterility. Long before the commencement of profane history, Abimelech took the city Shechem, and slew the people that was therein, and beat down the city, and sowed it with salt *; intimating thereby

Judges ix. 45.

by his wish that it might remain unfruitful and uninhabited for ever.

It does not appear from history, what circumstance gave rise to this custom, nor whether Abimelech was the first person who introduced it; but it has prevailed very generally among mankind even to the prefent age, it being still usual to raze the houses of rebels and traitors, and to fprinkle the ground upon which they stood with falt. Perhaps this general symbolical use of salt, might be derived from what had happened when Sodom was destroyed, and the falt sea was formed. This conjecture is, in some measure, supported by observing, that the severest denunciations of divine vengeance are frequently expressed by an allufion to that event. - Moab shall be as

Sodom.

Sodom, and the children of Ammon as Gomorrah, even the breeding of nettles, and falt pits, and a perpetual defolation*. The whole land thereof is brimfone, and falt, and burning, that it is not fown, nor any grass groweth therein like the overthrow of Sodom +.

Virgil reprobates a falt foil as occasioning the degeneration of fruit trees, and admitting no melioration from ploughing.

Salt earth and bitter are not fit to fow,

Nor will be tam'd or mended with the plough.

Sweet grapes degen'rate there, and fruitsdeclin'd

From their first flav'rous taste renounce. their kind ‡.

Pliny,

^{*} Zephaniah ii. 9.

⁺ Deuteron. xxix. 23.

[‡] Virgil's Georg. 1. 2. Dryd.

Pliny, though he recommends the giving of falt to cattle, yet in speaking of fossile salt, he expressly affirms, that every place in which it is found, is barren and unfit for vegetation *.

Notwithstanding these and other testimonies of the ancients concerning the sterilizing quality of common falt, yet it is frequently used as a manure with great fuccess. It has been the custom, ever fince the time of Henry the Third at least, for the farmers on the Cornish coast, to manure their lands with sea sand, in which fea falt is fo copiously mixed, that in many places it used to be extracted from a lye made of fand. When the fand has been long exposed to the air, it proves less useful and

^{*} Hist. Nat. L. xxxi. c. 7.

and enriching, which is by fome attributed to its having been deprived of a good part of its falt, by the dews and rains *. It may be observed, that this fand is of two kinds, shelfy and shelly; the shelfy is produced from the grating of stones one against another, by the constant wash of the fea, and is of little value; its quality, however, will be different in different countries, according to the nature of the stones exposed to the agitation of the sea; if the stones happen to be of the limestone kind, even the shelfy fand may be very serviceable; if the stones principally consist of flint, as at Yarmouth, and other parts of the Norfolk coast, the fand will differ very little from powdered flints. The shelly fand in Cornwal,

is

^{*} Campden's Britan. Cornw.

is produced by the fame fluctuation of the sea, as the slinty sand in Norfolk, it consists of the broken shells of muscles, cockles, oysters, scollops, and other fish. This fand varies fomewhat in colour and in grain, according to the substances from which it is formed, and the degree of agitation it has been exposed to, and it is found to fertilize almost all kinds of foils *. This practice of manuring lands with sea fand, has, within these few years, been introduced with great fuccess in other parts of Great Britain.

The Cheshire farmers purchase no inconsiderable quantity of refuse salt from the salt boilers; they mix it with dung, and it makes an excellent manure. This refuse salt costs them eight

^{*} Philof. Tranf. No. 113.

eight pence a bushel, there being a duty of four pence a bushel imposed on it. When the demand for this refuse falt is very great, the falt boilers have a custom to mix a quantity of foot, or other impurity, with the ordinary falt, and it then comes under the denomination of refuse falt; there were fold a few years ago, at Northwich alone, near 3000 tons of it in one year, for the use of the farmers in that and other counties. On the other hand, when the foil abounds with rushes and weeds, it is customary in Cheshire, to lay a quantity of rock falt upon it, as it is found utterly to destroy every vegetable. Hence it should seem, that falt, when used in fmall quantities, is a good manure, and when in large ones a real poison to vegetables. Some of the African and Arabian

Arabian deferts, are thought to be barren by their having too much falt in them; whilst many parts of . Barbary, are reckoned to be peculiarly fruitful, from their containing a less quantity of it *.

Sir John Pringle has observed, that common falt, when used in small quantities, as one ounce to twelve, accelerates the putrefaction of animal fubstances, when in larger it retards it; and hence he deduces its utility, in affifting the organs of digestion in man, and, perhaps, in other carnivorous animals +. The fame observation may be extended to graminivorous animals, they are all exceedingly fond of falt, probably

from

^{*} Brownrigg on Salt, p. 159.

⁺ Observ. on the Diseases of the Army, by Sir J. Pringle, Append. xxxix.

from its great tendency to corrupt the aliment, and to render thereby its discharge from the stomach into the intestines, more easy and expeditious.

In like manner falt, when applied as a manure, in small quantities, is found to be very beneficial; not probably from its entering as an aliment into the substance of vegetables, since there are many experiments tending to prove that no kind of falt can of itself become the food of plants*,

Wallerius expressly says—Les sels de quelle espece qu'ils soient, ne peuvent pas servir de nourriture aux plants, ni avancer par eux-memes la vegetation, and after quoting the experiments of Krastius, Alston, and Bonnet,

on the subject, and examining the arguments on the opposite side of the question, he concludes the inquiry in the following

words:

but from its efficacy in reducing weeds, dried herbage, dead roots, &c. into a putrid oily mass; the fructifying virtue of oily composts being now generally acknowledged: but when it is used in a larger proportion, by preserving these matters from corruption, and drying up or hardening the sibrous capillaries of the roots, so that they become unfit for sucking in nutriment, the ferti-

words:—D'ou nous concluons que les sels minéraux, ni les sels étrangeres, ni les terres minérales, ne contribuent point a la nourriture des végétaux. Elemens d'Agriculture traduits du Latin de M. Wallerius. Yverden, 1766, p. 134, &c. or an English translation of the same work, by John Mills, Esq; F. R. S. London, 1770. See also the Principles of Agriculture and Vegetation by Dr. Home; and the Elements of Agriculture by Dr. G. Fordyce.

lity of the ground is diminished, or wholly destroyed.

As to the fertility of lands overflowed by fea water, it may be in part owing to the slime and mud left by it, and partly to the falt contained in it, which, being in a small quantity, may contribute to the putrefaction of the effete vegetable roots, and the consequent production of an oily compost.

With respect to nitre as a manure, it is an opinion entertained by farmers, that fnow fertilizes the lands upon which it falls, more than rain, in consequence of the nitrous salts which it is supposed to acquire by freezing. False philosophy first gave rise to this idea*, and poetry has

con-

^{*} Gassend. Phys. sec. iii. 1. 11. The exiftence

contributed to spread the general error.

— Oh! may'ft thou often fee

Thy furrows whitened by the woolly rain
Nutritious, fecret nitre lurks within
The porous wet, quick'ning the languid
globe.

PHILIPS.

What art thou frost?—
Is not thy potent energy, unseen
Myriads of little falts, or hook'd or shap'd
Like double wedges, and diffused immense
Thro' water, earth, and ether.

THOMPSON.

The

istence of nitre in snow, and the fertilizing quality of salts were so generally admitted in the last century, that philosophers seem to have been at no pains to prove either of them,—On sait que la neige contient beaucoup de parties nitreuses, et que les sels contribuent beaucoup à la secondité des terres. Actes de Copenhague, Collect. Acad. vol. vi. p. 195.

The ancients were acquainted with the fertilizing quality of fnow, and though they did not very intelligibly explain its mode of operation in promoting vegetation, yet it is remarkable, that the supposition of saline corpuscles made no part of their illustration of that matter*. It is not here intended to deny the fertilizing virtue of fnow, but to shew that it probably does not proceed from the nitre contained in it; in fupport of this opinion, I will mention two of the most accurate experiments, which have probably ever been made on the subject.

Marggraf, in the year 1751, collected in the suburbs of Berlin as much snow as, when melted, afforded him one hundred measures of

water,

^{*} Plin. Hist. Nat. 1. xvii. c. 2.

water, each measure containing thirty fix ounces *. He collected the fnow in an open fituation, in clean glass vessels, after the atmosphere was purified, by its having fnowed fome time; in short, he used every possible precaution to procure the fnow free from every extraneous impurity. The nitrous, or other falts contained in the fnow as it fell upon the ground were, no doubt, disfolved in the water after the fnow was melted; and, in order to afcertain their quantity and quality, nothing more was requisite than to dissipate by evaporation or distillation, the water in which they were diffolved. From these hundred measures of snow water he obtained, by distilling it with every suitable attention, 60 grains, not

[·] Opuf. Chy. vol. ii.

not of nitre, but of calcareous earth, together with some grains, he does not mention the exact number, of the acid of sea salt, impregnated with a nitrous vapour.

The same quantity of rain water, collected in the winter months with equal precaution, and distilled with equal attention, yielded 100 grains, not of nitre, but of calcareous earth, with some grains of the acids of nitre and sea salt*.

The

* Toute la difference donc entre l'eau de pluie et l'eau de neige n'est d'aucune importance, et se reduit à ce que l'acide de l'eau de pluie est plus nitreux, et qu'elle renferme plus de terre calcaire, au lieu que l'eau de neige a plutôt un acide marin que nitreux, et contient une moindre quantité de terre calcaire. Opuscules Chymique, vol. ii. p. 21.

VOL. II.

The author infers from these experiments, that the chemical difference between rain and snow water is exceedingly small; but that the latter, however, is somewhat less nitrous, and contains a somewhat less proportion of earth than the former. But neither of them contain either earth or any kind of salt in any quantity, which can be sensibly efficacious in promoting vegetation.

Suppose an acre of land to be, at any one time, covered with snow to the depth of six inches; and that this snow would, when melted, be reduced in magnitude a fixth part, or that it would cover the land with water to the depth of one inch; then might it be made appear, by a very easy calculation, that allowing 60 grains of calcareous earth to every 28 gallons

28 gallons and one pint of water, according to the proportion of the foregoing analysis, the whole of the earth left upon the acre from the evaporation of the snow water, would not amount to ten pounds in weight; nor the faline part to above a few ounces. Now it is very improbable, that four or five ounces of any kind of falt, when spread over an acre, should produce any sensible effect in fertilizing the ground. And if we suppose the land to be so often covered with fnow in the course of a year, that the falt left upon it would amount even to a pound, yet the difficulty would still recur, fince even a pound of falt reduced to an uniform pellicle, and spread over an acre of land, would not much exceed in thickness, the four hundred thousandth F 2

if it should be admitted that nitre is a fertilizer of land, which many are, upon good grounds, disposed utterly to deny, yet so very small is the quantity of it contained in snow, that it cannot be supposed to promote the vegetation of plants upon which the snow has fallen.

The peculiar agency of snow as a fertilizer, in preference to rain may admit of a very rational explanation, without having recourse to any nitrous salts, which it has been supposed to contain. There are two causes constantly acting upon the surface of the earth, one of which is, generally speaking, uniform in its strength with respect to the production of heat; the other is variable. The internal substance of the earth

is heated uniformly, by some principle or other which we do not well understand, to the 48th degree of Fahrenheit's thermometer; this degree of heat is greater than that in which the watery juices of vegetables freeze, and it is propagated from the inward parts of the earth to the furface, on which the vegetables grow. The atmosphere being variably heated, by the variable action of the fun in different climates, and in the same climate at different seafons, communicates to the furface of the earth, and to some distance below it, the degree of heat or cold which prevails in itself. Different vegetables are able to preserve life under different degrees of cold, but all of them perish, when the cold which reaches their roots is extreme. Provi-

dence,

dence, in the coldest climates, has provided a covering for the roots of vegetables, by which they are protected from the influence of the atmospherical cold; that covering is snow. Even in our climate we often fee shrubs, and other small vegetables, killed by the feverity of a frost, when it is unaccompanied with fnow, which, had there been eight inches, or a foot of fnow upon the ground, would have remained unhurt. The fnow keeps in the internal heat of the earth, and it does not permit the cold of the atmosphere to penetrate through its substance, and on both these accounts it keeps the roots of the vegetables, comparatively fpeaking, warm; a kind of vegetation is carried on under its surface, which shews itself by the very rapid increase which

which plants of all kinds acquire in cold countries, as foon as the covering of fnow is removed by the approach of fpring. Those who are fond of making oil the food of plants, may derive part of the utility of fnow in fertilizing the earth from the oily particles which it contains; for not only the residue which was obtained from the distillation of snow water, had a brown colour proceeding from fome oily particles, but it is very commonly observed that fnow, as it thaws, becomes dirty; and this dirty appearance is probably enough referred to some particles of an oily or mucilaginous fubstance contained in it. Snow, moreover, in melting, moistens and pulverizes the foil, which had been bound up F 4

by

by the frost; and as its water has a tendency to putrefaction, it seems, on many accounts, without admitting it to contain any nitre, to be admirably sitted to promote vegetation.

In confirmation of the analyses of rain and fnow water which were made by Marggraf, I will here add those which we owe to the accurate industry of Dr. Rutty*. -- He evaporated fix different specimens of the purest rain water he could procure, and found that a gallon of the purest yielded 6 grains, and a gallon of the most impure 12 grains of a fubstance, for the most part, of a dark brown colour, and a bitter, brackish taste. From a gallon of fnow water, he obtained 4 grains of a brownish residue, which consisted partly

^{*} Rutty's Synop.

partly of sea salt, partly of an absorbent earth, and a small portion of oil.

It may be observed from these experiments, compared with those of Marggraf, that the proportion between the folid impurities of rain and fnow water, is much the fame, in parts of the globe as far diftant from each other as Ireland and Prussia. Dr. Rutty's experiments were made in Dublin; a gallon of the purest rain water gave him 6 grains, the fame quantity of the purest snow water gave him 4 grains of heterogeneous matter; now the proportion of 6 to 4, is not very different from that of 100 to 60, which expresses the proportional quantities of the residues left, from the evaporation of rain and snow water, water, according to the experiments of Marggraf.

No two authors perfectly agree, in ascertaining the quantity of solid impurity, contained in a definite portion of either rain or fnow water; this is not to be wholly attributed to the difference of their care and skill exerted in the analysis of them, but principally to the different natures of the subjects themselves, upon which their labours have been employed. The vapours which are daily raised from the sea, may, with great probability, be supposed to carry with them fome minute portions of the acid of fea falt, and, perhaps, of fea falt in substance, and of the calcareous earth, with which the fea abounds. The atmosphere itself may be looked upon, not only as the general receptacle

ceptacle of these aqueous vapours, but likewise of all mineral exhalations; of the steams, which are constantly arising from the perspiration of whatever enjoys animal or vegetable life; and from the instantaneous putrescence of those substances, when deprived of life; of the smaller seeds of terrestrial and aquatic plants; of the eggs of an infinity of species of imperceptible animalcules; of the acids and oils separated by combustion from all forts of fuel; of the matter of elight; of electric effluviums; and of a variety of other substances, which are elevated, and, for a time, kept fuspended, by natural and accidental causes: from these fources are derived, those various impurities, which have been discovered in all atmospherical water; and which which we can readily apprehend, must be different in quality and quantity, according to the nature of the heterogeneous substances, subsisting in that portion of the atmosphere, through which the aqueous vapours have ascended, or which they have washed in their descent; that is, in general, according to the nature of the climate, the season of the year, the direction of the winds, and the preceding temperature of the weather.



ESSAY IV.

Of the Saltness and Temperature of the Sea.

THERE are few questions, respecting the natural history of our globe, which have been discussed with more attention, or decided with less satisfaction, than that concerning the primary cause of the saltness of the sea. The solution of it had perplexed the philosophers before the time of Aristotle*, it surpassed

* Arist. Meteo. L. ii. c. iii.

passed his own great genius; and those of his followers, who have attempted to support his arguments, have been betrayed into very ill-grounded conclusions concerning it. Father Kircher*, after having confulted three and thirty authors upon the subject, could not help remarking, that the sluctuations of the ocean itself were scarcely more various, than the opinions of men concerning the origin of its saline impregnation.

The question does not seem capable of admitting an illustration from experiment; at least, no experiments have hitherto been made for that purpose, and therefore we may be the less surprised at its remaining, nearly as problematical in the present age, as it has been in any of the preceding.

^{*} Kirch. Mun. Subter. L. iii. c. iii.

ceding. Had there, indeed, any obfervations been made, three or four centuries ago, ascertaining the then faltness of the sea, at any particular time and place; we might, by making, at present, similar observations at the same place, in the same season, have been able to know, whether the faltness at that particular place, was an increasing, or a decreasing, or an invariable quantity; and this kind and degree of knowledge, would have ferved as a clue to direct us to a full investigation of this matter in general; but it is to be regretted, that no fuch observations have, till very tately, been made with any tolerable precision. - There are three principal opinions on this subject, which have been maintained by philosophers of modern date.

Some

Some * observing that river water, almost in every part of the globe, is, in a greater or less degree, impregnated with fea falt, have thought that the fea has gradually acquired its present quantity of falt from the long continued influx of rivers. The water, which is carried into the fea by the rivers, is again separated from it by evaporation, and being dispersed over the atmosphere by the winds, it foon descends in rain or vapour upon the furface of the earth; from whence it hastens to pour into the bosom of the ocean, the fresh tribute of falt, which it has collected in its inland progress. Thus the falt conveyed into the fea, not being a volatile substance, nor performing an incessant circulation, like the wa-

ter

^{*} Halley, Philof. Trans. No. 344.

ter which carries it thither, must be a perpetually increasing quantity, and time enough, it is contended, has elapsed since the creation, for the sea to acquire from this source its present quantity of salt.

The principle upon which this opinion is founded, cannot become the subject of accurate calculation; rivers may have formerly carried more or less falt into the sea, than they do at present; and the quantities, contained at present in different rivers, are fo various, that any general position, with respect to the proportion of falt observable in river water, will be liable to many exceptions from particular cases. It may appear probable, however, from the following observation, that the cause here affigned of the faltness of the G VOL. II. fea,

fea, is not adequate to the effect. Sea water, at a medium taken from observations made in different climates, may be supposed, without any great apprehension of error, to contain about one thirtieth of its weight of common falt; but all the rivers in the world could not have conveyed into the fea one five hundredth part of the weight of the fea, though we suppose that they have daily, ever fince the creation, carried into the sea and left there, the fame quantity of falt, which they do at present daily deposit in it. In order to make this out, with any appearance of perspicuity and precision, we will take for granted, what fome eminent philosophers have endeavoured to prove, - "that all the rivers in the world flowing into the bed

bed of the sea, with a continuance of their present stores, would take up at least eight hundred years to fill it to its present height *;" - this being premifed, let us suppose the ocean to have been originally quite fresh, and to have daily lost by evaporation as much water, as it daily received from the influx of the rivers, then must eight hundred years have passed before the fresh water of the ocean could have been changed into river water, or acquired that proportion of falt with which river water is impregnated. River water may, in general, be supposed to contain one four thousandth part of its weight of sea falt; some rivers, doubtless, contain more,

^{*} Goldsmith's Hist. of the Earth, &c. Vol. I. p. 228. Buffon, Hist. Nat. Vol. I. p. 356.

more, others less, but the quantity here affumed feems to be great enough; fince even the Thames* water taken up near Billingsgate, impregnated, as it may be supposed to be, with fea falt, from the quantity of it used in London, and washed into it by various drains, does not contain one half fo much; the ocean upon this hypothesis, at the expiration of eight hundred years from the creation, would have contained one four thousandth part of its weight of fea falt; and at the expiration of eight times eight hundred years, it would have contained eight four thousandth parts, or one five hundredth part of its weight of falt, but eight times eight hundred years carry

us

^{*} See an ingenious Inquiry into the Nature of Water, by Dr. Rotherham, p. 114.

us back to an æra antecedent to the creation of the world.

Other philosophers *, observing that large beds of fossile salt are not unfrequent in any quarter of the globe; and conceiving, with great probability, the bottom of the fea to be analogous in its formation to the furface of the earth, have undertaken to derive its faltness from the beds of rock falt, which they have supposed to be situated at its bottom; and they are further of opinion, that without fuch a permanent saline principle, the sea would long fince have become infipid from the fresh water poured into it by an infinity of rivers. Strange! that what

^{*} Mem. de l'Acad. des Scien, de Ber. Ann. 1760.

what according to the forementioned hypothesis was thought sufficient to account for the saltness of the sea, should in this be esteemed instrumental in annihilating the saltness already supposed to exist.

This opinion is liable to an objection of some weight; for it may reasonably be inquired, why the waters of the ocean are not perfectly faturated with falt, if they have ever fince the creation been exerting their diffolving powers, upon fuch permanent masses of rock salt as are thought to be fituated at its bottom. Were the waters of the ocean in a quiescent state, and every where of two or three miles in depth, as they are conjectured to be in some, it would not be an easy matter to define the time in which the waters at

the

the furface would become fapid, much less in which they would become faturated, though the whole bottom of the ocean was covered with a stratum of rock falt. The water contiguous to the falt would faturate itself therewith, and being thereby rendered heavier than the fuperficial water, it would not readily mix itself with it; but though the lower parts of the fea have been obferved by divers, to remain in a very tranquil state, when the upper have been much agitated by storms; yet it may reasonably be supposed, that they are fufficiently moved, to cause, in a sufficient length of time, an uniform diffusion of the rock salt, they may be supposed to have diffolved. The patrons of this opinion found their reasoning upon a mistake;

G 4 they

they think, that if there were no mines of rock falt in the bed of the ocean, its waters would have been long ago converted into fresh water, by the rivers discharged into it. Now this is an erroneous principle; for supposing that the rivers themfelves contained no falt, and that they returned into the fea, in any given time, the same quantity of water, which in the same time is raifed from it by evaporation, the faltness would remain precisely the fame for ever. But neither of these suppositions is true, for the rivers do convey into the ocean some portion of falt every day, and they do not, in any given time, return into the ocean so much water as in the fame time is separated from it; and upon both these accounts, the faltnefs

ness of the sea, so far from being diminished, ought constantly to be increased, from the rivers poured into it.

Boyle * unites, as it were, the two preceding hypotheses, and "takes the faltness of the sea to be supplied, not only from rocks and other maffes of falt, which at the beginning were, or in some countries may yet be found, either at the bottom of the fea, or at the fides, where the water can reach them; but also from the falt which the rivers, rains, and other waters dissolve in their passage through divers parts of the earth, and at length carry with them into the fea." Buffon +, and the generality

^{*} Boyle's Works, Vol. III. p. 381. † Hist. Nat. Vol. I. p. 361. Goldsmith's Hist. of the Earth, Vol. I. p. 234.

rality of philosophers, acquiesce in the opinion of Boyle.

After all, it may be observed, that we are inquiring into the cause of a phenomenon, which it may be faid had no fecondary cause at all. It is taken for granted in this disquisition, that the water which covered the globe in its chaotic state, was not impregnated with falt as at prefent, but quite fresh; now this is an opinion concerning a matter of fact, which can never be proved either way; and furely we extend our fpeculations very far, when we attempt to explain a phenomenon, primeval to, or coeval with, the formation of the earth.

Bernardine Gomesius*, about two hundred years ago, published an ingenious

Gomes de Sale. 1. i. c. 24.

genious treatife upon falt; in this treatife, after reciting, and refuting, the opinions of Empedocles, Anaxagoras, and Aristotle, upon the subject in question, he proposes his own; wherein he maintains that the fea was originally created in the fame state in which we at present find it, and impregnated from the very first with the falt which it contains. Though this hypothesis may be confidered by fome, rather as a cutting than an untying of the knot, yet it has been embraced by philosophers of great eminence *; and it must be owned that it may be applied to the folution of some phenomena with peculiar propriety. Naturalists affure us, that, though some few species of fishes

^{*} Kircher Mun. Sub. L. iii. c. iii. Nollet. Lec. de Phys. Tom. IV. p. 62.

fishes thrive in fresh water, and some others live alternately in fresh water and falt, yet by far the greatest number cannot exist out of the sea: now whether we suppose the sea to have become falt from the influx of rivers, or from the gradual folution of beds of rock falt, or from the combined influence of both these causes, it must for some years have remained so exceedingly fresh, that it will not be an eafy matter to account for the continuation of the existence of the numberless species of fishes, which cannot live in fresh water. This difficulty is not removed by supposing, that fishes do not imbibe any part of the fea's faltness with their food, and attributing the efficacy of sea water in preferving life, to the superior weight with which it compresses the organs of respiration, for this superior weight, is as much an effect of the salt dissolved in it, as the saline taste itself. The saltness of the Caspian sea, of the lakes of Mexico, and Titicaca, and of other large collections of waters, which have no effluent rivers, nor visible communication with the sea, may be as successfully explained upon this hypothesis, — that the sea was at the creation impregnated with salt — as upon either of the preceding.

Besides the opinions, concerning the cause of the saline impregnation of the sea, which have been here mentioned, there is another, which suture ages will, probably, see less questionable reasons to adopt than we do: I mean that which maintains, — that sea salt is constantly and abundantly

dantly generated, both on the furface of the earth, and in the bosom of the ocean.

But how ineffectual foever our attempts may be to explain the cause of the faltness of the sea; yet one might have hoped, that, in this age of philosophy and curious navigation, the degree of its faltness in every latitude, and every feafon of the year, would have been ascertained by accurate experiments. The acquiring knowledge by experiments, is a flow and laborious method, but it is, at the fame time, a method within our reach: whilst the theoretical investigation of the proximate cause of any natural phenomenon often surpasses, and that of its ultimate cause, always surpasses the apprehension of the human intellect.

Some experiments, tending to the elucidation of this point, respecting the fameness or diversity of the faltness of the sea, in different places, were made in the course of the voyage towards the North Pole, in 1773. We learn from these experiments, that the sea water at the Nore, contained not quite 3 of falt; at the back of Yarmouth fands not quite 1/32; off Flamborough Head rather more than 1/29; off Shetland rather less than 1/22; latitude 74 at fea 1/29; latitude 78 less than 1/28; latitude 80, near the ice, not quite 30; latitude 80.30, under the ice, not quite 1/28; latitude 68.46, rather more than $\frac{1}{28}$; latitude 65, at sea, rather less than 1/28 *. "Dr. Hales.

* These several quantities are derived from the experiments mentioned in a Voyage towards

Hales got only 1/27 from water taken up in the Mediterranean, and 1/2 from water taken up at the Nore. Dr. Rutty fays, he got $\frac{1}{25}$ from water taken up in latitude 65; 18 from water taken up near to Dublin; and I from water taken up at Dungarvan; and Dr. Lucas, that he got 1/23 from sea water taken up at Harwich *." The reader will observe that these experiments do not perfectly accord, as to the quantity of falt contained in water taken up at the same place, as at the Nore, and in latitude 65. This is not to be wondered at; the fea water in the same latitude, is not always equally di-

wards the North Pole, 1773, by Conf. John Phipps, now Lord Mulgrave, p. 143.

^{*} Monro on Mineral Waters, Vol. I. p. 105.

diluted by the fresh water which falls from the atmosphere; nor can we be certain, that different persons, in making experiments of this kind, have always used the same degree of heat, in drying the residue which remains after the evaporation of the water; or that they have evaporated the water with the same degree of heat: and yet this circumstance alone, may occasion a great disparity in the quantity of the faline matter, separable from a definite weight of sea water. For not to infift upon, what has been before mentioned, the decomposition of a part of the sea falt, which takes place when a folution of it is evaporated with a great heat, it may be observed, that the sea salt in substance is dispersed, when a faturated folution of it is evaporated with even less than a boil-VOL. II. ing ing heat. This is very clearly seen, when a small quantity of a solution of sea falt is evaporated to dryness in a deep copper vessel, for the inside of the vessel, which can come in contact with nothing but the vapour, is spangled with particles of salt, which have been carried up with the vapour.

It appears from some experiments, formerly made in a voyage from England to Bombay in the East Indies, that the weight of the sea water was the greatest, not precisely at the Equator, but where the fun was vertical, and confequently, in fimilar circumstances, where the heat was greatest. The greatest weight of a definite quantity of fea water, which was observed in failing from 28 degrees, north latitude, to the Cape of Good Hope, which is about 34½ degrees fouth latitude,

titude, in the months of May, June, and July, was at St. Jago island, north latitude, 15 degrees; and the least was at Tenerif island, north latitude 28. The weights of equal bulks of Thames water, of the fea water at Tenerif, and St. Jago, were $659 - 673^{\frac{1}{2}} - 780^{\frac{1}{2}}$ grains*; the proportion of which numbers may be nearly thus expressed. -Thames water 1000, - Tenerif sea water 1022, - St. Jago sea water 1184. By comparing these numbers with a Table in the Philosophical Transactions, exhibiting the comparative weight of equal bulks of fimple water, and of water impregnated with different portions of sea falt, it may be conjectured, that the Tenerif sea water contained about 3 of falt, and the Sr.

^{*} Gentleman's Mag. Vol. XXV. p. 260.

St. Jago water above $\frac{1}{4}$ of its weight of falt, so that it was nearly, if not fully, saturated *.

As it is not every person who can make himself expert in the use of the common means, of estimating the quantity of salt contained in sea water, I will mention a method of doing it, which is so easy and simple, that every common sailor may understand and practise it; and which, at the same time, from the trials I have made of it, seems to be as exact a method, as any that has yet been thought of. — Take a clean towel or

any

^{*} I formed the table here referred to above 10 years ago; I have reason to think, that those who have leisure and accurate instruments, might make it more correct, by using more precaution than I did in some particulars, especially in what relates to the purity of the salt. Philos. Trans. 1770, p. 349.

any other piece of cloth, dry it well in the fun or before the fire, then weigh it accurately, and note down its weight; dip it in the fea water, and, when taken out, wring it a little till it will not drip, when hung up to dry; weigh it in this wet state, then dry it either in the fun or at the fire, and, when it is perfectly dry, weigh it again. The excess of the weight of the wetted cloth above its original weight, is the weight of the fea water imbibed by the cloth; and the excess of the weight of the cloth. after being dried, above its original weight, is the weight of the falt retained by the cloth; and by comparing this weight, with the weight of the sea water imbibed by the cloth, we obtain the proportion of falt contained in that species of sea water.

Who-

Whoever undertakes to ascertain the quantity of falt, contained in fea water, either by this or any other method, would do well to observe the state of the weather preceding the time when the fea water is taken out of the sea, for the quantity of falt contained in the water near the furface, may be influenced, both by the antecedent moisture, and the antecedent heat of the atmosphere. And this leads to the confideration of a question proposed by Aristotle *, - Why are the upper parts of the fea falter and warmer than the lower? ... Some philosophers admitting the fact, have followed him in attempting to explain it; whilft others have thought themselves authorized by experiment, to deny the truth of the

po-

Arist. Prob. S. xxiii. 9. 30.

position; and those, perhaps, will argue with the greatest justness, who shall affirm, that it is neither generally to be admitted, nor generally to be rejected, but that the sea in fome places, and under certain circumstances, is falter and warmer at the furface, than at any confiderable depth beneath it, while in many others the reverse is true. The question confists of two parts, betwixt which, though there, probably, is a connexion, yet it is not so necessary a one, as to hinder us from confidering each part by itself.

As to the faltness of the sea at different depths, we have different accounts concerning it. There are two methods of estimating the relative quantities of salt contained in

H 4 differ-

different specimens of sea water; one confifts in weighing equal bulks of them, suppose a pint, or a bottle full of each; for if they have equal weights, it is fafely enough inferred, that they contain equal quantities of falt: the other consists in evaporating a pint, or any other measure of fea water, and weighing the falt (which is not evaporable) remaining after the water is wholly diffipated. Mr. Boyle found, that equal bulks of water taken up in the Channel between France and England at the furface, and at the depth of fifteen fathoms, were equally heavy, and thence he concludes, that the fuperficial water was as falt as that at a great depth *.

On

^{*} Boyle's Observ. on the Saltness of the Sea.

On the other hand, Count Marfilli obtained by evaporating the water, a thirty-fecond part only of its weight of falt from water, taken up on the surface of the sea in the gulf of Lyons, whilft that taken up at the fame time and place from a great depth gave him a twenty-ninth part of its weight of falt; and he thence infers, the greater faltness of the sea at the bottom than at its furface *. In this conclusion he has been supported by experiments made in the gulf of Bothnia.

There can be no reason to suspect the accuracy with which any of these experiments was made; in different places the facts will probably be different. The Rhone discharges much fresh water into the gulf of Lyons;

^{*} Histoire Phys. de la Mer.

Lyons; this fresh water being lighter than the sea water, will not readily mix itself with it, and for this reason the fuperficial water will be most diluted by it, and from that circumstance it will contain less falt, in a definite quantity, than the water which is at a greater depth. At Northwich they pump their brine, which is to be boiled into falt, into a very large circular bason, sunk in the ground, and lined with brick, from whence, when its impurities are fubfided, it is conveyed to the boiling pans. This bason is exposed to the open air, and in case of a great fall of rain, or fnow, they let off the uppermost parts of the water through a wooden tube, which is at other times stopped with a plug, placed

placed upon a level, nearly, with the upper furface of the brine in the bason; what is thus let off is not preferved, but thrown away as useless. This practice proceeds upon the principle we are speaking of, namely, that fresh water is not apt to mix itself, unless it be much agitated with falt water. The gulf of Bothnia receives rivers from an immense range of mountains, extending themselves to the east, the north, and the west, far beyond the polar circle; and therefore, as in the gulf of Lyons, its surface may be more diluted with fresh water than its middle or bottom. But in the water of the English channel, with which Mr. Boyle made his experiment, the case is very different. This water has has a communication with the German ocean on one fide, and with the Atlantic on the other; and, from that circumstance, it is subject to fuch a constant agitation as will occasion all the fresh water, poured into it by the Thames, Medway, and other rivers of less consequence, to be uniformly diffused through all its substance, so as to render it equally falt at all depths. The constant effect produced on the superficial water of the fea, by the influx of a large river, is somewhat similar to the temporary effect, attending a downfal of rain; the superficial water will be thereby much diluted. It was observed in the voyage to Bombay before referred to, that if a quantity of sea water in dry weather weighed

weighed 778 grains, an equal quantity immediately after a fall of rain would not weigh above 676 grains, the fame quantity of Thames water weighing 659 grains. Hence it may be collected, that the weight of a cubic foot of the fea water before rain exceeded the weight of a cubic foot after rain by 55 ounces.

In the voyage which was made towards the North Pole in 1773, we meet with some experiments on this subject.

In the open sea off Shetland, north latitude 60 degrees, equal quantities of water were taken up at the surface, and at the depth of sixty sive fathoms; these different waters yielded by evaporation equal quantities of salt, namely, \(\frac{1}{29} \) of their weight nearly.

On

On another occasion, in north latitude 65 degrees, some water taken up from the surface gave nearly $\frac{1}{28}$ of its weight of falt, whilst an equal weight taken up from the depth of 683 fathoms in the same place gave only $\frac{1}{32}$ *.

It is obvious that the first of these experiments confirms Mr. Boyle's notion of the sea being equally salt at all depths, and that the second is wholly opposite, both to his opinion, and that of Count Marsilli, so that the question remains still undecided. There is a circumstance, however, which I will submit to the reader's conside-

^{*} In page 143, from which this account is extracted, the latitude is put equal to 75 degrees; but it appears from pages 117 and 137, that the ship on the 4th of Sept. when this experiment was made, was in latitude 65.

consideration, whether it may not be fufficient to explain the different refults of the experiments made during the voyage here spoken of. The experiments which gave equal quantities of falt from equal quantities of water, taken up at the furface, and at the depth of 65 fathoms, were made on the 12th of June; the others, which gave more falt from the fuperficial, than from the deep water, were made on the 4th of September. Now, admitting the faltness of the superficial water, and of water at the depth of 683 fathoms to have been the same, in the beginning of June, why may not the quantity of water, evaporated from the furface of the fea, during the hot months of July and August, have left the superficial water more impreg-

impregnated with falt than the water at a great depth? It is some confirmation of this notion, that the air in June was only 6 degrees warmer than the water from the depth of 65 fathoms, and that the air in September, when the experiment was made, was above 26 degrees hotter than the water from the depth of 683 fathoms. The rife of fresh fprings at the bottom of the sea, in particular places, may be another reason for our accidentally finding the sea salter at its surface than at any great depth below it. However, neither of the reasons here offered in explanation of the phenomenon are wholly to be relied on; for the fresh water which may accidentally be found at the bottom of the fea will rife up till it becomes as much

much impregnated with falt, as the water incumbent over it is; and the water at the furface, which is rendered heavier by the fun's having evaporated fome of its fresh particles, will probably fink downwards, and mix itself with the water below it, till the whole mass of water becomes equally heavy, and consequently equally falt. The fact itself, of the fea being in any case salter at the furface than at its bottom, ought to be ascertained by repeated experiments.

With respect to the temperature of the sea at different depths, it seems reasonable enough to suppose, that in summer time it will be hotter at the surface than at any considerable depth below it, and that in winter it will be colder. Suppose a VOL II. I cistern,

cistern, twelve feet in depth, to be filled with fpring water, of 48 degrees warmth, to the height of eleven feet; then, if we fill up the ciftern to its top, by gently pouring water heated to 100 degrees upon the furface of the spring water, it may readily be understood, that the heat of this water will not be instantaneously communicated through the whole mass of water in the cistern, but that the water will decrease in heat from the furface to the bottom of the ciftern. On the other hand, if on the 11 feet of spring water heated to 48 degrees, we pour a foot of water heated only to 33 degrees, it may be expected, that the spring water, which is nearest to the cold water, will be fooner cooled by it than that which is at a greater distance:

distance; and on this account the water at the bottom of the ciftern will be warmer than that in the middle or at the top. It must be observed, however, that cold water being, bulk for bulk, heavier than hot water, the water which has only 33 degrees of heat will descend by its superior weight, into the mass of water contained in the cistern, and thus the water in the ciftern will be cooled, not only by the bare communication of cold from the upper water, but by the actual mixture of that water with the rest, so that the difference between the heat of the water at the bottom and top, will not be fo great as it would have been, if the cold water had not mixed itself with the rest. These 1 2

fuppo-

suppositions of hot and cold water incumbent on the spring water in the ciftern, are analogous to the action of the fummer and winter atmospheres incumbent on the furface of the sea. No person, who has bathed in deep standing water in fummer time, can have failed to observe, that the water grew colder and colder, according to the depth to which he descended. I have frequently observed, that the surface of a pool of water of two feet in depth, has in a funny day, even in winter, been five degrees hotter than the water at its bottom.

Mr. Wales describes the instrument he made use of for trying the temperature of the sea at different depths, in the following terms:

"The apparatus for trying the heat of the fea water at different depths, confifted of a square wooden tube, of about 18 inches long, and 2 inches fquare externally. It was fitted with a valve at the bottom, and another at the top, and had a contrivance for suspending the thermometer exactly in the middle of it. When it was used, it was fastened to the deep-sea line, just above the lead, fo that all the way as it defcended the water had a free passage through it, by means of the valves which were then both open; but the instant it began to be drawn up, both the valves closed by the preffure of the water, and of course the thermometer was brought up in a body of water, of the same tempera-

13

ture with that it was let down to *." With this instrument, which is much the same with one formerly described by Mr. Boyle, in his observations about the faltness of the sea, water was fetched up from different depths, and its temperature accurately noticed, in different seasons and latitudes.

August 27, 1772, fouth latitude 24°. 40'. The heat of the air was 72 1, - of the water at the furface 70, - of water from the depth of 80 fathoms 68 +.

December 27, 1772, fouth latitude 58°. 21'. The heat of the air was 31 12 - of the water at the furface

^{*} See Aftronomical Observations made in a Voyage towards the South Pole, &c. in 1772, 1773, &c. by W. Wales. Introduction, p. 53.

[†] Wales' Obser. p. 206.

face 32 — of water from the depth of 160 fathoms $33^{\frac{1}{2}}$ *.

In the voyage to the high northern latitudes before mentioned, they made use of a bottle to bring up water from the bottom, which is thus described. "The bottle had a coating of wool, three inches thick, which was wrapped up in an oiled Ikin, and let into a leather purse, and the whole inclosed in a wellpitched canvas bag, firmly tied to the mouth of the bottle, fo that not a drop of water could penetrate to its surface. A bit of lead shaped like a cone, with its base downwards, and a cord fixed to its small end, was put into the bottle; and a piece of valve leather, with half a dozen sips of thin bladder were strung.

^{*} Wales' Obser. p. 208.

strung on the cord, which, when pulled effectually, corked the bottle on the inside." I have here put down two of the experiments which were made during that voyage.

August 4, 1773, north latitude 80°. 30'. The heat of the air was 32, - of the water at the surface 36, - of water fetched up from the depth of 60 fathoms under the ice 29 *.

September 4, 1773, north latitude 65°. The heat of the air was $66\frac{1}{2}$, of the water at the furface 55, — of water from the depth of 683 fathoms 40.

It appears from all these experiments that, when the atmosphere was hotter than the furface of the fea, the superficial water was hotter than

^{*} Voy. towards the North Pole, p. 143.

than that at a great depth; and when the atmosphere was colder than the surface of the sea, it is evident that the superficial water was somewhat colder than that at a considerable distance below it: and I doubt not that this will generally be the case, though sudden changes, in the temperature of the atmosphere, which cannot be instantly communicated to the sea, may occasion particular exceptions.

In the year 1779, feveral experiments were made, with great accuracy, in order to investigate the temperature of the lake of *Geneva*, and of other lakes in Switzerland, at different depths; we learn from them, that in winter time there is very little difference between the heat of the

the water at the furface, and at a great depth below it; but that in fummer, the fuperficial water is confiderably warmer than that which is at a great distance from the furface. The experiments were made with a thermometer graduated after Reaumur's scale; some of them, reduced to Fahrenheit's scale, are expressed below.

Temperature of the lake of Geneva at different depths, in the beginning of February 1779, after a month's uninterrupted frost.

Heat of the open air variable from 37 to 40 degrees.

Water at the furface of the lake - $42\frac{1}{8}$ Depth 100 feet - - $42\frac{1}{8}$ Depth 250 feet - - $42\frac{1}{8}$ Depth 950 feet, bottom $41\frac{27}{40}$

(139)

In another part of the lake, open air from 37 to 40.

Surface - - $42\frac{\pi}{8}$ Depth 350 feet - - $42\frac{\pi}{8}$ Depth 620 feet, bottom $41\frac{27}{80}$

Temperature of the lake of Neu-châtel July 17, 1779.

Air - 75 $\frac{1}{5}$ Surface - 73 $\frac{5}{8}$ Depth 325 feet, bottom 41 *.

The reader will find a great many other experiments of the same nature, in the first volume (the only one yet published) of a very interesting work, intitled, Voyages dans les Alpes, par Horace-Benedict de Saussure, Professor of Philosophy at Geneva.



ESSAY V.

Of fresh Water procurable from Sea Water, by Congelation, and by Distillation.

"HE fecond day we descried a main bank of ice, in the latitude of 60°. We wanting fresh water did sail close to this land of ice, and hoisted out our boat, and loaded her twice with ice, which made us very good fresh water *." — About nine of

^{*} Cap. Weymouth's Voy. in 1602. Purchas's Col. B. iv. c. 13.

of the clock in the forenoon we came by a great island of ice, and by this island we found some pieces of ice broken off from the faid island, and being in great want of fresh water, we hoisted out our boats of both ships, and loaded them twice with ice, which made us very good fresh water *."-"The pieces of ice we took up were hard and folid as a rock, the falt water which adhered to the ice, was fo trifling as not to be tasted, and after it had lain on deck a little time, intirely drained off, and the water which the ice yielded was perfectly fweet and well tasted +." - " In the afternoon we filled our casks with fresh

^{*} Cap. Weymouth's Voy. in 1602. Pur-chafs' Col. B. iv. c. 13.

[†] Cook's Voy. towards the S. Pole in 1773; Vol. I. p. 37.

fresh water, from the ice, which we found very pure and foft *."

Notwithstanding these testimonies of our most experienced navigators, concerning the fresh water which they procured from the thawing of the ice, they found floating in the fea; yet it might still remain a matter of doubt, whether the ice, from which the water was obtained, had been formed in the fea, and, confequently, whether sea water itself would when frozen yield fresh water? For it might, with fome appearance of probability, be faid, that the ice had either been formed at the mouths of large fresh water rivers, and thence by tides or torrents drifted into the fea; or that it had been broken by its

* Phipp's Voy. towards the N.Pole in 1773, p. 60.

its own weight, from the immense clifts of ice and frozen fnow, which, in countries where there are few rivers, are found in high latitudes to project a great way into the fea*; or lastly, admitting it to be formed in the sea, it might be urged, that it was formed of fresh water, not of falt. Fotherbye, in his voyage in 1614, esteems snow the original cause of the ice found at sea, for he observed it to be an inch thick upon the furface of the fea; and Captain Cook, from his own observations in the South Sea

^{*} Icebergs are large bodies of ice filling the vallies between the high mountains.—Large pieces frequently break off from the icebergs, and fall with great noise into the water: we observed one piece, which had floated out into the bay, and grounded in twenty-four fathom; it was fifty feet high above the surface of the water. Phipps' Voy. p. 70.

Sea, was disposed to think, that the vast floats of ice he met with in the fpring, were formed from the congelation of fnow †. Without doubt, the snow which falls upon the surface of the fea, being in a folid state, and, bulk for bulk, lighter than the fea water, will not readily mix itself with it; but may, by a due degree of cold in the atmosphere, be speedily converted into a layer of ice; the upper furface of this first layer of ice, being elevated above the furface of the feawill receive all the fresh water which falls from the atmosphere in the form of fnow, fleet, rain, or dew; by the fuccessive congelation of which, the largest fields of ice may at last be formed. Whether the ice found at fea.

[†] Voy. towards the S. Pole, Vol. II. p. 242.

fea, be formed according to any one or all of these ways, it is evident, that it is produced from an accumulation of congealed fresh water, and that we cannot, from the fresh water procurable from ice thus formed, conclude that the ice of frozen sea water would yield fresh water.

To a navigator, it is a matter of little consequence to determine, whence the ice which supplies him with fresh water is produced, he is sure of meeting with more than enough of it for his purpose, and he leaves it to the leisure of philosophers to decide the question, whether congealed sea water will, when thawed, yield fresh water. They have decided it by actual experiments, made with every suitable attention. Some sea water was taken up off the North Foreland, it was exposed to a freezing atmosphere, and it afforded an ice perfectly free from any taste of salt. The specific gravity of the water, produced from the melting of the ice, was somewhat greater than that of distilled rain water, and fomewhat less than that of a mixture of rain and fnow water taken out of a water tub. The degree of cold, in which the fea water froze, was 28½ of Fahrenheit's thermometer, or $3^{\frac{1}{2}}$ lower than that in which common water freezes*. The degree of cold, however, in which fea water freezes, cannot be ascertained in general, unless it can be fhewn, that the fea water, taken up in different latitudes, contains equal quantities of falt, the contrary of which is probably true. And in general,

Philos. Trans. for 1776. p. 251. & 373.

general, the greater the quantity of falt contained in any portion of fea water, the greater will be the degree of cold necessary to freeze it.

We had a sharp frost at Cambridge on the 21st of last December; I filled a thin phial, holding 8 ounces, with fea water, which contained 1/32 of its weight of falt, and exposed it, fuspended from the branch of a tree, during the night of the day before mentioned, to the cold of the atmofphere. In the morning I found that a part of the water had been frozen: I poured the unfrozen part from the other, and having rinsed the ice in fresh water, so as to separate from it the falt water which adhered to it, I thawed it before the fire, and found the water which it gave to be wholly free from falt.

It had been long ago afferted by Macrobius*, that fea water was never frozen, but that the ice found at fea, proceeded from the freezing of the fresh water spread over its surface by the influx of rivers. And in modern times, the opinion, concerning the freezing of fea water, feems to have been admitted with great caution, by our most experienced navigators. They were aware, indeed, that the Baltic and other large feas, were frequently frozen quite over, but they appear to have thought, that falls of fnow laid a fufficient foundation for the production of that event, "without its being at all necessary for the sea water to freeze t." I cannot conceive, that there was any

great

Macrob. Sat. l. vii. c. 12.

t Cook's Voy. Vol. II. p. 242.

great occasion for this cautious mode of expression, since it had been observed, above a hundred years ago, that not only sea water, but water containing double the proportion of salt commonly sound in our sea water, and more than is contained in the sea water of any climate, might be frozen by the cold prevailing in our atmosphere *.

This freezing of sea water, moreover, was formerly practised, and, I believe, is still practised in several parts of the north of Europe, with a view to lessen the expence and trouble of extracting salt from sea water †. Stahl informs us of a chemist, who,

near

^{*} Boyle's Works, fol. ed. Vol. II. p. 264.

[†] Junck. Cons. Chem. Tab. xviii. f. 15. And Wallerii Mineral. French Tranf. Vol. I. p. 316,

near a century ago, endeavoured to expedite the business of making salt in Sweden and Livonia, by means of frost. With this view he proposed the making large reservoirs to contain the sea water, and the pumping the concentrated brine from under the ice into proper vessels, to be boiled in the ordinary way. He obtained a patent, but a combination of salt-boilers ruined his project *.

I cannot see why this custom might not be introduced into England with great advantage. A third part at least of sea water, may, by freezing, be converted into ice by the ordinary cold of our winters; this ice, consisting intirely of fresh water, may be thrown away as useless, and the remaining

^{*} Traitè des Sels, par M. Stahl. French Trans. 1771. p. 143.

maining two thirds, being boiled down, will give all the falt contained in the whole of the fea water; thus there would be a faving at least of one third part of the fuel employed in boiling fea water into falt *. When it is faid, that the unfrozen fea water contains all the falt, this must be understood with some restriction, since it is probable, that the frozen part will, upon most occasions, hold a little falt, but not so much as is contained.

* Bristol and other waters containing earth, are found to deposit their earth, or a great portion of it, by being frozen. Brownrigg on Salt, p. 76. Some ice, taken from under the surface of the sea in Hudson's Streights, being melted, gave 6 ounces of salt from 40 quarts of water. — It is probable, that it would not have given so large a proportion of salt had it been previously cleansed from the adhering sea water. Philos. Trans. 1740. p. 807.

tained in many spring waters, which are reckoned sufficiently pure. Eight pounds of frozen sea water, taken up near Calais, left upon evaporation 32 grains of residuum, about half of which was sea salt. The same quantity of unfrozen sea water, taken up at the same place after the frost, left by evaporation 1412 grains of residuum, so that the water by being frozen, had freed itself from 1380 grains of heterogeneous matter *.

The ice found at fea is of different colours and confistences, some is polished and pellucid, and thought to be fresh water ice; another kind is of a spungy texture, and of a pale green colour like vitriol; and it has been affirmed, that this kind of ice

is

^{*} Journ. des Sçavans Mai. 1769. See also Boerh. Chem. Vol. I. p. 721.

is falt, and consists of salt water frozen *. This is a mistake, both as to the fact and the reason of it; for the vitriol coloured ice, when freed from the salt water in which it swims, is quite fresh †, and sea water when frozen, we have seen, does not yield a salt ice.

We may, perhaps, be less surprised at the particles of water, in which sea salt is dissolved, separating themselves from the particles of the salt, and coalescing together without admitting any junction with such a heavy extraneous body, when we consider, that, during the action of freezing, they refuse all union even with the air itself. Water in its sluid state

^{*} Crantz's Hist. of Greenland, B. I. c. ii. s. 13.

[†] Philos. Trans. for 1770, p. 111.

state is saturated with air, but it is in a great measure, if not wholly, deprived of it by being frozen; and modern philosophers have followed the opinion of Aristotle, in attributing the infalubrity (real or supposed) of water which has been frozen to the loss of its air *. "The water we melted out of the ice (taken up at fea) was perfectly fresh, and had a purer taste than any we had on board. If any fault could be found with it, it was that the fixed air was

* Non solo rigore nivalis aqua perniciosa est, sed ob aliam causam quam non pigebit aperire auctore Aristotele. Omnis aqua, inquit, habet in se aeris tenuissimi portionem quæ salutaris est — nix ergo quæ nihil aliud est quàm aqua in aere densata tenuitatem sui cum densaretur amisit, et ideo ex ejus resolutæ potu diversa morborum genera visceribus inseminantur. Macrob. Sat.

expelled from it, by which means almost every one who used it, was affected with fwellings in the glands of the throat. Water melted from fnow or ice is known always to have this effect, and the constant use of it in mountainous countries produces those enormous wens which are common among Alpine nations*". If the loss of the water's air be the true cause of the tumid throat, obfervable among the inhabitants of the Alps, and of the glandular fwellings here mentioned, it feems as if a very simple process would free it from this noxious quality, and restore it to its original salubrity. A fimple exposure to the air, for a few days, would be fufficient for the purpose; since water, which

^{*} Forster's Voy. Vol. I. p. 107.

which has been deprived of its air, imbibes it afresh very readily, and becomes saturated with it in no great length of time. And this readiness of imbibing air makes a material difference between the water obtained from the simple thawing of snow, and river water, though the river water itself should proceed from melted snow; for being in its course constantly exposed to the air, it will soon regain the air which it had lost by being frozen.

This may not be an improper place to observe, that several physicians have rejected the notion of the use of snow water being the cause of the wens here spoken of, and that upon good grounds. For in Greenland, where snow water is commonly used, these unsightly protuberances

u

are never met with*; nor did I ever fee one of them in Westmoreland, where we have higher mountains, and more snow than they have in Derbyshire, in which country they are very common. But what puts the matter beyond doubt is, that these wens are common in Sumatra, where there is no snow during any part of the year †.

The possibility of extracting fresh water from sea water by distillation, has been long known; and indeed it seems as if it could never have been questioned by those, who duly reslected upon the origin of all the fresh water we meet with on the surface of the earth. The geography of the globe is yet but impersectly known:

* Rutty's Synop. p. 42.

⁺ Philos. Trans. for 1778, p. 165.

known; enough, however, is known of it to convince us that a much larger portion of its furface is occupied by sea than by land. The Atlantic Ocean appears at first view to be larger than the whole Western Continent, and the area of the rest of the habitable world, even if we take into confideration the land recently explored in the fouthern hemisphere, seems as if it could not equal half that immense expansion of water which constitutes, the Indian and Pacific Oceans. Philosophers have attempted, by meafuring the most approved maps, and by other ingenious methods, to afcertain the exact proportion between the land and sea; great precision cannot reasonably be expected to accompany this inquiry; but when

we learn from one, that the fea covers near three fourth parts *. and from another that it covers four fifths + of the furface of the globe, we may furely rest satisfied of the truth of the general position, that there is a much greater extent of fea than of dry land. This immense mass of falt water which furrounds the globe, is the great primary fource from which all fresh water is derived. The vapour which is inceffantly elevated from thence by the heat of the fun, the action of the wind, and other

* See Dr. Long's Astron. Vol. I. p. 168.

† The seas, and unknown parts of the earth (by a measurement of the best maps), contain 160,522,026 square miles; the inhabited parts 38,990,569: Europe, 4,456,065; Asia; 10,768,829; Africa, 9,564,807; and America, 14,110,874. Ferguson's Tables, p. 300.

other less obvious causes, consists, generally speaking, of fresh water, which being discharged from the atmosphere in the form of dew, rain, hail, or fnow, constitutes springs, rivers, and stagnant pools. The taste of sea water is, we know, not only falt but bitter; the common falt, which occasions its faltness, and the Epsom salt, which occasions its. birterness, can neither of them be raised in vapour (in any sensible proportion) by the same gentle degree of heat with which water may be raised; in order, therefore, to obtain fresh water from sea water, we need only copy the process of nature, and distil sea water with a gentle heat. This method of obtaining fresh water, from the distillation of sea water, was practifed by Sir R. yol. II. L Hawkins,

Hawkins, in the reign of Queen Elizabeth:—" Although our fresh water had failed us many days, yet with an invention I had in my ship, I easily drew out of the water of the sea a sufficient quantity of fresh water, to sustain my people, with little expence of suel; for with four billets I stilled a hogshead of water, and therewith dressed meat for the sick and whole. The water so distilled was found to be wholsome and nourishing *."

Since the time of Sir R. Hawkins, a great variety of attempts have been made in our own, and in other countries to procure fresh water from sea water; they have in general been little else than different modes of distillation, but many of the authors

^{*} Purchass' Collec. of Voy. B. vii. c. 5.

authors of them, either from an ignorance of the real nature of fea water, or from a defign of rendering their process mysterious, have mixed different ingredients with the water either before or after its distillation. The manner of procuring fresh water, by the simple distillation of sea water, seems at present to have attained a great degree of perfection, both in France and England. M. de Bougainville, in his voyage round the world, has borne honourable testimony to the utility of the machine for distilling sea water, which was made public in 1763, by M. Poissonnier, its inventor. Lord Mulgrave, in his voyage towards the North Pole, in 1773, has done equal justice to the method of obtaining fresh water from the sea

by

by distillation, which was introduced into the English navy in the year 1770, by Dr. Irving. Whether the invention of M. Poissonnier suggested any hints to Dr. Irving, is best known to himself; but he has unquestionably added such improvements to that method (to fay no more), as seem to have justly intitled him to the parliamentary reward of five thousand pounds, which he has obtained. The French are as jealous of the glory of their nation in arts as in arms, and the English, we trust, will never be their inferior in either; it is to this excess of jealousy we must attribute the acerbity, with which one of the best chemists of the age speaks of Dr. Irving, as having deceived the parliament of England, by appropriating to himfelf

(165)

felf the discovery of M. Poisson-nier*.

In order that the reader may have a clear notion of Dr. Irving's method, let us suppose a tea-kettle to be made without a fpout, and with a hole in the lid, in the place of the knob; then the kettle being filled with sea water, the fresh vapour which arises from the sea water as it boils, will iffue out through the hole in the lid; into that hole fit the mouth of a tobacco-pipe, letting the stem have a little inclination downwards, then will the vapour of fresh water take its course through the stem of the tube, and may be collected by fitting a proper veffel to its end. This would be an apt representation of Dr. Irving's contrivance:

^{*} Baumè's Chy. Vol. III. p. 588.

trivance: he has adapted a tin tube, of fuitable dimensions, to the lid of the common kettle used for boiling the provisions on board a ship; the fresh vapour which arises from boiling sea water in the kettle, passes through this tube into a hogshead, which serves as a receiver: in order that the vapour may be readily condensed, the tube is kept cool, by being constantly wetted with a mop dipped in a tub of cold sea water.

It appeared from the testimony, which was delivered to the Lords of the Admiralty, by many respectable officers who were eye-wilnesses to an experiment, made on board the Arrogant, at Spithead, in January 1771, that "80 gallons of sea waterdid, in twenty-sive minutes, after being put into the Arrogant's cop-

per, and a fire made, distil in the proportion, of twenty-five gallons per hour, into fresh water, perfectly well tasted, and of less specific gravity than the best spring water in that neighbourhood;" and the faid officers gave it as their opinion, that 500 gallons of fresh water might be distilled in the space of 24 hours, with the same quantity of fuel in proportion to the time, as is required in the ordinary business of the ship. Every ship's kettle is divided into two parts by a partition in the middle, one of these parts is only in use when pease or oatmeal are dressed, but water is at the same time kept in the other to preserve its bottom. Dr. Irving has availed himself of this circumstance, and by filling the spare part of the copper

L 4

with -

with fea water, and fitting on the lid and tube, he has shewn, that 60 gallons of fresh water, may be drawn off during the boiling of either of the abovementioned provisions, without the use of any additional fuel: he recommends also the preserving the water which may be distilled from the coppers in which peafe, oatmeal, or pudding are dreffing, as both a falutary beverage for the fcorbutic, and the most proper kind of water for boiling of falt provisions.

In November, 1771, Lord Sandwich fent me two bottles of the best distilled water, which could be prepared by Dr. Irving from sea water, desiring my observations upon it. In compliance with his Lordship's request, I made the following experiments,

ments, of which I fent him an account, without venturing to give the most distant opinion concerning the falubrity or infalubrity of the water. - Exper. 1. - Four ounces of the distilled sea water, being evaporated by a flow fire, upon a filver plate, left a pellicle, which was very fenfibly saline to the taste, and glutinous to the touch. - 2. Four ounces of the conduit water of Trinity college, treated in the same manner, left a pellicle, but not quite fo large, nor so manifestly sapid, as that from the distilled sea water. - 3. The same quantity of common distilled water, being evaporated in the same way, left no sensible pellicle. - 4. The fame quantity of common distilled water, impregnated with a small drop of

of spirit of falt, left no pellicle upon the whole surface of the plate, but only a yellowish spot upon that part of it from which the last portion was evaporated, this fpot was glutinous to the touch, and had a bitter metalline taste. — 5. The same quantity of common distilled water, impregnated with two grains of sea falt, left a pellicle, fimilar to that left by the distilled sea water, except that it was fomewhat whiter, had a less piquant tafte, and a less glutinous consistency. From the 4th and 5th experiments, compared with the first, it may be inferred, that the distilled sea water, which I examined, contained a small portion of fea falt, and also a small portion of the acid of sea salt uncombined with any basis. A very minute

minute portion of sea salt, or of the acid of sea falt, may be discovered in a large quantity of water, by the milkiness which ensues on dropping intoa glass full of the water, a drop or two of a faturated folution of filver in the acid of nitre. — 6. I dropped a folution of filver in acid of nitre into common distilled water, no milkiness enfued, nor was the transparency of the water changed. - 7. Into an equal quantity of the distilled sea water, I dropped an equal number of drops of the folution of filver, the water became very turbid, and a copious white precipitation enfued. These experiments shew, that the distilled sea water is not wholly freefrom saline particles; but it probably contains them in fo small a proportion,

portion, as not to injure its falubrity in any fensible degree.

We may be the more disposed to admit the possibility of distilled sea water containing faline particles, when we reflect upon the smell of the acid of fea falt, which circulates through the houses in which falt is prepared, by boiling either fea water or brine. The vapour which arises from the pans in which falt is boiled, being caught and condensed in proper vessels, and examined by proper tests, gives indications both of sea falt in substance, and of its acid. It is not an easy matter to ascertain the precise degree of heat, in which saline particles begin to accompany the vapour which is raifed from folutions of sea falt; it is probably a degree far inferior to that in which water boils: at least we are certain, that faline particles are found in rain and snow water, both of which are derived from vapours raised into the atmosphere by the action of the sun upon the ocean.

ESSAY



E S S A Y VI.

Of calcareous Earth, crude and calcined.

THE word Calx has been introduced into the English language from the Latin; it properly denotes the friable earth, to which some sorts of bodies are reduced by fire; the operation by which they are reduced to that state, is called calcination, and a very large class of bodies, from their being peculiarly subject to be converted by fire into a calx, have been deno-

denominated, by various mineralogifts, calcareous bodies; the calx or powdery earth, procured from calcareous fubstances by calcination, is commonly called lime, more philosophically quicklime.

Lead, iron, tin, and feveral other mineral fubstances, may respectively be reduced by fire to the state of a calx, but the earths obtainable from these substances by calcination, not possessing the other general qualities appertaining to the calces of calcareous fubstances, are not called quicklimes, but calces of this or that fubstance from which they are prepared.

In Cambridgeshire, and many of the fouthern counties of England, lime is prepared from the calcination of chalk, or, as it is here generally called clunch. The kilns are inverted cones

funk

funk in the earth, and lined with brick; the base of the cone is about ten feet in diameter, and the depth of the kiln is about fourteen feet. One of these kilns will burn about 150 bushels of lime in twenty-four hours; they use generally one bushel of coal, for every four bushels of lime, and in fummer, when the chalk is dry, they will fometimes get 5 bushels of lime, from the confumption of one bushel of coal; but coal being dear, the chalk is feldom well burned. In Wales, Westmoreland, Derbyshire, and many other counties, they burn different sorts of limestone, fome of them approaching to the fineness of marble: In Holland, where they have neither chalk nor limestone, they drag fish shells out of the fea with nets drawn by horses, M VOL. II.

and burn the shells into lime. In the islands of the southern hemisphere they burn coral rocks into chenam or lime; and in some parts of America they calcine madrepores, and other fpecies of coral for the same purpose. Lime may also be prepared from the calcination of all kinds of marble; of various kinds of spar; of stalatites, otherwise called dropstone, and in Derbyshire watricle; and of several other substances which consist of calcareous earth, either pure, or mixed with clay or fand, or other matters in different proportions. In Cheshire, and other countries, where they have no common materials for making of lime, it would be worth while to examine the earths, which may be met with upon the furface of the ground, or at a little distance below it; for

cal-

calcareous fubstances are not always united into hard compact masses, but are sometimes found in the form of earth, and that of different colours.

Calcareous fubstances are in some countries calcined with pit-coal, in others with the cinder of pit-coal, in others with wood, in others with peat, in others with furze; the kind of fuel feems to be of no confequence, provided the degree of heat be the same. Some forts, indeed, of pit-coal are apt, especially when used in large quantities, to cake together, and thus hindering, in some measure, the equable diffusion of the heat, the stone remains unburned. In order that the heat may penetrate through every part of the substance to be calcined, it is usual to break it into small pieces; but if the calca-

M 2

reous

reous stone happens to be naturally shaken or split into layers, large pieces may be calcined, by placing them fo that the flame of the fuel may, in ascending, find its way between the feveral layers of which the stone confists. In some parts of Yorkshire, they burn pieces of this fort of stone a foot in thickness, and a foot and a half in length, without breaking them; they use generally eight dozen of coal to a kiln, and obtain twenty-two dozen of lime, the dozen containing thirty-fix bushels.

It is probable, that there is a certain definite degree of heat, to which any particular kind of calcareous fub-flance ought to be exposed, in order to its being converted into the best possible lime. If the heat be too small, the whole of the substance will

not be converted into lime; and on the other hand, it is possible, that the heat may be fo great, as to reduce the substance to a kind of glassy scoria; and whenever it becomes vitrified, it will lose the properties of lime. I am aware of what is generally faid, that calcareous bodies, when pure, cannot be vitrified with the greatest degree of heat; but though the heat of a chemical furnace may not be sufficient for the purpose, yet there is reason to believe, that a superior degree of heat may effect a kind of vitrification; certain it is, that the lime burners are careful not to give too much heat, left they should injure the quality of the lime. When the heat has been too violent, they, in many kilns, find feveral pieces of limestone covered

M 3

vered with a glaffy coat, and flicking together. I do not take upon me absolutely to say, that this effect is to be ascribed to a beginning vitrisication of the limestone, it may either proceed from thence, or it may be accounted for by faying, that the ashes of the fuel adhering every where to the furface of the calcareous fubstance, have, in particular places, where they happened to be amassed in fufficient quantity, contributed to irs vitrification. This vitrification of calcareous earth, when mixed with other fubstances is obvious enough in the iron furnaces, where they are accustomed to mix limestone with the iron ore, the scoria or slag of an iron furnace perfectly refembling glass.

There is a very fingular experiment, which may be properly mentioned

tioned in this place. Mix well together equal weights of powdered chalk, or other calcareous body, and powdered pipe clay, put the mixture into a crucible*. Any where towards the middle of the crucible, put two folid pieces, one of pure chalk, the other of pure clay, fo that they may not be contiguous to each other, but be every where feverally furrounded with the mixture of chalkand clay; then by exposing the whole to a strong degree of heat for a sufficient length of time, it will be found that the mixture has been converted into

* Crucibles are round or triangular vessels of different dimensions, wider at the top than at the bottom; they are principally used for the melting of metals, and are made of clay and fand, or of clay and black lead, or of such other materials as can resist the strongest fires without melting.

into glass; and upon breaking the vitrified mass, we shall discover the two folid pieces of chalk and clay, unvitrified, and unaltered in their figure, though every where furrounded with glass. Any other fort of clay, would probably answer the purpofe as well as pipe clay, but I have always made the experiment with that, as being one of the purest clays. From this experiment it is certain, that a mixture of calcareous earth and clay, is reducible to glass, in a degree of heat which is not fufficient to vitrify either of these substances when pure. The clay, of which bricks and tiles are made, often contains a quantity of calcareous earth, and hence we may understand the reason why ordinary bricks and tiles are not able to refift a great degree

degree of heat: a tile covering a crucible is often quite vitrified, whilft the crucible remains unaltered, the tile being a mixture of clay and calcareous earth, and the crucible being made of pure clay and fand.

It is well known, that lime is lighter, bulk for bulk, than the chalk or stone from which it is made: fome fubstance therefore or other is diffipated during the calcination; the nature of this substance will be inquired into hereafter, at present our concern is to ascertain its quantity. The fubstances which I converted into lime, were fine white marble called statuary marble; Sienna marble; fine transparent crystallized spar, of that species which mineralogists have denominated hexagonal truncated; rhomboidal opake refracting fpar;

spar; rhomboidal transparent refracting spar; all these spars from Derbyshire; a marble, of a blueish cast, called dove marble; purple-veined marble; Clitheroe limestone; Purbeck stone; chalk from Cherry Hinton, near Cambridge; Portland stone; Ketton stone from Rutlandshire, denominated hammites, from its being composed of globules resembling the roes of fishes. A common die is a little cube; if we suppose the length, breadth, and thickness of a die, to be respectively increased, till each of them becomes equal to an inch, foot, yard, or mile, then will the die become a cubic inch, a cubic foot, yard or mile. The weight of a cubic foot of water is found, by experiment, to be precisely equal to 1000 avoirdupois ounces. Assuming then the weight

weight of a cubic foot of water to be 1000 ounces, by a method, sufficiently explained in books which treat of Hydrostatics, I calculated what would be the weight of a cubic foot of each of the calcareous substances, which I converted into lime.

Weight of a cubic foot of

Water	10007	
Purple-veined marble -	2750	
Sienna marble	2729	
Statuary marble	2725	
Crystallized spar	2701	
Rhomboidal opaque spar	2700	OA
Dove-coloured marble	2694	rd
Rhomboid. transparent spar	2693	lupois
Clitheroe limestone	2686)is
Purbeck stone	2680	gn
Chalk, near Cambridge	2657	ounces
Portland stone	2461	
Ketton stone	2456	
	-	
Medium of the 12 forts	2661	1
	-	J

It is unnecessary to trouble the reader with a particular detail of each experiment, in which one or other of these substances was converted into lime, he will judge it fufficient to be informed of the general method of proceeding, and to be made acquainted with the general refult. The method confisted in selecting pure pieces of the feveral fubstances, and putting fometimes two, fometimes three of them into a crucible filled with fand; care was taken that the pieces neither touched each other nor the fide of the crucible, the crucible was then exposed to a very strong fire for four hours; none of the pieces weighed more than an ounce, fo that the fire to which they were exposed, it is apprehended, was quite fuffi-

fufficient to convert them into perfect quick limes; they were all dry, and were weighed very accurately before and after calcination, and in the weighing after calcination great care was taken to free them from every particle of fand, and to weigh them before they were quite cold. The following table comprehends in one view the different results of the feveral experiments; the first column mentions the different forts of calcareous fubstances with which the experiments were made; the fecond expresses in hundred weights, quarters, and pounds, the quantity of lime which a ton of each respective fubstance would yield by calcination; these numbers were derived, by the rule of proportion, from the small weights used in the experiments;

ments; the third column exhibits the weight of the matter diffipated from each calcareous fubstance during the calcination.

	C.	q.	1b.	C	.q.	1b.
Purple-veined marble -	H	I	24	8	2	4
Purbeck stone	II	I	22	8	2	6
Clitheroe limestone	11	I	17	8	2	11
Dove-coloured marble -	11	I	13	8	2	15
Chalk	11	1	9	8	2	19
Sienna marble '	IJ	I	7	8	2	21
Portland stone	11	I	4	8	2	24
Ketton stone	II	1	2	8	2	26
Statuary marble	II	1	1	8	2	27
Rhomboidal transp. spar	11	I	0	8	3	0
Rhomboidal opaque spar	II	0	12	8	3	16
Chrystallized spar	11	0	1	8	3	27
Med. of lime from a ton	II	1	4 ² / ₃			
Medium loss of weight in a ton	8	2	23 ¹ / ₃			

Having

Having formed this table from my own experiments, I was willing to fee what correspondence it bore with the experiments of others. Authors seldom express themselves on this subject with sufficient precision; I have met, however, with some experiments, which seem to have been made with great accuracy, and I have from them calculated the following table upon the same principle as the preceding.

	C	a	1b.	C	0	lb.]
* Courcelles limestone	11	-				26
‡ Calcareous earth sepa-						
rated from Marle	11	I	23	8	2	5
Calc. earth from Marle	II	1	20	8	2	8
+ Chalk	11	I	9	8	2	19
§ Vienna limestone	11	I	0	8	3	0
* Courcelles limestone	11	0	24	8	3	4
¶ Swedish limestone	H	0	18	8	3	10
¶ Gothland coral -	11	0	12	8	3	16
¶ Fish shells	11	O	6	8	3	22
* Courcelles limestone	11	0	1	8	3	27
¶ Chalk	11	0	0	9	0	0
§ Vienna limestone	10	2	14	9	I	14
Med. of lime from a ton	1 I	0	20 I			
Medium loss of weight } in a ton }	8	3	$7^{\frac{1}{1}\frac{1}{2}}$			
					Fr	'Om

* Paris is principally supplied with lime from the Courcelles limestone,—the three pieces here mentioned were burned in an ordinary lime kiln for 30 hours. Mem. de l'Acad. 1747, p. 62.

From the bare inspection of these tables it is obvious, that calcareous substances of different kinds and countries, do not differ much from each other in the quantity of lime which a ton, or any other definite weight of them would yield by calcination.

Though I had every reason to believe, that the experiments from which I calculated the tables were made with as much accuracy as the nature of the subject would admit;

yet

† Philo. Trans. 1773, p. 161.

|| Edin. Ess. Vol. III. p. 16.

+ Dr. Black, to whom we are indebted for our knowledge of the constituent parts of calcareous earth. Edin. Est. Vol. II.

§ Prof. Jacquin's Exam. Chem. Doc. Mey. Vienna, 1769.

Wallerius, Swed. Mem. 1760.

yet I thought it would add greatly to their confirmation, if it could be shewn, that the quantity of lime really procured from the calcination of a ton of chalk or limestone, was not much different from the medium quantity ascertained by the experiments. I went, therefore, to one of the kilns of this country, where they burn chalk into lime; and I first weighed four bushels of chalk, which had been dried by the heat. of a hot fummer, the medium weight. of the four bushels was 86 pounds: I then weighed four bushels of the lime, warm from the kiln, the medium weight of which was 66 ‡ pounds. Calculating, from these numbers, the weight of lime which a ton of chalk would yield, it will be found to amount to 15 c. 19. 7lb. This quantity of lime being fo different

different from what I expected, I brought a piece of the chalk to my elaboratory. I then weighed it accurately, and found that a month after, though the weather was hot, it had neither gained nor lost weight. I then converted it into lime, and it gave after the rate of 11c. 1q. 19 lb. of lime from a ton; or 3c. 3q. 16 lb. less than what the same chalk when burned in the kiln would yield. I take this difference to be wholly attributable to the superior degree of heat, with which the chalk in my experiment was burned. It is to be wished that more coal was used in the burning of lime in this country; for if a ton of chalk, when properly burned, ought to weigh only about 11 hundred weight, and it does ordinarily N 2 weigh

weigh about 15 hundred weight, it is obvious that the purchaser has about 4 parts in 15 which are not lime but chalk; and to this cause are to be referred the hard lumps, which are found in the lime of this country, when it is slaked; these lumps being nothing but chalk which is not burned into lime for want of a sufficient fire: the expence also of carrying 4 tons of chalk in every 15 tons of lime is a circumstance not to be neglected.

At Pennybridge, in Lancashire, they burn a hard limestone, a Winchester bushel of this stone weighed 1841b. The same measure of the lime, when just burned, weighed 109 lb. These numbers give 11 c. 3 q. 11 lb. of lime from a ton of the stone.

The

The lime burned at Clitheroe, in Lancashire, is reckoned to be as good as any in the kingdom, when applied either as a manure or as a cement: a bushel up-heaped of the best crude stone weighed 147 pounds, an equal measure of the same stoneafter calcination weighed 71 pounds; from this proportion it follows, that the Clitheroe limestone would give only 9c. 2q. 17lb. of lime from a ton of the stone, - this conclusion might be rendered more certain if the medium weight of several bushels. was taken. It may, however, be expected that the Clitheroe limestone should lose more weight than the Cambridgeshire chalk does, for inburning it they use at least twice as much coal, or one measure of coal to two of limestone. This propor-

N- 3

tion

kind of limestone formed by petrefaction, they use I bushel of coal to 3 of lime.

From what has been faid, it must be concluded, that calcareous fubstances have a very great resemblance to each other, as to the quantity of that matter which is dispersed from equal weights of them during calcination; and here a curious question presents itself which cannot be easily decided: - Is the difference in the quantity of lime, procurable from equal weights of different calcareous, fubstances, to be accounted for, from the different proportion in which the earth remaining after calcination is united, in the crude substance, with the volatile part dispersed. during

during calcination; or does it proceed from some unavoidable inaccuracy in making the feveral experiments? - It must be acknowledged, that it is difficult to fay whether the bodies are equally dry before they are fubmitted to calcination, unless we knew the precise degree of force, with which they imbibed and retained the humidity of the atmosphere; it is difficult also to give them exactly the same degree of heat during their calcination, and to weigh them whilst they are equally warm; the greatest attention, moreover, cannot always prevent a loss of some part of the substance to be weighed, nor a gain, in weight from the accretion of some heterogeneous matter; yet, notwithstanding these, and; perhaps, other fources of error in making N 4

making the experiments, I am rather disposed to think, that the proportion is which the fixed earth is united to the volatile substance, is not the same in all calcareous bodies.

A piece of dry chalk, and the three Derbyshire spars were put into the same crucible, and exposed for four hours to the same fire; it appeared, from the experiment, that a ton of the chalk would have given 36 pounds more of lime than a ton of the spar which gave the least quantity of lime, and that the spar which gave the most lime from a ton, exceeds that which gave the least by 27 pounds.

I made another experiment with the same view. Six different calcareous substances, which had been kept in the same room for a month, or more, were put into the same crucible, and exposed to a very strong fire for 24 hours. I weighed them all whilst they were warm, and the quantities of lime which a ton of each would have given, with that degree of heat, are expressed in the following table:

	C.	q.	16.
Chalk:			6
Clitheroe limestone -	11	0	22
Sienna marble	I.I	0	8
Statuary marble -	10	3	21
Rhom. fpar	10	3	2
Crystallized spar -	1.0	I	26

From this experiment it may be inferred, that the difference between the quantities of lime earth, procurable, under similar circumstances, from a ton of chalk, and a ton of hard transparent crystallized spar,

is 92 pounds, or near $\frac{1}{24}$ of the whole weight.

Whether this difference be greater than what might arise from different specimens of the same kind of calcareous fubstance, is more than I dare positively affirm. One specimen of the Courcelles limestone we have feen, gave after the rate of 11c. 2q. 2lb. from a ton of the crude stone; another calcined in the fame kiln gave only 11c. oq. 1lb. from a ton, the difference is 57 pounds, or about 40 of the whole weight. Different pieces broken even from the same lump of chalk, limestone, marble, and almost every other calcareous substance, seldom consist of precisely the same materials; this is obviously feen in buildings and pavements, made either with

with marble, Ketton, or Portland ftone; there may generally be obferved hard knobs, which do not wear away fo fast as the other parts of the stone; and those who are accustomed to faw any of these substances are fully fensible of this diversity of structure in the same block of stone, from the greater difficulty of cutting some parts of it than others. I broke the fame small lump of chalk into four different pieces, and calcined them for different lengths of time, with a view of feeing whether there was not fome regular proportion with respect to the time according to which the quantity of lime procurable from chalk would vary. I broke also the fame lump of Clitheroe limestone into four small pieces, and calcined them

them for different lengths of time with the same intention, the result of the experiments is expressed in the annexed table.

	Lime			
	from a	I		
	ton of	ľ		
Chalk calcined 4 hours	11 1 21			
7 hours -	11 2 18			
10 hours -	11 2 14			
24 hours -	1116			
Clitheroe limestone calc. 4 hours	11 1 17	-		
7 hours	1101			
10 hours	11.1 9			
24 hours	11 0 22	1		

The reader will perceive that these experiments did not answer my intention in making them, since there does not appear to be any regular decrease of lime with the increase of the time of calcination; but they probably point out to us a difference

in the composition of the different specimens; and, indeed, in the chalk which was burned for 7, as well as in that which was burned for 10 hours, I could discern, after calcination, some small specks of iron which were wholly invisible before calcination.

Mr. Whitehurst * has favoured the world with some very interesting observations, concerning the strata in Derbyshire; the following is his account of their respective thicknesses, and of the order in which they succeed one another; No. 1. denoting the uppermost stratum.

^{*} See his Appendix to the Inquiry into the State of the Earth.

1. Grit - 120 yards

2. Shale - 120

3. Limestone 50

4. Toadstone 16

5. Limestone 50

6. Toadstone, 46

7. Limestone 60

8. Toadstone 22

9. Limestone not cut through.

These several strata of limestone, are each of them divided into layers, which have very different appearances. Thus No. 3. which is 50 yards in thickness, may be considered as consisting of 5 distinct layers. The 1st layer, which is contiguous to the shale, is the black Derbyshire marble; the 2d is called by the miners, snail horn marble, from its abounding with screw-stones, and sish shells; the 3d is a compact grey limestone, with several large crystalline specks

in it, but with few shells; the 4th has rather less specks, and is whiter than the 3d; the 5th layer, which lies immediately over the toadstone, is likewise a grey limestone. I examined the relative weights of the black marble, and of the second, third and fourth layers of the stratum, No. 3. with great attention, and also the quantities of lime, which a ton of each would yield; the several specimens were calcined in the same crucible, for the same length of time.

Weight of a cubic foot, of the crude stone.		Weight of lime from a ton.			
1997 T	Ounces.	C. q. 1b.			
Layer 1.	- 2690	11 2 7			
2.	- 2685	11 1 7			
3.	- 2640	11 0 15			
4.	- 2650	11 1 4			
Medium	2666	11 1 81			
. 6-1-		Ite			

It appears from these experiments, that these 4 layers of the same stratum of limestone, do not lie in the earth according to their weights, the uppermost layer being the heaviest, and the third layer being lighter than that either immediately above or below it. The quantity of lime, which a ton of each would yield, feems to have some dependence on their weights; the heaviest layer yielding the most, and the lightest layer yielding the least lime, from the same weight of stone *.

I

^{*} This observation is not true, I think, concerning calcareous substances in general, for a piece of Derbyshire watricle, which was 30 ounces in a cubic foot heavier than the Derbyshire black marble, being calcined in the same crucible with the marble, gave only 11 c. oq. 11 lb. of lime, which is 52 pounds in a ton less than the marble gave.

I have now given an account of 12 experiments made by other authors, and of 32 made by myself, on calcareous substances of different kinds and countries, the medium quantity of lime procurable from a ton of these substances, will be found to amount to 11 c. oq. 25 lb. and consequently the medium loss of weight will be 8 c. 3 q. 3 lb.

When compact masses of any fort of lime are exposed to the air, even in a room sheltered from rain or dew, they soon begin to crack, and in no great length of time they fall into a powder, and receive a considerable increase of weight. The time requisite for effecting this change, depends much upon the quantity of the surface of the lime which is exposed to the air, partly, I believe, but I am vol. II. O not

not certain, upon the degree of humidity reigning in the atmosphere, and partly upon the nature of the body. A piece of statuary marble was converted into lime on the 10th of Feb. 1779, before its calcination it weighed 540 grains, after calcination, and whilst it was yet warm from the fire, it weighed 304 grains; this last quantity was laid upon a piece of clean paper, put into a drawer of my fludy table, and weighed at different intervals, till it had acquired its utmost increase of weight, which it attained on the 4th of March, it then weighing 515 grains. I weighed this lime for two months afterwards, at different times, but it still weighed the same. Another quantity of lime from statuary marble, was examined in the same way, and it acquired

quired its greatest increase of weight in twenty-two days. It did not feem to me, that any other kind of calcareous fubstance, when reduced to lime and exposed to the air, acquired its greatest increase of weight fo speedily as statuary marble; I make this observation with diffidence, for I have neither tried all the forts of calcareous substances, nor any of them under precisely the same circumstances. There is far greater trouble in making experiments, than those, who have not been accustomed to the business, can readily conceive; many niceties are to be attended to, the least of which being omitted, the conclusion becomes doubtful; the mind, moreover, having once acquired the striking outlines of knowledge, has not always

02

patience

patience to attempt the filling up the minuter part of the defign, especially if its attention can be but accidentally employed upon the subject.

Whoever undertakes to ascertain the time in which lime, prepared from different substances, acquires its greatest increase of weight by expofure to the air, would do well to take equal quantities of the limes, whilst warm from the fire in which they were made, to reduce them immediately to powders equally fine, to expose the powders to the air, in a room free from dust, and to weigh them at stated intervals. Or theexperiment may be varied by taking, instead of powders, equal in weight and fineness, solid pieces equal in bulk and furface, fuppose a cubic inch of each fort, and I question not but

but some interesting conclusions, relative to the attractive powers of the different substances, might be derived from experiments of this fort, carefully and repeatedly made.

The powders, into which the limes of different substances are resolved by exposure to the air, have not all the fame appearance; those of Statuary marble, Dove marble, Portland stone, Ketton stone, and, probably, feveral other forts, are composed of little globules visible to the naked eye; whilft those of chalk, Sienna marble, and spar, have no appearance of globules, nor do they feel fo harsh and gritty to the touch, as the others do. The whitest of all the limes, which I have ever feen, is that which may be obtained from the crystallized spar before mentioned; statuary marble,

03 and

and Portland stone, give very white limes, but they are many degrees less white, than that from crystallized spar. The limes from Sienna marble, chalk, rhomboidal spar, and Ketton stone, have a yellowish cast.

Several experiments were made, in order to ascertain the utmost increase of weight, which different forts of lime can acquire by exposure to the air. The limes were all loofely folded up in clean paper, laid in the closet of a room where there was a constant fire, and weighed at different intervals, till they had acquired their greatest increase of weight, which some of them did not do in less than three quarters of a year. The general refult of the experiments is expressed in the following table; where the first column contains the names of the substances, from which the limes were prepared, the fecond expresses the weight, to which a ton of each fort of lime would increase by exposure to the air, and the third shews the quantity of the increase in a ton.

ng'	C. q. 1b.	C. q. 1b.
Sienna marble -	35 0 12	15 0 12
Dove marble	35 0 9	1509
Portland stone -	34 3 21	14 3 21
Statuary marble -	34 2 0	14 2 0
Rhomboid. trans. spar	34 0 16	14 0 16
Purbeck stone	34 0 8	140 3
Crystallized spar -	33 1 25	13 1 25
Rhomb. opaque spar	32 I 21	12 1 21
Clitheroe limestone	32 1 15	12 1 15
Ketton stone	31 3 13	11 3 13
Chalk	30 2 9	10 2 9

Hence it is evident, that the greatest increase of weight which a ton of

04

lime,

lime, of the feveral forts here mentioned, would acquire by exposure to the air, amounts to rather more than three quarters of a ton, and the least amounts to above half a ton. This observation is worthy of notice in a practical view; lime is fometimes fold by weight, and it is obvious, that the feller will be a very confiderable gainer, if, after having drawn his kiln, he lets his lime remain exposed to the air for a few days before it is fold. I have frequently observed pieces of new burned lime, daily increafing at the rate of one hundred weight per ton, for the first five or fix days. The farmer too, in liming his land, should contrive to carry out his lime as foon as possible after it is burned, he may otherwise for every ton, have the trouble of carrying a ton and a half, or more.

Lime which has once acquired its greatest increase of weight, does not lose any part of what it has acquired by fubfequent exposure to the air, even during the heat of fummer. Several forts of lime, which I apprehended had gained their greatest increase of weight in April and May 1779, were weighed at different times during the fummer of the fame year, which was frequently very hot, but I did not observe that any one of them was diminished in weight by the action of the heat: let the matter, therefore, which is attracted by the lime from the air be what it may, it is a permanent substance, and not subject to evaporation during fummer. Hence it cannor

cannot be doubted, that the foil upon which lime is spread acquires a great increase of matter; every ton of lime attracts above half a ton of fome fort of matter or other from the air, and adds it to the earth; now this matter would not have become united with the earth without the intervention of lime: but whether any part of the advantage of liming, where the foil is bad or fcanty, may be attributed to this increase of the quantity of matter which is derived from the air to the earth, is a question which I have not skill enough in agriculture to decide.

I have been told by a gentleman of fortune in Derbyshire, that he has frequently, with great success, spread 1000 Winchester bushels of lime upon an acre of ground: let us fuppose a Winchester bushel of Derbyshire lime to weigh 100 pounds, then will 1000 bushels weigh 100000 pounds, or above 44 tons: and supposing 1 ton of such lime to gain only 14 hundred weight by exposure to the air, then will the whole acre receive an increase of soil, from the lime which is spread upon it, equal to above 30 tons in weight beyond the weight of the lime.

Having estimated the loss of weight sustained by different calcareous substances during their calcination, and also the gain of weight which the limes procured from these substances acquire by exposure to the air, it is natural to inquire whether the gain is equal to the loss. Upon the 6th of March I converted

into lime 204 grains of dove marble, the lime weighed whilst hot 116 grains; upon the 5th of the following November the lime weighed 203 grains. This lime was frequently weighed from March to November, and if it should be supposed that half a grain was insensibly lost by frequent weighing, then we must conclude that this kind of lime gains by exposure to the air, just as much as the marble it is prepared from loses by calcination. Upon a repetition of this experiment with another specimen of the dove marble lime, I found the result to be as accurately, as can be expected, the fame. If we make no allowance for any loss of weight by repeated weighings, then the increase of weight by exposure to the air must be esteemed less

less than the loss of weight by calcination, by about one four hundredth part of the weight of the marble.

Some dry chalk, weighing 120 grains, was reduced by calcination to 68 grains of lime; this quantity of lime became, by exposure to the air, when it had acquired its utmost increase of weight, 104 grains; that is, it wanted 16 parts in 120, or between one seventh and one eighth of the original weight of the chalk.

The dove marble and the chalk are the two extremes of all the fub-flances I have tried; no kind of lime regained fo much weight as that from dove marble, and none fo little as that from chalk. Philosophy may be well employed in accounting for this diversity; I am only interested

terested at present in establishing the fact, which seems not to have been sufficiently understood by chemists of deservedly great eminence. M. Macquer says "quicklime combines with the moisture of the air which it seems capable of attracting, by the moisture thus attracted the weight of the quicklime is doubled *." M. Baumè weighed some lime very accurately, and though he kept it in a cellar

* Chem. Dict. by M. Macquer, artic. Quicklime in the English translation — the original of this work is excellent in its kind, and it is greatly improved by the very judicious notes of the translator. In justice to M. Macquer it ought to be observed, that in the second English Edition of his Dictionary, the passage quoted in the text is greatly altered, there is no mention made of the moisture of the air, and the quicklime is only said to recover a great part of its original weight, by exposure to the air.

a cellar for feveral years, yet it never regained the weight of the calcareous earth, from which it had been prepared, there was always a deficiency of more than two ounces in a pound*.

I do not question the veracity of either of these gentlemen, or their accuracy in making their experiments; but the properties of the particular limes which they examined should not have been given as characteristic properties of limes in general. No lime that I ever tried was doubled in weight by attracting matter (be it moisture, or other matter) from the air, yet if a limestone could be found, which is not impossible, that lost half its weight by calcination, a specimen of lime from such a limeffone

Chymie par M. Baumè, Vol. I. p. 177.

stone might, perhaps, be doubled in its weight. On the other hand, I only met with one fort of lime, that from chalk, which in its increase feemed to fall so far short of the original weight of the substance from which it was made, as to want more than two ounces in a pound, or between one seventh and one eighth of the whole weight. My experiment in this particular instance, sufficiently coincides with the too general observation of M. Baumè.

The chalk or clunch of this country is not a pure calcareous earth, it contains a portion of fand; and hence, when a definite weight of this chalk lime is exposed to the air, it cannot acquire as much increase of weight, as the same quantity of purer lime would do: for the sand, which

which is mixed with the lime, is of a very different nature from the lime, and does not attract any thing from the air. This observation may be extended to different sorts of limestone, and it may suggest one reason for the diversity, in the strength of different sorts of lime, when used either in building or in agriculture.

The table in which the increase of weight acquired by different sorts of lime, in consequence of their exposure to the air, is expressed, was made with great accuracy; yet is it not to be considered as universally true, even of the substances there mentioned: for there is great reason to believe, that the quantity of matter, which the same sort of lime can attract from the air, depends very much upon the degree of heat with which vol. II.

the lime has been burned; there is a certain definite degree of heat requisite to make the lime attract the greatest possible quantity from the air. When the heat is not sufficient to convert the whole of the fubstance into lime, then that part which is not changed into lime, will not contribute any thing to the increase of the weight of the lime when exposed to the air, inasmuch as it possesses no quality of attracting any thing from the air. And, I believe, the observation is equally true, when the heat has been more than sufficient to convert the whole of the substance into lime. It has been before mentioned, that 6 different calcareous substances were changed into lime, by being exposed to a very fierce fire for 24 hours: this

this experiment was made in November, 1780; I have frequently weighed the limes fince that time; they have all of them acquired their greatest increase of weight, for on weighing them in January, 1781, I found that they had not gained any increase of weight in an interval of three months. The following table expresses, in the 2d column, the increase of weight which a ton of these substances would have gained, and the third column expresses the increase which a ton of the same fubstances would have gained had they been only exposed to the same fire for 4 hours.

	C.	q	. 1b.	C. q. 11	b.
Sienna marble -	8	1	15	15 0 1	2
				14 0 1	
Statuary marble -	8	0	0	14 2	0
Chalk	7	1	13	10 2	9
Clitheroe limestone -	6	2	9	12 1 1	5
Crystallized spar -	6	0	0	13 1 2	5

These experiments clearly prove the great utility of burning lime with a definite heat, for the excellency of lime, to whatever purpose it be applied, depends, probably, upon its disposition to attract that matter from the air, which it has loft by calcination; and we fee that none of the limes, which were burned for 24 hours, attracted fo much from the air, as those did which had been more moderately burned; the difference is very confiderable in all the instances. Would

not a greater degree of heat have still further deprived lime of its property of attracting matter from the air, and thus have made it approach nearer to the nature of glass?

We have feen how greatly calcareous substances are diminished in weight by being calcined, — do they receive any alteration of bulk during that operation? Having proposed. this question to various lime-burners, in different parts of the kingdom, I found some were of opinion that the chalk or stone swelled a little, others that it shrunk a little during calcination, and a third fet thought that it underwent no fort of alteration: the most obvious inference from these different accounts seems to be, that calcareous substances

do

do in this particular differ from each other.

I took a piece of blackish marble four inches in length, half an inch broad, and one quarter of an inch thick, and having placed it in a proper vessel, and covered it with sand, it was exposed to a very sierce fire for three hours; the marble thereby became perfectly white and friable as calcined bones, but I could not observe that it had undergone the least change in any of its dimensions.

I cut a piece of chalk till it was an inch in length, half an inch in breadth, and as much in thickness; after it was calcined its dimensions were not sensibly altered.

A piece of rhomboidal spar from Derbyshire, and a piece of white marble, marble, were severally measured before and after calcination, but no difference could be observed in the dimensions of either of them.

I thought the length of a piece of Sienna marble, in one experiment, was diminished about one fistieth part by calcination, but I was probably mistaken; for in another piece, above two inches in length, I took, with a pair of compasses, the distance between two points upon its surface before calcination, and found that distance precisely the same after calcination.

A piece of Clitheroe limestone, which had been calcined for four hours, appeared to be diminished in length one part in twelve; another piece which had been calcined ten hours was unaltered in length, and

P 4 thick-

thickness; and so was a piece which had been calcined 24 hours.

I took a piece of chalk, which had been dried by the fun and air, and having shaped it into a square, each fide of which was four inches, the thickness being two inches, I put it into a lime kiln; it was kept there as long as chalk which is burned into lime usually is, when it came out of the kiln, I compared it with the standards of its several dimensions, which had been accurately taken before calcination, and could not discover that it had suffered the least change either in length, breadth, or thickness. This experiment was repeated with wet chalk, but neither was this altered in its dimensions by calcination. Lastly, I took a flat piece of chalk, about

one fourth of an inch in thickness, and calcined it for 24 hours; the length of this chalk was three inches, and it was diminished by calcination one tenth of its length.

The reader is possessed of all I know from my own experiments upon the fubject; but I will not conceal from him the opinion of M. Baumè, who esteems the diminution of the bulk of calcareous substances during calcination, as one of their most distinguishing properties. He does not, indeed, mention any experiments which he had expressly made, with a view of deciding the question, but I cannot suppose, that so able a chemist would speak from conjecture, when he affirms, that calcareous substances are fometimes diminished half their bulk bulk during calcination*; and therefore I should apprehend, that the calcareous substances, which he used, were different from any of these on which I made my experiments. Be this as it may, his conclusion is, if at all, certainly not generally to be admitted.

The experiments, by which the nature of any particular fort of earth is chemically investigated, are principally of two kinds; one consists in observing its solubility or insolubility in different menstruums, the other in noticing.

* Le second phénomene que la terre calcaire présente après sa calcination, est sa diminution de volume — la retraite de ces parties, pendant leur calcination, est quelque fois si grande, qu'elle va jusqu' à la moitiè de leur volume. Chym. par M. Baumè, Vol. I. p. 182.

noticing the changes produced in it by the action of various degrees of heat. We may form a general idea of the operation of fire upon calcareous fubstances, from the experiments which have been before related; I did not spare either time or labour, nor was I fensible of any want of care, in making them; yet I cannot help apprehending, that a numerous repetition of similar experiments, might lead to some general conclusions, which have escaped my observation. The following experiments can hardly fail of being acceptable to the reader, as they tend greatly to corroborate what has already been inferred, concerning the nature of calcareous earths. We have concluded, that twenty hundred weight, or a ton of any calcareous fubstance, consists of between eight and nine hundred weight of some matter or other, which is diffipated during calcination, and of between eleven and twelve hundred weight of earth, which cannot be diffipated in that degree of heat: now if it can be shewn, by a way wholly different from that of calcination, that a ton of any calcareous body, does really confift of about twelve hundred weight of earth, and of about eight hundred weight of a volatile substance, we cannot entertain any further doubt concerning the proportion of the constituent parts of calcareous substances.

If the reader has not been accustomed to the making of chemical experiments, and yet should be desirous of ascertaining, from his own observation, the truth of such as I am

going

going to mention, he may do it at a very easy rate; he need only procure from his apothecary, a few ounces of the acid of sea salt, and a Florence slask, and he will be furnished with the main part of the apparatus.

I took a Florence flask, and poured into it a small portion of the acid of fea falt diluted with water; the flask and its contents were then weighed in a pair of scales, which turned with a quarter of a grain, the weight was noted down. I then dropped into the acid, by a very little at a time, 20 grains of a calcareous fubstance, and stopping gently the top of the flask with my finger, till the whole was dissolved, the slask was weighed again. Now it is obvious, that if nothing had escaped during the folution, the weight of the flask

and its contents, after the folution of the calcareous fubstance, would have exceeded its weight before folution by 20 grains. There was, however, a very confiderable loss of weight, in all the substances which I tried. instead of 20 grains, a ton, or 20 hundred weight of each substance, had been dissolved, and no notice had been taken of any weight less than 1/4 of an hundred weight, the weight of the earth, or other matter remaining in the bottle after folution, would have been expressed by the second column of the following table, and the weight of the matter lost during folution by the third.

	C.q.1b. C.q.1b.
Namure black marble	13 3 0 6 1 0
Clitheroe limestone -	13 10 6 30
Chalk	1230 710
Ketton stone	12 3 0 7 1 0
Portland stone	12 1 0 7 3 0
Purbeck stone	12 1 0 7 3 0
Mother of Pearl	12 2 0 7 2 0
Dove marble	1200 800
Blue-veined marble -	1200 800
Purple-veined marble -	1200 800
Statuary marble	12 0 0 8 0 0
Rhomboidal spar	1200 800
Crystallized spar * -	1200 800

The

examined, lost 8 parts in 20 during their solution, which is the very proportion assigned by Dr. Black, in his most ingenious Essay, (Edin. Ess. Vol. II. p. 104.) for the loss sustained by chalk; it will appear, however, from what follows, that pure calcareous substances, probably lose 9 parts in 20 of their weight, by being dissolved in an acid.

The Namure black marble and the Clitheroe limestone, threw up an oily fcum during solution, and left a large portion of black fediment, which probably was iron. The chalk had a whitish sandy sediment, the Ketton stone a yellowish one, Portland and Purbeck stone a white one, which looked like particles of fand, and was gritty between the teeth; Mother of Pearl left feveral foft infoluble flakes floating on the top of the acid, the other bodies either gave no fediments, or very minute ones.

When I first began making these experiments, I was accustomed to weigh the slask as soon as the solution was ended, and this lead me into an error in estimating the quantity lost during solution; for, upon further trial, I always sound, that the weight

weight of the flask and its contents, taken, as accurately as possible, as foon as the folution was finished, was diminished very fensibly in the space of three or four hours. I was at first inclined to attribute this diminution to the evaporation of a part of the fluid; but the true cause is this, the weight of the air remaining in the flask after solution, is greater than the weight of an equal bulk of atmospherical air. This is easily proved, either by fucking through a pipe the air contained in the flask, or blowing it out with a pair of bellows, fo that the flask may be filled with common air; for the flask will then be found to weigh less than it did before. Sucking out the air is a troublesome operation, for the air has a disagreeable taste in the mouth, and VOL. II.

and if suffered to pass into the lungs, might be noxious. This disagreeable taste is not to be attributed to any subtle particles of the acid, which may be supposed to float in the inside of the slask, but to the air contained in it, for after the air has been thoroughly exhausted, so that the slask becomes full of only common air, no further taste is perceived.

I took a Florence flask, which would hold 26 ounces troy of water; into this flask I poured a two ounce measure of the acid of sea salt, and dissolved slowly in the acid a quantity of the purest calcareous spar, the bottle was weighed as soon as the solution was ended: I then permitted it to stand quiet for two hours, and at the expiration of that time, I blew into it with a pair of bellows till the

the air became tasteless, the bottle was then weighed, and it had loft 7 grains. The weight of common air filling a flask, holding 24 ounces of water, is about 14 grains; the weight of the fame quantity of the kind of air which filled the flask, immediately after the folution of the calcareous substance, was 7 grains more, or 21 grains; hence the weight of common. air, is to that of the air which filled the flask after solution, as 14 to 21. or as 1 to 1½. I do not offer this conclusion to the reader as an accurate one, but it is probably not far from the truth.

The circumstance of the weight of the stask being greater, immediately after the solution was finished, than it would have been if filled only with common air, was not neglected in

Q2 making

making the experiments mentioned in the table; it was not, however, attended to with fuch a fcrupulous exactness, as it ought to have been: I made therefore the four following experiments with the greatest care. The feveral folutions were flowly made, to prevent any loss of the acid, and the flask was not weighed till 20 hours after the folution was finished; in which time the air in it had become tasteless; nor did the flask and its contents suffer any further diminution of weight, by a longer exposure to the air.

120 gr. of white marble lost by solut. $53\frac{1}{2}$ gr. 120 gr. of crystal. spar lost by solution 54—
120 gr. of rhomb. spar lost by solution 54—
120 gr. of Matlock petrefaction—54—

The lofs of weight fustained by the marble during folution is fo nearly nearly the same with that of the other three bodies, that its difference may probably be referred to some unavoidable inaccuracy in making the experiment; if this be admitted, we may reasonably conclude, that equal weights of pure calcareous substances, contain equal quantities of a volatile matter, which is dispersed during solution, and that this volatile matter amounts to 54 parts in 120, or 9 hundred weight in a ton, the earth amounting to 11 c.

Since calcareous substances lose nearly equal portions of their weight, whether they are calcined in the fire, or dissolved in acids, it may be presumed, that the matter which is lost is of the same nature in both cases; this matter is a species of air. The reader may easily convince himself of

this.

this by fastening a flaccid bladder over the mouth of a Florence flask, or other veffel, in which any calcareous substance is in the act of solution, for the bladder will presently be blown up, by the matter which issues through the neck of the stask; and if the neck of the inflated bladder be tied, and the bladder be in that state removed from the flask, it will not become flaccid again, but remain blown up; which is a fufficient proof that it is filled with a species of air. The air thus separated from calcareous substances, is very different from common air, in many particulars. We have before feen, that the weight of a given bulk of this air, is as much greater than the weight of the same bulk of common air, as 21 is greater than 14, or as 3 than

than 2. - This air, it has also been remarked, has a fingular tafte, and common air has no taste. - This air extinguishes flame and animal life, and common air fupports both. This air by being shaken in contact with water, or otherwife mixed with it, impregnates the water with an acidulous taste, but common air produces no fuch effect on water. - This air is as much a constituent part of the atmosphere as common air is, for a ton of lime will attract half a ton of this air from the atmosphere. The particles of matter constituting light, are supposed to be of different magnitudes: are the particles of matter which constitute atmospherical air of different magnitudes? - Does the fmell of a room newly plastered, proceed from particles of matter emitted Q4

emitted by the plaster, or from the air of the room having undergone a decomposition, in consequence of the lime having absorbed one of its component parts?

When any calcareous earth has been dissolved in an acid, it has lost its air, and is much diminished in weight; it has undergone as great a decomposition, as if it had been calcined. Calcined calcareous earth or lime, may be restored to the state of crude calcareous earth or limestone, by exposure to the air; in consequence of fuch an exposure, it, in a greater or less space of time, attracts from the air a part at least of the principle, which it had loft during calcination; but when a calcareous earth has been dissolved in an acid, and is thereby deprived of its air, it

may be wholly reftored to the state of a crude limestone, by an almost instantaneous process. Suppose 20 pennyweights of marole, to have been diffolved in a proper quantity of the acid of sea salt, then will these 20 pennyweights have lost 9 parts of their weight; the earth remaining in the acid will only weigh in pennyweights. Salt of tartar, pot-ash, and other fixed alkalies, contain, in their crude state, a great portion of fixed air, of the same nature with that which constitutes 9 parts in 20 of the substance of marble, and other calcareous bodies. The acid of fea falt, and all other acids, have a stronger tendency to unite themselves with the earthy part (if the expression may be admitted) of fixed alkalies, than to continue united with the earthy

earthy part of marble, or any other calcareous body. If then, into the acid, in which 20 pennyweights of marble have been dissolved, and which really confifts of the acid united with 11 pennyweights of earth, we pour a folution of falt of tartar, or potash, the acid will quit the earth of the marble, and unite itself with one of the constituent parts of the alkali; the earth of the marble is by this means fet at liberty, and one of the constituent parts of the alkali is also set at liberty, namely, its fixed air; these two will unite together, and by their union they will form an earth of the same nature as crude limestone, the weight of which is found to be equal to the original weight of the marble, or 20 pennyweights.

From

From the various experiments which have been here faithfully related, without any previous attachment to fystem, it seems as if we might conclude, that pure calcareous fubstances are composed of 9 parts in 20 of a volatile substance, which is dispersed, not only during the calcination, but during the folution of the substances in an acid, and of 11 parts in 20 of an earth which is generally known under the name of lime. Several authors of distinguished reputation in chemistry have thought, that water was an essential constituent part of calcareous fubstances, and from particular instances they have endeavoured to ascertain its quantity in general. The experiments which I have made do not tend to establish this opinion.

- Into a new glass retort I put two ounces of crystallized spar, and having fitted a clean receiver of flint glass to it, I exposed it at first to a gentle fire, which was increased, by degrees, till it became strong enough to melt the retort; during the whole of the operation I did not observe that any water was separated from the spar, the transparency of the receiver was not fo much as tarnished by a vapour. From this experiment I would conclude, that this species of calcareous earth does not contain any water, which is separable from it in a degree of heat sufficient to melt glass. - I took an earthen retort, and put into it fix ounces of crystallized spar, and exposed the retort to a very strong fire till the spar had lost one third of its weight, there

there was not a drop of water found in the receiver. The retort, when taken out of the fire, appeared to be cracked, fo that this experiment is not quite fo convincing as the preceding, though, perhaps, fufficiently fo to make us doubt concerning the existence of water as a component part of this kind of spar. - I took 720 grains of Derbyshire watricle, which is the fubstance of which the ornamental columns feen on chimney pieces is generally formed, and distilled them with a violent fire in an earthen retort, till they were reduced to 400 grains (that is, till they gave after the rate of 11 c. oq. 12 lb. of lime from a ton of the watricle), but I did not find any sensible portion of water in the receiver; it was indeed clouded with a vapour, vapour, but this vapour I think arose from the dampness of the retort, or of the substance used in fastening the receiver to the retort, or from something or other unconnected with the watricle.



E S S A Y VII.

Of Clay, Marle, and Gypseous Alabaster, or Plaster-stone.

A Rgillaceous earth, or clay, may be distinguished from every other fort of earth, by its tenacity when wetted with water, and by its growing hard when exposed to the fire. We may levigate sand, chalk, or plaster-stone into very fine powder, but these powders, when kneaded with water, will not form a tenacious

cious ductile mass, capable of being moulded and turned at the pottery wheel, or of being hardened in the fire like clay. Even clay itself loses its tenacity by being baked in a gentle fire: a potter or a pipe-maker will in vain attempt to substitute the powder of potsherds, or of broken pipes, in the place of clay; these powders may be serviceable, on some occasions, when mixed with clay, but they cannot, on any, supersede its use *.

The whitest clays are esteemed the purest, but even these, besides other impurities, generally contain a very consider-

* In the Mem. de l'Acad. des Scien. de Prusse, 1749, there are some experiments tending to prove, that the tenacity of clay is owing to some inflammable matter which is mixed with it, and which is easily consumed in the sire.

confiderable portion of fine fand. I took 16 ounces of the finest pipe clay from Dorfetshire, and by repeatedly washing it in large quantities of water, and pouring off the turbid water, I collected a fandy fediment amounting, when well dried, to 3 ounces. I have no doubt that this clay contained a much greater proportion of fand, than what I had been able to collect; for the white particles which had been fuspended in the water, certainly consisted in part of a fand of a finer grain than what had fettled to the bottom, for they were very fenfibly gritty between the teeth. It may eafily be conceived that in washing clays, the finest part of the fand contained in them will remain suspended in the water, and that on this account, the R VOL. II.

fediment collected at the bottom of the vessel, in which the operation is performed, will not give the true proportion of the sand which enters into their composition. In confirmation of this idea, we have been instructed, by the experiments of a very able chemist, to consider sine white clays, as consisting of about 3 parts in 8 of true argillaceous earth, and of about 5 parts in 8 of sand, or earth, resembling powdered slints *.

All forts of earthen wares, from the coarfest pots, to the finest pieces of either Asiatic or European porcelane, consist either wholly or principally

* M. Marggraf's Opus. Chy. Vol. II. p. 171.— Is it possible, by any artificial or natural comminution of its parts, to reduce the sand sound in clay into a true argillaceous earth? cipally of clay. There are a great many forts of clay which differ from each other in colour, in tenacity, in the degree of contraction which they fuffer in being burned, in their power of relisting the action of fire without being melted, and in many other properties; and hence we need be at no pains to prove, that the properties of earthen wares must be very various, according to the properties of the clays from which they are formed; and this variety becomes still greater, when we take into confideration the ingredients which are purposely mixed with the natural clays.

The flint, or white-stone ware, is made in Staffordshire, and other places, in the following manner. - Tobaccopipe clay which they have from Dorset-

R 2

Dorsetshire, is beat much in water; by this process the finer parts of the clay remain suspended in the water, whilst the coarser sand, and other impurities, fall to the bottom. The thick liquid, confifting of water and the finer parts of the clay, is further purified, by being passed through hair and lawn fieves of different degrees of fineness: the clay is then fufficiently prepared to be mixed with powdered flint, the other ingredient in the stone-ware. They use annually in Staffordshire about 5000 tons of flint, which they have from Hull. They have a tradition concerning the first introduction of flint into their potteries, which is briefly this, - a Staffordshire potter, about 80 years ago, in travelling to London, met at an inn upon the road

road with an hoftler, who undertook to cure a disorder in his horse's eye. The hoftler took a flint stone, and having calcined it for a sufficient length of time in a hot fire, it became very white; he pounded it into a fine powder, and blew some of it into the eye of the animal: the potter took the hint, conceiving that as flints could be calcined and pounded into a fine white powder, they might be used in conjunction with clay to make a whiter ware than the clay would do alone. He amassed large quantities of slints, burned and pounded them in fecret, and found the event answerable to his expectation. The discovery soon became general, and many lives were lost from the powder of the flint being inhaled by the men employed.

in

in pounding it: horses were afterwards used for the same purpose, and for some time past they have been accustomed to grind their flint *. If the flints are pounded, or ground by instruments of iron, the powder is not fo good as it ought to be, for the particles of the metal, which are abraded during the operation, being mixed with the powder, give the ware, when burned, a bad colour.

They formerly were accustomed to grind their flints with Moorstone, or Granite; but of late years a large bed of Chert (a species of slint) has

heen

I suspect the date assigned by this tradition to the potter's discovery, for the grinding of flints is incidentally mentioned as practised at Brosely in the year 1697. Phil. Tranf. No. 228.

been discovered near Bakewel, in Derbyshire, and the Staffordshire and Yorkshire potters prefer it to Moorstone for grinding their flints: it is very hard, and, being itself of the nature of flint, the parts of it which are worn off and mixed with the flints in grinding, do not vitiate the quality of the flint powder. It is fold at the quarries for 8 s. a ton, of which the Duke of Rutland, as lord of the foil, has 5 s. and the workmen the other 3 for raising it. It is reckoned that they annually raife between four and five hundred tons, besides the smaller pieces, which are thrown by as refuse; but which might be calcined upon the spot instead of flint, and being ground there, might answer the purpose of ground flint; though as coals are.

R 4

compa-

comparatively dear at Bakewel, and as there is no navigation from thence into Staffordshire, I am not certain whether the ground Chert could be afforded to the potters at an easier rate than they can prepare their flint. However, Chert is very commonly to be met with in other parts as well as at Bakewel, though not, perhaps, in fuch large quantities, and therefore the hint of using calcined Chert, as a substitute for calcined flint, may be of fervice to those who are better situated with respect to fuel and water carriage, than they are at Bakewel.

When the flints have been properly calcined and ground, they are fifted in water till the water is, as near as may be, of the fame thickness as that in which the clay is sufpended;

pended; then the liquid clay and flints are mixed together in various proportions, for various wares, and left to fet; the mixture is then dried in a kiln, and being afterwards beaten to a proper temper, it becomes fit for being formed at the wheel, into dishes, plates, bowls, &c. When this ware is to be put into the furnace to be baked, the feveral pieces of it are placed in cases, made of clay, cailed Seggars, which are piled one upon another in the dome of the furnace; a fire is then lighted, and when the ware is brought to a proper temper, which happens in about 48 hours, it is glazed by common falt. The falt is thrown into the furnace (through holes in the upper part of it), by the heat of which it is instantly converted into a thick

a thick vapour, which circulating through the furnace, enters every Seggar through holes made in its fide (the top being covered, to prevent the falt from falling upon the ware) and attaching itself to the furface of the ware, it forms that vitreous coat upon the surface which is called its glaze.

This very curious method of glazing earthen ware, by the vapour of common falt, was introduced into England from Holland, at least it was introduced from thence into Staffordshire, about 80 years ago by two Dutch men. An old man informed the person, from whom I had the account, that he remembered, when he was a boy, running with others to help to extinguish, what from the smoke they apprehended

to be a fire in the pottery where the Dutchmen were working, but that their entrance was opposed by the proprietors of the pottery, who were unwilling that the cause of the smoke, which was the common salt they were using in glazing their ware, should be generally known.

The Yellow or Queen's ware, is made of the same materials as the flint ware, but the proportion, in which the materials are mixed, is not the fame, nor is the ware glazed in the same way. The flint ware is generally made of 4 measures of liquid flint, and of 18 of liquid clay; the yellow ware has a greater proportion of clay in it; in some manufacturies they mix 20, and in others 24 meafures of clay, with 4 of flint. These proportions, if estimated by the weight

weight of the materials, would probably give for the flint ware, about 3 hundred weight of clay to 1 hundred weight of flint, and for the yellow ware fomewhat more clay. The proportion, however, for both forts of ware, depends very much upon the nature of the clay, which is very variable even in the same pit: hence they cannot be certain of the exact quantity of flint, which they ought to mix with the clay, till they have made some trial of the quality of the clay, by burning a kiln of the ware. If there is too much flint mixed with the clay, the ware, when exposed to the air after burning, is apt to crack, and if there is too little, the ware will not receive the proper glaze from the circulation of the falt vapour. This glaze, even when it is most most perfect, is in appearance less beautiful than the glaze on the yellow ware. This yellow glaze is made by mixing together in water, till it becomes as thick as cream, 112 pounds of white lead, 24 pounds of ground flint, and 6 pounds of ground flint glass. Some manufacturers leave out the glafs, and mix only 80 pounds of white lead with 20 pounds of ground flint, and others doubtless observe different rules, of which it is very difficult to obtain any account. The ware, before it is glazed, is baked in the fire, by this means it acquires a property of strongly imbibing moisture, (we perceive something of this in the force with which a new pipe sticks to the lips, though the pipe has received a kind of glaze by being rubbed with bees wax after being being baked) it is therefore dipped in the liquid glaze and fuddenly taken out, the glaze is imbibed into its pores, and the ware presently becomes dry; it is then exposed a fecond time to the fire, by which means the glaze, which it had imbibed, is melted, and a thin glaffy coat is formed upon its furface: the colour of this coat is more or less yellow, according as a greater or less proportion of lead has been used. The lead is principally instrumental in producing the glaze, as well as in giving it the yellow colour; for lead, of all the substances hitherto known, has the greatest power of promoting the vitrification of the substances with which it is mixed. The flint ferves to give a confiftency to the lead, during the time of its vitrification.

tion, and to hinder it from becoming too fluid, and running down the fides of the ware, and thereby leaving them unglazed. The yellowish colour, which lead gives when vitrified with flints, may be wholly changed by very small additions of other mineral substances; thus, to give one instance, the beautiful black glaze, which is fixed on one fort of the ware made at Nottingham, is composed of 21 parts by weight of white lead, of 5 of powdered flints, and of 3 of an earthy, or metallic mineral called Manganese.

The powder, into which calcined flints are ground, is whiter than common fand, and of a finer grain; and hence it constitutes, when mixed with clay, a species of earthen ware, superior to that in which sand is used

as an ingredient; the coarse stone ware made at Bristol, is composed of tobacco-pipe clay and fand, and is glazed by the vapour of falt, like the Staffordshire slint ware, but it is far inferior to it in beauty. As our flint ware is superior to the stone ware here mentioned, because it is made of materials, which, though of the same kind, are of a finer quality, than those which enter into the composition of stone ware; so is it inferior to all the forts of Porcelane in whitenefs, and transparency; because powdered flints and tobacco-pipe clay, are neither of them fo white and pure, as the clays and flints of which all porcelanes are made. According to this notion the only difference between Porcelanes and many forts of earthen ware, confifts in the fineness and

proportion of the ingredients; and these causes joined to the different degrees of heat employed in baking different porcelanes, are abundantly sufficient to account for all the varieties observable in the grain, colour, hardness, and transparency of different forts of china.

We are told that the component parts of oriental porcelane, "are (1) a vitrescent stony substance, reduced to an impalpable powder, Petunse. (2) An unvitriable unctuous clay, reduced to an impalpable powder also, Kaolin. These are thoroughly mixed, the latter in as small proportion as possible, and then moulded and baked. (3) A varnish composed of the finest particles of a foapy earth, disfolved in water to the confiftence of a cream, in which, S when a VOL. II.

when dry, the pieces are dipped before they are baked *." The Chinese Petunse differs from powdered flints, in being fusible in a strong degree of heat, whereas flints are not fufible in a fire sufficient for the baking of porcelane, unless they are mixed with fome heterogeneous matter; and this property of the Petunse probably gives to china, a degree of transparency not observable in our flint ware; for the vitrifiable Petunse, when mixed with the unvitrifiable clay, may communicate a degree of vitreoufness to the compound.

The moorstone or granite found in Cornwall, is thought to resemble the Chinese Petunse; and the Scap-rock, which is plentifully met with at the Land's End, is esteemed a species of Kaolin.

Campbell's Surv. of Brit. Vol. II. p. 18.

Kaolin, and is much fought after by the makers of porcelane. The granite is looked upon by mineralogists as a vitrifiable stone; at least, as to the greatest part of it *, and there may, probably, be discovered other stones which possess the same property. The lead mines in Derbyshire abound in two kinds of spar, which are very different from each other in figure, (where the figure is discernible); in weight; and in the change which they undergo from the action of fire. The figure of one of the kinds of spar, is that of a lozenge or rhomb; the figure of the other, is that of a die or cube: a cubic foot of the rhom-

boidal

Exposè au feu, il s' y vitrifie, à l' exception du mica, et du cement qui souffrent la meme violence du feu sans en être altéré. Miner. par M. Val. de Bomare, Vol. I. p. 275.

boidal spar weighs 2700 ounces; a cubic foot of the cubical spar weighs 3219 ounces: the rhomboidal spar, in being calcined in a strong fire, loses near 18 parts in 40 of its weight, and is changed into quick lime; the cubical spar, in the same degree of heat, loses about 1 part in 40 of its weight, and is not converted into quick lime: the cubical spar may be melted in a degree of heat, in which the rhomboidal spar remains unmelted; and from this property, the cubical spar might, probably, be used with advantage by the porcelane manufacturers. Some mines, as those near Critch in Derbyshire, yield no kind of spar but the cubical; whilst others yield only the rhomboidal; and some yield both: I have seen a narrow crack in a limestone rock, coated

coated on one fide with the cubical, and on the other with the rhomboidal spar.

Having fallen into the mention of spars, it may just be observed, that Blue-John, which has, of late years, been fabricated into vafes, and other ornamental figures, is of the same quality as the cubical spar, with respect to its fusibility in the fire; it loses, moreover, its colour, and becomes white in a moderate heat: the weight of a cubic foot of the blueft kind is 3180 ounces, and that of a cubic foot of the least blue is 3140 ounces. This fubstance was first discovered, (or more properly speaking, it first began to be applied to fome use) about 16 years ago, at one of the oldest lead mines in Derbyshire, called the Odin mine, (probably from

its

its being dedicated to Odin, the great God of the northern nations,) at the foot of a high mountain called Mam Tor near Castleton. Spars tinctured with the amethyst colour, have been discovered in other mines; there is great plenty of what they call the chocolate coloured spar, in a mine at Critch (a few miles from Matlock) where I saw, the last year, a piece of oak, which had stood long in the water of that mine, tinged with a deep purple colour; but the greatest quantity of Blue-John is still raised at Castleton; the largest pieces are fold for 9 pounds a ton, the middlefized for 6 pounds, and the least for fifty shillings. - But to return to the confideration of porcelane.

Several European nations, in particular the Germans, the English, the

French, and the Italians, have, fince the beginning of the present century, applied themselves with great industry and ingenuity, to the making of porcelane, and they have all of them arrived at great perfection in the art; though none of the European porcelanes, unless, perhaps, we except the Dresden, can yet be said to equal, both in strength and beauty, the porcelanes which are imported from China and Japan. The Drefden, and the German porcelanes in general, are as unvitrifiable as the Afiatic; whilst most of the others which are made in Europe, may be vitrified by a longer continuation of the heat, in which they are baked. The being or the not being convertible into glass in a strong fire, is one of the principal criterions by which

S 4

connoisseurs judge of the goodness of porcelane, that being esteemed the best which is the least fusible. Porcelane being feldom exposed to a degree of heat, greater than that of boiling water, it feems to be an odd method of judging of its worth, by inquiring whether it is capable of fustaining, unaltered in its form, a degree of heat sufficient to convert many other fubstances into glass; but probably that fort of it is the most hard, and tough, and best capable of bearing the fudden transitions from heat to cold, which is baked with the strongest heat; and, if this be true, then there is a good reason for esteeming that china to be the best, which is the most unfusible, inasmuch as it has, probably, undergone a stronger fire in being baked, than

than the more fufible kinds could

support.

There is some reason for thinking, that the strength of porcelane has fome dependence on its weight, for the more closely its parts are compacted together, the more forcibly, other circumstances being the same, will they refift the impulse of a stroke tending to disunite them. I have estimated the relative weights of most of our English porcelanes; but I forbear mentioning particulars, as I should be forry to fay any thing which might have the most distant tendency to injure any individual; especially as the great price of labour in this country, and, indeed, in all parts of Europe, compared with its price in Asia, must ever render the engaging in a porcelane manufactury

a hazardous undertaking, whilft the importation of Asiatic porcelane is allowed. The best mode of encouraging the European manufacturies of porcelane, would be the imposition of a heavy duty on that which is brought from Asia. It is, I believe, generally ackowledged, that the yellow ware, is far more brittle than the flint ware; the relative weights of a cubic foot of these wares and of East India china, were

East India china 2346
Flint ware - 2188
Yellow ware - 1988

Now supposing a plate of the common yellow or Queen's ware, (for there are very different sorts of it) to weigh 12 ounces; then will a plate of the flint ware of exactly the

fame fize and thickness weigh 13 \frac{1}{5} ounces; and an equal plate of china will weigh 14 \frac{1}{6} ounces; and hence we need not wonder at the great fragility of the common yellow ware, when compared either with china or flint ware. The coarse Bristol stone-ware has nearly the same weight as china, a cubic foot of it weighing 2340 ounces.

The precise meaning of the term marle is not yet fully fixed; it is most generally used to denote an earthy or stony substance, consisting principally of clay and calcareous earth, and falling into powder by exposure to the air. There are several solid strata of stones, such as the Derbyshire shale and toadstone, which moulder into powder by exposure to the air, and yet they are not esteemed marles,

marles, because they do not contain any calcareous earth; there are also limestones which contain portions of clay, and clays which contain portions of limestone, but which not falling into powder by the influence of the air, are not classed amongst the marles: and hence these two properties, of containing calcareous earth, and of falling into powder when exposed to the air, may be esteemed characteristic of marles; and they are, perhaps, the characteristics which are most to be relied on, for as to colour and confiftency marles cannot by them alone be distinguished from several other bodies.

As the use of marle in agriculture, depends in some fort of soils upon the quantity of calcareous earth which

which it contains, and in others upon the clay which enters into its composition, some readers will wish to be acquainted with a general method of ascertaining the exact proportion of clay and calcareous earth, contained in any particular kind of marle.

Take an ounce of the proposed marle, previously reduced into powder, and well dried; pour upon the marle a diluted acid of sea salt; an effervescence will ensue; this effervescence arises from the action of the acid on the calcareous earth, for the acid has no action on pure clay, nor even on clay and sand, as may be seen by pouring a little of it on pipe-clay; when so much acid has been added to the marle that no further effervescence is observed, we

may conclude that all the calcareous earth contained in the marle is now dissolved in the acid: put the whole into a filter; the calcareous earth being diffolved in the acid will pass through the filter, whilst the clay will remain upon the filter: wash the clay, and the filtering paper, by pouring upon them hot water till they are freed from all faline particles; the clay being afterwards dried, as the ounce of marle had been, will shew, by its loss of weight, the quantity of calcareous earth which the marle contained. As to the matter which remains upon the filter, and which has been called clay, it may chance either to be pure clay, or a mixture of clay and fand; if it is the latter, the quantity of fand

may be known by washing it and collecting the sediment.

This method of examining how much calcareous earth is contained in any species of marle, may be usefully adopted also when the clay or marle is to be applied to the making of brick. For if the quantity of calcareous earth is large, the marle in being burned will rather form lime than brick, or the brick at least will foon moulder in the air, in confequence of the calcareous earth falling into a powder like lime. The marle dug out of the same pit is often very different in its properties, some parts of it containing so much calcareous earth, that they may with advantage be burned into lime; whilst other portions of it may be made into good brick. I will illustrate illustrate what has been faid concerning the analysis of marle, by an instance.

We have a stratum of lead coloured clay, a little beyond Magdalen College, on the road to Ely, which burns to a whitish brick: I took four ounces of this clay, moist as it was dug out of a pit, ten or twelve feet deep; by being dried on a hot fire shovel till no more vapour appeared to rife from it, the weight was reduced to three ounces. These three ounces, or 60 pennyweights, were put into a quantity of diluted acid of falt, till no more effervescence was observed, the mixture was filtered, and what remained upon the filter, being dried, weighed 46 pennyweights, the quantity of calcareous earth amounting to 14 parts

in 60, or near \(\frac{1}{4} \) of the weight of the clay when dried. What remained upon the filter was washed in much water, I obtained a fediment amounting to about 1 pennyweight, but it was not a fandy fediment, it resembled an earthy falt, resulting from an union of the acid of vitriol with calcareous earth, which is usually called Selenites; there was also separated, by washing, a quantity of greyish earth, which was chiefly iron.

The moulds, used in making bricks from this clay, are 10 inches in length, and 5 in breadth, and the bricks, when burned, usually measure 9 inches in length, and 4½ in breadth, so that the clay shrinks about 1 inch in 10. But the degree of contraction, which clays undergo VOL. II.

in being burned is very various, and it does not folely depend upon the purity of the clay; for I have been informed by perfons employed in making coarse earthen ware from fimple clay, that the same clay just dug out of the earth, and put into the fire, will contract less, than when it has been sometime exposed to the influence of the atmosphere; for frost more perfectly divides its particles than any artificial process can do: the Chinese are said to let their clay remain exposed to the atmosphere 20 or 30 years, before they apply it to the making of porcelane: and the goodness of common tiles, and bricks, is much increased, by fuffering the clay to lie mellowing for a year or two before it is used.

The clay here spoken of, though it does not contain fo much calcareous earth, as to render it a proper manure for stiff, loamy foils, yet it might probably be used, with great advantage, on those which are light and fandy; inafmuch as by its clayey part (for clay is greatly retentive of humidity) it would contribute to keep the ground from being deprived of its moisture, by the action of the fun and wind during the height of fummer. The quantity of moisture which is imbibed by the leaves of vegetables from the atmosphere, as well as that which is fucked in by their roots, has a great dependence on the moisture of the ground on which they grow; for when the ground is dry, the air incumbent upon it will, comparatively speaking,

ba

be dry also, and the vegetables which grow in that dry air, will lack a part of that moisture which is necessary to their well being, for whether moisture be itself the food of vegetables, or only the vehicle of food, it is indispensably necessary for the promotion of vegetation *.

From the confideration of marle we pass to that of alabaster, which is seldom found in beds, except in conjunction with marle. There is some confusion both in the philosophical and in the common acceptation of the term alabaster, I do not mean merely with respect to the colour and transparency of the substance, but with relation to its constituent parts. This confusion may be

Vegetabilia omnia a liquoribus omnino crescunt. — Newton.

be greatly removed, by admitting two forts of alabaster, which are: essentially different from each other, calcareous and gypseous alabaster: to which fort any particular specimen. belongs may be determined by the easiest experiment. Dip a feather in the acid of fea falt, touch the specimen of alabaster with the wet feather, if an effervescence ensues, the alabaster is calcareous, it is of the nature of marble, and may be burned into lime; if no effervescence ensues, the alabaster is gypseous, it is of the nature of Plaster-of-Paris, and very different from every fort of marble. This fubstance is called in the north of England allplaster, being a corruption probably of alabaster, and it is also often called by the Latin appellation gypsum, especially by the T 3 French.

French. Gypsum was applied by the ancients to the very same purposes to which it is applied by us; they used it in architecture for the making of cielings, medallions, and cornices; and even the name of the person, who sirst invented the method of taking off the impression of a man's face in gypsum, has been preserved by Pliny*.

There are some sorts of alabaster which differ so widely in weight, both from the finest kinds of plaster-stone, and of calcareous stone, that I know not how they can properly

be

^{*} Usus gypsi in albariis, sigillis ædissciorum, et coronis gratissimus. Plin. Hist. Nat. L. xxxvi. s. 59. — Hominis autem imaginem gypso e facie ipsa primus omnium expressit Lysistratus. Id. L. xxxv. s. 54. where it is observed that the cast was improved by pouring wax into the gypsum mould.

be considered as being of the same nature with either of them. Mr. Cotes has fixed the weight of a cubic foot of alabaster at 1875 ounces*, and two other authors have reprefented it as weighing 1872 ounces +. I have tried feveral specimens of the finest Derbyshire plaster-stone, and find that a cubic foot of it weighs, at a medium, 2286 ounces; a cubic foot of the Derbyshire watricle, which is a fine calcareous stone, refembling alabafter in colour and transparency, weighs 2720 ounces.

Two substances when combined together in different ways, or in different proportions, may constitute a great variety of bodies differing much

^{*} Cote's Hydros.

Musichenbroek - Wallerius.

much from each other in external appearance, and fomewhat, probably, in their internal properties. We have an instance of this in the combination of the acid of vitriol with calcareous earth, for this combination constitutes a great many substances exceedingly different from each other in appearance. I will mention some of the most remarkable. (1) A folid fubstance not fo hard nor fo heavy as marble, nor fo capable of receiving a fine polish, but confifting of finer particles, and having a greater degree of transparency - Gypseous alabaster. (2) A Substance composed of larger particles than the preceding, and having a fealy or granulated texture -Plaster stone. (3) A substance whose parts, instead of being flat or granulated.

lated, lie in longitudinal fibres, like a parcel of needles, or a skein of thread - Striated gypsum. (4) A pellucid substance confisting of a number of transparent plates of a lozenge-like form, found in great plenty and perfection at Shotover-hill, near Oxford - Rhomboidal selenites. (5) Some take the lapis specularis, which the ancients used instead of glass, to have been composed, like all the preceding bodies, of the acid of vitriol and calcareous earth; whilft others look upon it as a species of tale, which differs from plaster-Itone in this, that it does not after being calcined and wetted with water fwell and concrete into a hard ftony fubstance. This lapis specularis came into use at Rome in the age of Se-

neca*; it was foon after its introduction applied not only to lighten apartments, but to protect fruit trees from the feverity of the weather +; and it is recorded to have been principally by its means, that the Emperor Tiberius was enabled to have cucumbers at his table during almost every month in the year t.

I be-

* Quædam nostrå demum prodiisse memoria scimus, ut speculariorum usum, perlucente testâ, claram transmittentium lucem. Sen. Ep. 90.

+ Pallida ne Cilicum timeant Pomaria brumam,

Mordeat & tenerum fortior aura nemus: Hibernis objecta notis specularia puros Admittunt soles, et sine fæce diem. Mar. L. viii. epig. 14. & 68.

1 Nihilo minus Specularibus integi debebunt ut etiam frigoribus serenis diebus tuto producantur ad solem. Hac ratione fere toto anno Tiberio Cæsari cucumis præbebatur. Colum. L. xi. c. 3.

I believe it is still used in some countries in the place of glass, and we certainly know that it was so used in the time of Agricola, for he mentions two churches in Saxony which were lighted by it *.

If the lapis specularis was a kind of transparent plaster-stone, it must have been subject to one inconvenience, it could not have long stood the action of the weather: for gypleous alabaster, plaster-stone, selenites, and all other combinations of the acid of vitriol with calcareous earth, are foluble in water, either wholly or in a great degree. These substances require, indeed, a greater proportion of water to dissolve them, than any other saline substances do, but they are, nevertheless, soluble in water.

I

^{*} Agric. de Natura Fos. L. v. p. 257.

I took fome very white plasterstone, and pounded it into a fine powder; I pennyweight of this powder was put into a pail, containing 10 quarts of water; the powder was entirely diffolved in it; from hence we learn, that this kind of plasterstone, is wholly soluble in water; the water was pump water of 48 degrees of heat. I thought that this quantity of water was perfectly faturated with 4 pennyweights, or 96 grains of the powder, and hence it seems as if fpring water, which is usually of the temperature of 48 degrees, would dissolve about one fourteen hundredth part of its weight of plasterstone. There are great beds of plaster-stone in the environs of Paris, and the hardness of the well water of that city is thought to arise from the par

particles of plaster-stone which are dissolved in it.

Agricola esteemed the lapis specularis to have been a species of plasterstone, and in speaking of it he remarks, that though it could bear, without being injured, the hear of fummer and the cold of winter, yet the largest masses of it were wasted by the rain *. I tied a lump of plaster-stone, weighing two ounces, to the end of a pair of scales, and kept it suspended in the middle of a pail of water for 48 hours, the water having been changed two or three times in the interval; at the end of the

^{*} Res gypso cognata lapis specularis — fert calores solis et hyemis frigora, sed imbrium adeo impatiens est, ut si vel magnæ ejus moles ipsis suerint expositæ corrumpantur. Agric. de Nat. Foss. L. v. Ed. Bas. 1546.

the experiment, it appeared, that the plaster-stone had lost one thirtieth of its weight.

There are many places in England, where plaster flone is gotten in great abundance, the principal of those which I have feen, are at Chelaston, a small village about four miles south from Derby, and at Beacon-Hill near Newark. They annually raise at Chelaston about 800 tons of plasterstone, which is fold upon the spot for 5 s. a ton. It is chiefly used for the making of floors in Derbyshire, Leicestershire, and Nottinghamshire: that which has a blueish cast is most esteemed for flooring; the very white pieces are fold to the potters; to the polishers of spar, who call it alabaster, (though they get their best sort of alabaster from Staffordshire;) and

to the plasterers. The plaster-stone before it is used, either for floors or cielings, is calcined; it loses in that operation, from 4 to 6 hundred weight in a ton; the loss, however, in the fame kind of stone, depends very much upon the degree of heat with which it is calcined. I calcined, in the same crucible, a piece of Derbyshire watricle, a piece of fine grained plaster stone, and a piece of the striated kind from Chelaston. The watricle lost after the rate of 8 c. 3 q. 17 lb. in a ton; the plaster-stone lost after the rate of 12 c. 0 q. 3 lb. and the striated kind after that of 10c. oq. 2lb. in a ton. When the stone is calcined, those parts of it which are exposed to the greatest heat, are fometimes melted, and they frequently acquire a yellowish cast,

and emit a fulphureous exhalation, and are in both cases thrown aside as useless. The flooring made from the stones, which are become sulphureous by calcination, is apt to rife in blifters; this proceeds from the plaster-stone having lost a portion of the vitriolic acid, which enters into its composition, and being thereby changed into a species of lime. They calcine the stone usually at night, that they may be the better able to observe when it becomes red hot, in which state they judge it to have received heat enough. After calcination they reduce it to a powder, by threshing it with slails, or grinding it in a mill; and when it is become of a due fineness, they mix it with a proper quantity of water, and spread it to the required thickness upon reeds.

reeds, where it immediately concretes into a folid floor: 30 hundred weight of the crude stone, will, when calcined, make 20 square yards of flooring of 21 inches in thickness. For preparing the stone, and shooting the floor, the Derbyshire masons charge od. a square yard; hence 20 square yards of plaster slooring, including the price of the stone at the pits, will cost 11. 2s. 6d. - The additional expence must be various, it depending upon the price of the conveyance of the crude stone, from the place where it is dug, to-the place where it is used. Plaster-stone, however, is found in fo many parts of the kingdom, and the inland navigations are become fo commodious, that plaster flooring might be introduced into many countries with a VOL. II. COM -

confiderable faving of expence; a circumstance especially to be attended to in the erection of Public Infirmaries, and Houses of Industry.

They have fawn out of the quarry at Chelaston, square blocks of a yard in breadth and thickness, and of two yards in length; and blocks of still greater dimensions have been raised at a place called Red-hills, in the county of Nottingham, about four miles from Chelaston. The stone from the red-hills is not so good for flooring, as that at Chelaston; it is, however, a very beautiful stone, Lord Scarsdale having gotten from thence those superb columns which adorn his hall at Kedleston. These columns are made of different blocks, from 2 or 3, to 6 or 8 feet in height, which are fo artfully cemented together, that they

they may be taken for one piece. The blocks are raifed out of the quarry, by being fawn to the proper. length on each fide, and to the depth requisite for the thickness of the column, the block still adhering, by its lower furface, to the quarry, is broken off from thence, by being raised on each side with levers. It is afterwards rounded into the proper cylindric form by the mallet and chisel, and polished by being rubbed with various kinds of stones, then with emery, and last of all with putty. If the veins of the separate blocks which are to compose the shaft of an alabaster column, of the kind we are speaking of, do not happen to fuit each other; in order to make the juncture less discernible, and to give a greater appearance IJ 2. of

of confistence to the whole column, small pieces are here and there cut out of the separate blocks, and others of a different colour inserted, and cemented by a mixture of rosin and bees-wax, tinged green, red, brown, yellow, according to the nature of the piece to be inserted.

Alabaster columns, though they are much easier to be wrought than marble, and when finely polished look very well, yet, I apprehend, their polish must be injured by a circumstance which does not affect either marble or calcareous alabaster. The atmosphere is always much charged with humidity, upon the breaking up of a frost, and in other states of the weather, so much water is discharged from the air, that marble, wain-

wainfcot, and other fubstances, upon which it fettles, are faid to fweat. Now the water which thus fettles on a gypsecus alabaster column, will disfolve part of the substance of the column, and as fome parts of the alabaster, are more soluble than others, the uniformity of its furface will be injured; and the part, moreover, of the alabafter which has been diffolyed, will, upon the evaporation of the water, either not adhere at all to the column, or it will adhere in fuch a way, as to render the polish less gloffy. But whether this account of the matter be admitted or not, the fact, I believe, of the polish of gypfeous alabafter being injured by moift weather, is not to be denied. The alabaster columns in the Egyptian Hall at Holkam, were dug from the quarries in Staffordshire, and the late Lord Leicester was at the trouble of contriving means to keep them dry in moist weather, lest their polish should be impaired by the action of the moisture.

They annually raise about 2000 tons of plaster-stone at the pits near Newark, it is sold on the spot at 5 s. 6 d. and at Gainsborough at 8 s. 6 d. a ton, from whence it is sent to London, and various other places.

It having been said, that plasterftone is a saline substance resulting
from an union of the acid of vitriol with a calcareous earth, the
reader may expect some proof of the
affertion. — Boil together pot-ash
and plaster-stone, and you will obtain
the same kind of salt, which would
arise from uniting the acid of vitriol
with

with pot-ash; and thence we conclude, that the acid of vitriol is one of the component parts of plaster-stone: that calcareous earth is the other, is evident from this consideration, that the earth, which remains after the acid of vitriol has been separated from the plaster-stone, effervesces with acids, and may be burned into lime.

Having faid fo much concerning gypfeous alabaster, which is an earthy falt resulting from an union of the acid of vitriol with a calcareous earth; it may not be improper to add a word or two concerning alum, which is an earthy salt, composed of the acid of vitriol and an argillaceous earth. The acid of vitriol when united with any earth, may be separated therefrom by a fixed alkali; and

if

if we pour into a folution of alum any fixed alkali, the earth of alum will be precipitated, and we shall obtain a falt, of the same kind, as would result from a direct combination of that alkali with the acid of vitriol; and thence it is inferred, that the acid of vitriol is one of the component parts of alum: upon examining the earth, which is precipitated by the alkali, it will be found to be very white, and very tenacious, and to be capable of being hardened in the fire; in short, it is one of the purest clays in nature: and thence it is concluded that an argillaceous earth is the other component part of alum. The constituent parts of alum may also be proved by its artificial composition, for though the vitriolic acid, when poured upon pipe-clay, does

does not feem to act upon it, yet if it be boiled with it, a folution of the clay in the acid takes place, and an alum may be obtained by flowly evaporating the folution.

Being one day engaged in evaporating something or other, from a faucer made of the Staffordshire yellow ware, I was furprifed to fee a white fubstance bubbling through a crack in the faucer; upon tasting it, I found it to be a falt; I collected a fufficient quantity of it, and when it was dissolved and crystallized, it appeared to be a perfect alum. The fire was a very hot one, and it was made of coal cinders, the faucer was placed on the bar of the grate, and the alum, I conceive, was formed from the sulphureous acid of the cinders uniting itself with the clay, which enters into the composition of the yellow ware. I have been informed by a very intelligent person, that the vapour which, in some places, escapes from the coal-pits which are on fire in Staffordshire, forms an alum whereever it meets with an argillaceous earth. This is very conformable to the manner of making alum on the Solfatara near Naples, where they place little heaps of argillaceous earths, or stones, over the crevices from which the fulphureous vapour issues, in order that they may collect a greater quantity of alum *.

In England we make alum from a black flaty substance, called *shale*, this substance is a clay, hardened into a stony consistence, and so much

im-

^{*} Lett. sur la Minera. par M. Ferber, French Trans. p. 261.

impregnated with bitumen, that it burns fomewhat like coal. We have feen, that coal emits, when it is in the state of a red hot cinder, a sulphureous acid: many other bitumens, probably, in the same state emit the fame acid, and the acid which is emitted from shale, during its calcination, uniting itself to the argillaceous earth of the shale, forms alum. About 120 tons of calcined shale, will make I ton of alum. The shale, after being calcined, is steeped in water, by which means the alum, which is formed during the calcination of the shale, is dissolved; this dissolved alum undergoes various operations, before it is formed into the alum of the shops. The greatest alum works, and, I believe, the only ones which now fubfift in the kingdom,

dom, are at Whitby; a few years ago there were fome in Lancashire; and alum might be made in many other parts; but Whitby is so conveniently situated for coal and water carriage, that alum can be there afforded at a cheaper rate, than in most other places, and it costs even there 9 or 10 l. a ton making.



E S S A Y VIII.

Of Pit-coal.

Took 96 ounces of Newcastle coal, and putting them into an earthen retort, distilled them with a fire gradually augmented till nothing more could be obtained from them. During the distillation, there was frequent occasion to give vent to an elastic vapour, which would otherways have burst the vessels employed in the operation. The weights of the

the liquid found in the receiver, and of the refiduum remaining in the retort, after the distillation was finished, were accurately taken, and are expressed in the following table.

Weight of Newcastle pit-coal distilled - - 96 ounces

Professor Newmann analysed by distillation, the best fort of the pit-coal found at Halle, in Germany. He used only 48 ounces in his analysis, but I have expressed the result of his operation, upon the supposition of his having used twice as much, or 96 ounces *.

Weight

[•] Newmann's Chem. by Lewis, p. 245.

Weight of the Halle pit-coal diftilled - - 96 ounces

Weights of the Products.

Lofs of weight $0\frac{1}{4}$ ounc.

Lofs of weight $0\frac{1}{4}$

Dr. Venel, of Montpellier analysed, by distillation, 64 ounces of the pitcoal of Alais, in Languedoc; supposing that instead of 64 he had used 96 ounces, the result of his analysis would have been expressed by the following numbers *:

Weight

Instructions sur l'Usage de la Houille. A. Avignon, 1775, p. 45.

Weight of Alais pit coal distilled - - 96 ounces

Weights of the Products. $\begin{cases} \text{Liquid} & -10\frac{1}{2} + \\ \text{Refiduum} & -84 \\ \text{Lofs of weight } 1\frac{1}{2} - \end{cases}$ ounces

96

M. Sage, of the Academy of Sciences at Paris, fays that he has distilled various specimens of pitcoal taken from different places, and that they generally yielded 2 ounces of liquid from 16 ounces of coal *, that is 12 ounces from 96; which is the same proportion as in the analysis of the Newcastle and Halle pitcoal. He does not mention the weights of the residuums, so that

^{*} Elémens de Mineralogie. A Paris, 1778, tome prem. p. 94.

the losses of weight, in his distillations, cannot be ascertained.

These several analyses correspond so nearly, with respect to the quantity of liquid procurable from different forts of coal, that they very much confirm one another; and make it probable, that we shall not be far from the truth in generally afferting, that pit-coal contains one-eighth part of its weight of liquid.

With respect to the nature of the liquid, it may be observed, that when poured out of the receiver, it is seen to consist of three different substances; (1) The middle part is an acid watery fluid, of a reddish colour, it seems as if it was loaded with oil, and it smells of volatile alkali; (2) On the surface of this watery fluid there floats a small porvol. II.

tion of oil, more or less liquid and transparent, according as the heat used in conducting the distillation has been less or greater; (3) At the bottom there is found a black thick tenacious oil, very much resembling tar. The two oils together amounted in the distillation of the Newcastle coal to four ounces, or one-third of the weight of the whole liquid; in the analysis of the Halle and Alais coals, as well as in the experiments of M. Sage, the two different forts of oils were observable, but they bore a greater proportion to the whole of the liquid, than in the Newcastle coal, amounting to one half of the weight of the liquid. This difference makes me suspect that I committed some error, in estimating the quantity of oil obtained from

from the distillation of Newcastle coal. It is probable, however, that the quantity of oil, separable from the same kind of coal, may be influenced, in some degree, by the manner of performing the operation; and there is, moreover, some reason to believe, that in different kinds of coal the quantities of oil may be very various; as we observe them to differ from each other both in their proneness to catch fire, and in their ability to support it: though it must be owned, that both these effects may as confiftently be explained, from the difference of the manner in which the oil may be combined with the other principles of the coal, as from the difference of its quantity.

The

The correspondence, with respect to the quantity of liquid obtained by the feveral distillations of English, German, and French pit-coal, would induce one to suppose that the experiments had been respectively made with great accuracy; but the great disparity, as to the quantity of the refidues remaining after the extraction of the liquid, feems to indicate the contrary; for it is greater, I apprehend, than can be accounted for from the different natures of the coals. The German and French analyses corroborate each other, and the reader may thence reasonably be disposed to question the truth of mine. He will permit me, however, to produce a testimony in its support, and which is, perhaps, the more to

be depended on, as I was not aware of it when the analysis was made.

Dr. Hales *, by distilling 158 grains of Newcastle coal, obtained 51 grains of air. From 96 ounces he would according to the fame proportion have obtained 30 ounces of air; now the difference between 28 ounces of some fort of matter or other which was loft during my distillation of 96 ounces of coal, and 30 ounces of air, which might have been obtained from the fame quantity of coal by Dr. Hales' method, is fo small, that it may eafily be accounted for from the different modes of operating, or from a flight difference in the qualities of the coals. Many naturalists have thought that pit-coal has been

pro-

^{*} Vegetab. Stat.

produced from vegetables, and especially from forests of resinous woods, which have been buried in the bowels of the earth; without entering into all the reasons on which this opinion is founded, I will lay before the reader an account of the products obtainable from different woods by distillation.

The woods which I distilled were heart of Oak, Box, Mahogany, and Sallow. They were all dry and old, and were cut into small pieces, about half an inch square, before they were put into the earthen retort. The annexed table shews, at one view, the results of the respective distillations.

Weight distilled, 96 oz. 96 96	
Weight diffilled, 90 out 1 90 1 90	96
Liquid - $37\frac{1}{4}$ $61\frac{1}{2}$ $33\frac{1}{2}$ 4	18
	20 1
Lofs of weight 28 3 8 35 2	$27\frac{1}{2}$
96 96 96 9	96

The liquids separable from woods by distillation consist partly of oil, but principally of water impregnated with an acid, from which also a volatile alkali may be difengaged. The oil varies in quantity according to the nature of the wood, the hardest woods, and the hardest parts of the fame wood abounding most in oil; thus both oak and box contained, in the same weight of the wood, more oil than fallow did. That part of the oil which is first separated from the wood is so light as to float

X 4

upon

upon water, and of a yellowish colour; its quantity, however, is but small, compared with that of the thick, black, heavy oil, which follows it. It appears from this account, that the quality of the liquid separable from wood by distillation, is wholly the same with that of the liquid separable from pit coal by the same means.

The matter which is lost during the distillation of both wood and pit-coal has been called air, and it certainly has one, at least, of the most distinguishing properties of air—permanent elasticity, for bladders may be inflated with it as with common air. It does not begin to be separated from either wood or coal till the lighter of the two oils begins to appear; it then rushes out with great

great violence, and unless a proper vent be given to it, the strongest vessels will be burst by it.

In distilling heart of oak, during the course of chemical lectures which I read in the university of Cambridge, in the year 1767, I remarked to the audience, that the air which issued with great violence from the oak was inflammable, not only at its first exit from the distilling vessel, but after it had been made to pass through two high bended glass tubes, and three large veffels of water. I at first supposed the inflammability to proceed from fome oily particles which had accompanied the air, and which I thought would foon be condensed by the cold, though they had not been been condensed in passing through the water; but upon repeating the experiment, and collecting the air in bladders, I found that it retained its inflammability a long time, and burned like the air separable from some metals by solution in acids.

From the refearches which have been lately made into this subject, it is now believed, that this kind of air may be separated from all vegetable, animal, and inflammable mineral substances by distillation; and the common burning of wood, coal, paper, pitch, oil, and other combustible bodies, is attributed to this air, which being separated from the body by the heat, and inflamed by the contact of the fire, continues to burn as long as the body continues

to afford a proper supply of it. Inflammable air, considered in this view, bears a great resemblance to what the chemists have hitherto understood by their phlogisten, or food of fire.

Distillation is not the only means of separating inflammable air from vegetable and animal substances, it is found to be produced by putrefaction. Stagnant waters, whose bortoms are covered with putrefying vegetables, yield an inflammable air; the Thames water, in becoming putrid, yields an inflammable air: and the fame observation may, probably, be true of other river waters which are subject to putrefaction. An inflammable air has been observed also in fwampy grounds, in cellars, and in privies. There are many instances recorded,

corded, of a vapour issuing from the stomachs of dead persons, which took fire on the approach of a candle *; the matter producing that vapour could not, probably, become putrid enough in the stomach, to generate an inslammable vapour, whilst the persons were alive; for Van Helmont has remarked, that the air discharged from the stomach by eructation, is not inslammable, but that it becomes so in the lower intestines †.

From

^{*} Collect. Acad. Tom. III. Part. Etrang. p. 16.

[†] Ructus sive slatus originalis in stomacho, prout et slatus Ilei extinguant slammam candelæ. Stercoreus autem slatus, qui in ultimis formatur intestinis, atque per anum erumpit, transmissus, per slammam candelæ transvolando accenditur, ac slammam diversicolorem, iridis instar exprimit. Van Helmont, Oper. p. 405.

From heart of oak moderately dried Dr. Hales got one third of the weight of the oak of the air here spoken of; this proportion sufficiently agrees with the quantity which was lost during the forementioned distillation of oak.

A cubic foot of dry box-wood weighs, according to Mr. Cotes' table of specific gravities, 1030 ounces; hence, supposing that 96 ounces of fuch wood had only given 61 ounces of liquid, it may appear by an eafy calculation, that a cubic foot of dry box-wood contains above 5 gallons of liquid; supposing the liquid to be no heavier than water; and if we admit the oil and the acid, when concentered, to amount to two quarts, the other 18 quarts may be looked upon as pure water; nay, the quantity tity of water may be confidered as amounting to almost the whole of the liquid, since both acids and oils principally consist of water.

A cubic foot of fallow weighs, according to Muschenbroek, 585 ounces, and supposing that 96 ounces of such wood would yield by distillation 48 ounces of liquid, then a cubic foot would contain about 9 quarts of liquid, which is not half so much as an equal bulk of box-wood contains:

I put the matter in these different lights, in order to excite those who have leisure to make similar inquiries, for it is undoubtedly a very wonderful thing, that such large quantities of water, and air, should be combined with the earth of wood, by such a peculiar bond of union as

to remain for ages, without losing any of their distinguishing properties. And here I am sensible is great room for many phylical investigations. - Are the denfest woods the most abundant in air and water? Is the air generated by the process of distillation, or only disengaged from the wood, into the composition of which it had entered, together with water, by vegetation? Have the inflammable airs, separable from different woods by distillation, the same specific gravity, and the same degree of inflammability? or is the inflammability influenced by the nature of the oil contained in the wood? How long will a given quantity of air retain its inflammability? Does it lose it in consequence of the precipitation of some oily particles, which are disfolved

folved in it, when it is first distilled? As no particle of matter can be annihilated, what becomes of the inflammable air, after it has been inflamed? is it reduced to an unelastic earth, or does it still exist under the form of an uninflammable elastic fluid? whence is it that no air begins to be distilled, till the most volatile part of the oil begins to be separated from the wood? Fraxinella is a very odorous plant; when in full bloffom, the air which furrounds it in a still night, may be inflamed by the approach of a lighted candle; does this inflammability proceed from an inflammable air, which is exhaled by the plant, or from some of the finer particles of the oil of the plant, being diffolved in the common air of the atmosphere? Whence is it that the oils distilled from

from wood, during the fame operation, are of different colours, confistences, and specific gravities? Does this variety depend upon the loss of the air, or upon the quantity of the acid mixed with the oils? Are the oils and acids of different woods distinguishable from one another, by any specific differences, or do they only differ from one another as to more or less? Supposing the acids obtained from different woods to be of the same fort, and to be purified to the greatest degree, what kind of falts would they form, when united with alkalies, earths, and metallic substances? In what manner are the relative proportions of the water, acid, oils, air and residuum separable. from wood by distillation, influenced VOL. II. byby the operation being conducted with a quick or a flow fire?

These, and a great many similar questions, might be resolved with the greatest accuracy, and our knowledge be thereby much advanced. But it falls to the lot of sew to be able to build commodious Elaboratories, to purchase suitable instruments, to supply proper materials, and to maintain operators to execute the infinite variety of experiments, which might be devised, for the regular and systematic improvement of every branch of Chemistry.

The residue remaining in the retort, after the distillation of the wood, is a perfect charcoal, and that which remains after the distillation of pitcoal, is a light spungy mass, in appearance, pearance, and, indeed, in quality, refembling a substance prepared from pit-coal, as an article of trade, and which is usually called coak or cinder.

At Newcastle, 24 barrows of coals produce generally but 18 barrows of cinders, and the price of a bushel, or of any other measure of cinders, is commonly one third more than the price of the same measure of coals *. At Cambridge, on the contrary, where great quantities of cinders are prepared for the drying of malt in the town and neighbouring villages, the price of cinders and of coals is the fame. From this circumstance it might probably be inferred, that the coal was increased in bulk by being converted into cinder, otherwise the Merchant would have no compenfation

Newmann's Chem. by Lewis, p. 245.

tion for the expence attending the process. Upon examining the fact, I found that in one instance 30 bushels of coal gave 39 bushels of cinders, and in another 28 bushels of coal gave 36 bushels of cinders. The quantity of cinders, being estimated by measure, depends much upon the cinders being in rounder lumps thanthe coals; and the real quantity, estimated by weight, depends greatly upon the degree of heat to which the cinder has been exposed. I take the difference in the bulks of the Newcastle and Cambridge cinder, procurable from an equal quantity of coals, to proceed from the different degrees of heat to which they are exposed: the Cambridge coak ovens being drawn once in 24 hours, and those.

those at Newcastle only once in 48 hours, or thereabouts.

In order to fee what effect a longer continuation of fire, would have upon the ordinary Cambridge cinder, I took a large piece, and, having broken it, threw one part of it into the middle of a fierce cinder fire, employed in the drying of malt. This part became red hot in less than ten minutes; after it had continued in that situation for above two hours, I took it out, and when it was cold I found it considerably wasted in bulk, but it appeared to be harder and blacker than the other part of the fame piece, and its parts were certainly more condensed; for I found that a cubic foot of the ordinary cinder weighed 1090 ounces, and a cubic foot of that which had been exposed

Y 3

to the fire for two hours, weighed 1208 ounces. This cinder was, probably, as much changed in the space of two hours, by the strong draught of the fire in which it was put, as it would have been by a much longer continuance in the coak oven, where the draught of air is very little: and from this experiment it may be inferred, that the quantity of cinders. procurable from a definite quantity of coals, depends very much upon. the strength and continuance of the fire, fince the cinder after it is fully formed, is not only wasted in part by a longer continuance in the oven, but the part which remains is rendered more dense, and upon both accounts the quantity, estimated by measure, is lessened. This observation may be of use to those, who are employed in

pre-

preparing cinder for sale; and upon inquiry I find, that the quantity of cinder procured from the same quantity of coal is very variable; when the operation has been longer, or the heat greater than usual, instead of gaining of six or eight bushels from every thirty bushels of coal, they sometimes are not able to get even 30 bushels of cinder.

The confumption of charcoal in fluxing iron from its ores, and in manufacturing it into bar iron is fo very confiderable, and the price of charcoal, from the great scarcity of underwood in this kingdom, is so great, that many attempts have been made to substitute in this business charred pit coal in the room of charcoal. These attempts have in part succeeded, and iron is now very

Y. 4

gene--

generally extracted from its ore by fires made with coak. But the iron thus procured is very fragile and coarse, and cannot, without great difficulty, be rendered as malleable as that which is fluxed with charcoal; it may answer nearly as well for casting, but it cannot be made into good bar iron by any art hitherto known. Hence it became an object worthy the contemplation of the fociety for the encouragement of arts, manufactures, and commerce, to propose premiums for the making pigiron, and converting pig iron into bar iron with coak. The pigs and bars were required to be as good as those made with charcoal, but the premiums, though proposed from 1762 to 1766 were never claimed *. Those who are

^{*} Memoirs of Agriculture, Vol. I. p. 2200

are interested in iron works, have motives, more prevalent than the fociety's premiums, to induce them to perfect the art of fmelting by means of charred pit-coal; and it may not be an useless hint to them, to try the effect of coak, which has undergone different degrees of heat. I ordered a ton of coals to be put into a coak oven, and when it was in the usual way converted into a cinder, I found that it weighed in hundred weight; had it stayed longer in the oven it would have been reduced further, and it may deserve to be inquired, whether there is not a definite weight to which any given quantity of coals ought to be reduced, in order to produce the best posible coak for the fluxing of iron ore.

ore. The *alais pit-coal is faid tolose half of its weight by being reduced to coak, whilst another fort of coal lost only 35 parts in an hundred: this diversity may depend partly on the nature of the coal, but principally, I conceive, on the degree and continuance of the fire used in the preparation of the coak.

What shall I say further of coals, except I tell you of one Becher, in King Charles the Second's time, who pretended to make pitch and tar from them, but I think his project came to nothing †." This is Houghton's observation concerning a project of one of the greatest chemists that ever lived. Whatever sate his project met with in his own

age,

^{*}Instruc. sur l'Usage de la Houille, p. 81. † Houghton's Collec. Vol. II. No. 242.

age, it has been realized in ours; for a kind of tar has for several years last past been prepared from coal in the bishopric of Liege, and in other parts of Germany; we also make considerable quantities in England, especially near Broseley, and at Bristol*; a person at Bristol having obtained a patent for making tar from pit-coal, the condition of which, if I am rightly informed, is, that every person who undertakes to pro-

cure

^{*} In the Philo. Trans. No. 228, year 1697, there is mention made of pitch and tar being then separated at Broseley, in Shrop-shire, from the black bituminous stone which lies over the coal. It was separated, partly by boiling the stone, and partly by distilling it—the present method of obtaining pitch from pit-coal is a great improvement upon the former practice.

cure tar from pit-coal must pay a shilling a barrel to the patentee.

The method of making tar is thus described by Newmann. - " Tar is prepared in different parts of Germany, Norway, Sweden, &c. from the pine and the fir-trees, and in fome places from the larch and the terebinth. The wood is inclosed in a large oven to the quantity of ten or more loads at a time: this flands within another oven called the mantle, the space betwixt them receiving the fire. From the bottom of the inner oven runs a gutter, by which the tar is conveyed off in proportion as it melts out of the wood *." This process is a kind of distillation, in which the inner oven repre-

Mewmann's Chem. p. 288.

represents the body of the retort, and the gutter its neck. The fluid parts of refinous woods are probably capable of being melted out of them with a less degree of heat than what is requifite for the distillation of coal, yet the process for procuring tar, here mentioned, might be applied with a few alterations to the obtaining the thick oil of coals. There would in this plan be no loss of fuel, the coal contained in the inner oven would be converted into one of the most valuable kinds of coak, and the fire between the ovens would afford a cinder as good as the common cinder.

In the bishopric of Liege the coal is distilled in a kind of still composed of two large cast-iron pots. In England the coal is put into ovens which

which are heated by fires lighted under their bottoms, and the liquid matter is forced through an iron pipe inserted into the top of the oven, and which communicates with proper condensing vessels. As the pitchy oil is very heavy, the distillation, I think, would be most advantageously performed by making the fire on the top of the oven containing the coal, fo that the liquid matter might be made to descend through a pipe inferted into the bottom of the oven, and communicating with proper receivers.

In the great works they obtain the very fame substances which we got from the analysis of coal—a corrosive watery liquor, and two forts of oil. The two oils are put into an iron still, in order to their being

being further purified from the watery liquor with which they are mixed; 6 barrels of this oily matter produce about 5 barrels of oil of a thicker confistence; of the oil thus thickened one part is lighter than the other, the lighter part is drawn off from the other, and is not at present applied to any use; the thicker part is used as tar, for the paying the sides and bottoms of ships, but it is not found to answer fo well as tar either for cordage, or to mix with oakum.

Those who are interested in the preparation of coak would do well to remember, that every 96 ounces of coal would furnish 4 ounces at the least of oil, probably 6 ounces might be obtained, but if we put

the product so low as 5 ounces from 100, and suppose a coak oven to work off only 100 tons of coal in a year, there would be a saving of 5 tons of oil, which would yield above 4 tons of tar: the requisite alteration in the structure of the coak ovens, so as to make them a kind of distilling vessels, might be made at a very trifling expence.

It has been before observed, that wood and pit-coal wholly resemble each other in the products which they yield by distillation, and as the oil from pit-coal is found to answer the purpose of tar, it might surely be a matter worthy the consideration of those who are engaged in the burning of wood into charcoal, to contrive means which might easily be

be done, of faving all the oil which is feparated from the wood during; that operation.

The acid liquor which is procured from pit-coal, when it is distilled for tar, is at present thrown away, as I have been informed by a person who is much engaged in this business. Without entering into the dispute concerning the origin of the vegetable fixed alkali, we may observe, that it is generally obtained from the combustion of the vegetable, and there is reason to think, that the acid of the vegetable contributes in some way or other towards its production: thus the concrete acid of tartar yields, by being burned, a great quantity of fixed alkali. Is it wholly improbable, that the acid liquor which is feparated from the coal by distillation, Z might VOL. II.

by being boiled down and calcined, either by itself, or in conjunction with straw, charcoal dust, or any other substance, containing the inflammable principle?

The making of fixed alkali in Great Britain, is a matter of fuch great national concern, that the commercial reader will excuse me, if I give another hint or two upon the subject. Might not pot-ash be prepared in the cyder countries, from the calcination of the acid earthy epulp, which remains after the juice s is pressed out from the apple? The brewery grains are at present applied to some use, would they not, if suffered to turn four, yield more profit by being calcined for pot-ash? The brewery hops, which are impregnated a

with the fweet wort, would probably turn four, and as they are thrown away as useless, might it not be adviseable to see whether they would not yield pot-ash by calcination? The lees and refuse from the making of vinegar, might be tried for the fame purpose; and so might all the water which is impregnated with the washings of the floors, vessels, &c. in which any vegetable liquor is fermented, either into ale or vinegar. I remember having evaporated, feveral years ago, a large quantity of horses' urine, with a view of seeing whether it would yield by crystallization, the fame kind of phosphoric falt, which may be obtained from human urine; I could not procure any falt of that kind from it; but, when it was evaporated to dryness,

it

it yielded, even without calcination, a great deal of fixed alkali. The urine of animals, which feed upon vegetables, arises from the juices of the vegetables, which have been changed in some degree by the organs of digestion; may not a similar change take place by putrefaction? and may not the putrefaction of vegetable juices be increased, by a small admixture of common falt? and would not the quantity of alkali be thereby increased? Is it not possible to decompose common falt, by mixing it with vegetables in a state of putrefaction? If the acid of fait could by any cheap means be separated from its alkaline basis, it would undoubtedly be the interest of government to exempt from the falt duty, all fuch. rock or fea falt, as should be converted

werted into a fixed alkali; for by that means, all the money might be kept in the kingdom, which is now fent out of it, for the purchase of barilla, and other sorts of fixed alkali.

It has, with fome men, been a subject of apprehension, lest all the coal-pits in England should soon become exhausted. The quantity of coal which is annually raised, is certainly very great; and as coal is not found to grow again, the time must come, when it will all be confumed. That æra, however, is certainly at a great distance, since in those countries where coal is found, they are constantly opening fresh pits, and may for centuries to come continue to open more; and coal may, probably, be discovered in many counties, where none is extracted at

Z 3

present. It will enable the reader to form some notion of the great excavations, which are annually made in this Island from the digging of coal, if we calculate the extent of that which is made in one year, in consequence of the coal which is imported into London. The following account may be relied on.

An account of coals imported into the port of London, in ten years, ending at Christmas 1779.

Christmas 1770 615,330 chalders. 1771 - -694,003 725,008 1772 - -624,781 1773 -1774 - - 623,727 1775 - - 672,786 1776 - - 700,207 - - 697,435 1777 - - 647,361 1778 - - 587,895 1779 Annual average 658,853 No

No accounts are kept at the Cuftom House, distinguishing the importation from Newcastle, Sunderland, Blythe, Hartlepool, &c. or from the feveral parts in Scotland and Wales, the Crown revenue not being affected thereby. The duty is 8s. per chalder of 36 Winchester bushels, on all coals fold by measure, and 6s. 4d. per ton, on fuch as are fold by weight. It appears from the preceding account, that in the year 1777, there were imported into the port of London 697,435 chalders, and we learn from another authority*, that in the same year there were imported from Newcastle and Sunderland alone 692,0933 chalders; by comparing these numbers, we may observe how small a portion of the

^{*} Ann, Reg. 1777, Ch. 161.

the coal confumed in London, is brought from any other quarter.

A chalder of coals, Newcastle measure, is allowed by Act of Parliament * to weigh 53 hundred weight: and as 8 Newcastle chalders are equal to 15 London chalders, reckoning 36 Winchester bushels to the London chalder, it follows, that a chalder of coals, London measure, is equal to a little more than 28 hundred weight. But supposing 28 hundred weight to be the weight of a London chalder, then as the medium quantity of coal annually imported into London is 658,853 chalders, it may be collected, that there are annually imported 922,394 tons.

The following table expresses the

.re-

^{6 &}amp; 7 W. & M. III. c. 10. f. 2.

relative weights of a few different forts of coals.

Weight of a cubic foot of

O	
Welsh coal	1396 ounces avoir.
Yorkshire stone-coal	1307 —
Lancash. cannel-coal	1273 —
Newcastle upon Tyne	1271
* Staffordshire coal	1241 —
† Coal de Graissesac	1371 —
‡ Coal des Carmaux	1333 —
‡ Coal d' Alais -	1500
B/adium waish	2006 0000000000000000000000000000000000
Medium weight	1336 ounces avoir.

The Welsh coal was of that kind which burns without giving any smoke, they mix it here with cinder for the drying of malt. The Yorkshire stone coal was taken from a pit

near

^{*} Philof. Trans. No. 169.

[†] The weights of the three French coals were calculated from experiments mentioned in Instruct. fur l'Usage de Houille, p. 2.

near Wakefield, and is part of the stratum, which lies at the bottom of the black coal. The Cannel coal was from Wigan in Lancashire: this coal is commonly used by the country people to work by in winter nights, instead of candles, and its name has been probably derived from its use, candles being called in the dialect of the northern counties, cannels.

The Newcastle coal was of a kind which is much esteemed at Cambridge, and which is called Old Ducks. The medium weight of a cubic foot of these several coals being 1336 avoirdupois ounces, a cubic yard or 27 cubic feet of coal, will weigh 2254½ avoirdupois pounds; there are 2240 such pounds in a ton, hence we may say in general, that a cubic yard

of pit-coal weighs a ton; fome forts of coal weigh a few pounds more, and other, a few pounds less than a ton. From what has been before observed concerning the quantity of coal annually imported into London, we may now conclude that 922,394 cubic yards of coal are annually dug out of the earth for the supply of the London market. This quantity of coal, if spread to the thickness of an inch, would cover an area of above 10 square miles; and no doubt the confumption of so large a quantity contributes very much both to the daily dirtiness of the streets of London, and to that elevation of foil-which is fufficiently obvious in the city and its environs, when distant periods of time are compared together.

The

The weight of a London chalder of coals is here put equal to 28 hundred weight, upon the supposition of 8 Newcastle chalders being equal to 15 London chalders. Upon weighing a bushel of the middle sized, large, and small old ducks at Cambridge, I found the weights to be

Middle fized - 74Large coal - 76Small coal - 80Medium - $76\frac{2}{3}$

This medium does not give quite 25 hundred weight to a chalder. I found, by weighing coals at another warehouse in Cambridge, that 30 bushels made a ton, which is 74 ? pounds to a bushel.

It is not certainly known how long coal has been dug in great Britain; Britain; the first fort of fuel which all nations used was probably wood, and as that grew scarce men began to fearch into the bowels of the earth for fomething to fupply its place. We have good reason to believe that the Newcastie coal pits were wrought in the time of the Romans, for coal cinders have been found at the bottom of the foundation of a city built by the Romans in that country *, but whether they were not wrought by the Britons before the Roman invasion, is a question which cannot, perhaps, be positively decided either way.

Anderson, in his history of commerce, fixes the introduction of Newcastle coal into London at so early a period as the year 1305; and mentions

^{*} Wallis' Hist. of Northumberland.

mentions a complaint of the nobility and gentry, which was preferred to the King against the use of sea coal, as a public nuisance. A fimilar prejudice prevails at this day, among those who have not been accustomed to pit-coal fires. The great Hoffman had given it as his opinion, that the peripneumony, the dry asthma, and the consumption were common maladies amongst the inhabitants of Liege and London, and that they were occasioned by the great use of pit-coal in those places. M. Morand, in 1769, was at the trouble to inquire into this matter, and it appears from the attestations of the College of Physicians in London; of the Faculty of Medicine at Paris; of the physicians at Liege, at Lyons, and other places,

that the opinion concerning the peculiar infalubrity of pit-coal fires is utterly without foundation.

It has been remarked that coal, in being distilled, yields near is of its weight of air; in being confumed by burning, it yields a great deal more; for both the refidue remaining in the retort, and the oil obtained by distillation, yield much air during combustion. I do not think that it would be an extravagant supposition, if we should say, that the 922,394 tons of coal which are annually confumed, dispersed into the atmosphere incumbent over London, 500000 tons of air; and this quantity may, probably, be about i of the whole quantity of air, which is respired by the inhabitants of London in the course of a year. Hence, Hence, though it should be granted that the air from coal, is not more unwholesome than that which is separated from any other kind of suel, yet the vast quantity of it with which the common air over great cities is daily infected, may contribute something to the rendering them, what they have been justly called, the GRAVES of mankind.

END OF VOL. II.





